



**Roadside Safety  
Pooled Fund**



**Texas A&M  
Transportation  
Institute**  
Proving Ground

---

**Test Report No. 612061-08-01**  
**Test Report Date: January 2021**

**MASH TL-3 EVALUATION OF MODIFIED MERRITT PARKWAY  
GUIDERAIL WITH NO CURB**

by

Chiara Silvestri Dobrovolny, Ph.D.  
Research Scientist

Wanda L. Menges  
Research Specialist

William Schroeder  
Research Engineering Associate

and

Darrell L. Kuhn, P.E.  
Research Specialist



Contract No.: T4541-DF

Test Nos.: 612061-03-1 and 612061-03-1

Test Dates: 2020-12-17 and 2020-10-12

Sponsored by

**Roadside Safety Pooled Fund**

---

**TEXAS A&M TRANSPORTATION INSTITUTE PROVING GROUND**

Mailing Address:  
Roadside Safety & Physical Security  
Texas A&M University System  
3135 TAMU  
College Station, TX 77843-3135

Located at:  
Texas A&M University System RELLIS Campus  
Building 7091  
1254 Avenue A  
Bryan, TX 77807



## DISCLAIMER

The contents of this report reflect the views of the authors, who are solely responsible for the facts and accuracy of the data and the opinions, findings, and conclusions presented herein. The contents do not necessarily reflect the official views or policies of the Roadside Safety Pooled Fund, The Texas A&M University System, or the Texas A&M Transportation Institute (TTI). This report does not constitute a standard, specification, or regulation. In addition, the above listed agencies/companies assume no liability for its contents or use thereof. The names of specific products or manufacturers listed herein do not imply endorsement of those products or manufacturers.

The results reported herein apply only to the article tested. The full-scale crash tests were performed according to TTI Proving Ground quality procedures and *Manual for Assessing Safety Hardware* guidelines and standards.

The Proving Ground Laboratory within TTI's Roadside Safety and Physical Security Division ("TTI Lab") strives for accuracy and completeness in its crash test reports. On rare occasions, unintentional or inadvertent clerical errors, technical errors, omissions, oversights, or misunderstandings (collectively referred to as "errors") may occur and may not be identified for corrective action prior to the final report being published and issued. If, and when, the TTI Lab discovers an error in a published and issued final report, the TTI Lab shall promptly disclose such error to the Roadside Safety Pooled Fund, and both parties shall endeavor in good faith to resolve this situation. The TTI Lab will be responsible for correcting the error that occurred in the report, which may be in the form of errata, amendment, replacement sections, or up to and including full reissuance of the report. The cost of correcting an error in the report shall be borne by the TTI Lab. Any such errors or inadvertent delays that occur in connection with the performance of the related testing contract shall not constitute a breach of the testing contract.

**THE TTI LAB SHALL NOT BE LIABLE FOR ANY INDIRECT, CONSEQUENTIAL, PUNITIVE, OR OTHER DAMAGES SUFFERED BY THE ROADSIDE SAFETY POOLED FUND OR ANY OTHER PERSON OR ENTITY, WHETHER SUCH LIABILITY IS BASED, OR CLAIMED TO BE BASED, UPON ANY NEGLIGENT ACT, OMISSION, ERROR, CORRECTION OF ERROR, DELAY, OR BREACH OF AN OBLIGATION BY THE TTI LAB.**



1. Report No.		2. Government Accession No.		3. Recipient's Catalog No.	
4. Title and Subtitle <b>MASH TL-3 EVALUATION OF MERRITT PARKWAY GUIDERAIL WITH 4-INCH CURB</b>				5. Report Date <b>December 2020</b>	
				6. Performing Organization Code	
7. Author(s) <b>Chiara S. Dobrovolny, Wanda L. Menges, William Schroeder, and Darrell L. Kuhn</b>				8. Performing Organization Report No. <b>Test Report No. 612061-08-01</b>	
9. Performing Organization Name and Address <b>Texas A&amp;M Transportation Institute Proving Ground 3135 TAMU College Station, Texas 77843-3135</b>				10. Work Unit No. (TRAVIS)	
				11. Contract or Grant No. <b>T4541-DF</b>	
12. Sponsoring Agency Name and Address <b>Roadside Safety Pooled Fund Washington State Department of Transportation Transportation Building, MS: 47372 Olympia, Washington 98504-7372</b>				13. Type of Report and Period Covered <b>Technical Report: September 2018-December 2020</b>	
				14. Sponsoring Agency Code	
15. Supplementary Notes <b>Project Title: MASH Full Scale Crash Testing and Evaluation of the Merritt Parkway Guiderail Name of Contacting Representative: David Kilpatrick, State of Connecticut Department of Transportation</b>					
16. Abstract  <p>With the adoption of the AASHTO/FHWA Joint Implementation Agreement for <i>MASH</i> in 2016, specific implementation dates were defined to determine crashworthiness of roadside safety systems to be implemented on projects on the NHS using the 2016 edition of <i>MASH</i>. CTDOT was interested in including this guardrail system within its standards as an available roadside safety hardware. However, prior to adding this system to the CTDOT standards, it was necessary to have a <i>MASH</i> compliant system. CTDOT proposes to full-scale crash test and evaluate the Merritt Parkway Guiderail system performance in accordance to the guidelines specified in the 2016 edition of <i>MASH</i>.</p> <p>The Modified Merritt Parkway Guiderail with 4-inch curb met the performance criteria for <i>MASH</i> TL-3 longitudinal barriers, and the Merritt Parkway Guiderail Transition met the performance criteria for <i>MASH</i> TL-3 transitions,</p>					
17. Key Words <b>Guiderail, guardrail, longitudinal barrier, transition, steel post, curb, curbless, timber rail, crash testing, roadside safety</b>			18. Distribution Statement <b>Copyrighted. Not to be copied or reprinted without consent from the <a href="#">Roadside Safety Pooled Fund</a>.</b>		
19. Security Classif. (of this report) <b>Unclassified</b>		20. Security Classif. (of this page) <b>Unclassified</b>		21. No. of Pages <b>310</b>	22. Price

## SI\* (MODERN METRIC) CONVERSION FACTORS

### APPROXIMATE CONVERSIONS TO SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
<b>LENGTH</b>				
in	inches	25.4	millimeters	mm
ft	feet	0.305	meters	m
yd	yards	0.914	meters	m
mi	miles	1.61	kilometers	km
<b>AREA</b>				
in <sup>2</sup>	square inches	645.2	square millimeters	mm <sup>2</sup>
ft <sup>2</sup>	square feet	0.093	square meters	m <sup>2</sup>
yd <sup>2</sup>	square yards	0.836	square meters	m <sup>2</sup>
ac	acres	0.405	hectares	ha
mi <sup>2</sup>	square miles	2.59	square kilometers	km <sup>2</sup>
<b>VOLUME</b>				
fl oz	fluid ounces	29.57	milliliters	mL
gal	gallons	3.785	liters	L
ft <sup>3</sup>	cubic feet	0.028	cubic meters	m <sup>3</sup>
yd <sup>3</sup>	cubic yards	0.765	cubic meters	m <sup>3</sup>
NOTE: volumes greater than 1000L shall be shown in m <sup>3</sup>				
<b>MASS</b>				
oz	ounces	28.35	grams	g
lb	pounds	0.454	kilograms	kg
T	short tons (2000 lb)	0.907	megagrams (or metric ton")	Mg (or "t")
<b>TEMPERATURE (exact degrees)</b>				
°F	Fahrenheit	5(F-32)/9 or (F-32)/1.8	Celsius	°C

### FORCE and PRESSURE or STRESS

lbf	poundforce	4.45	newtons	N
lbf/in <sup>2</sup>	poundforce per square inch	6.89	kilopascals	kPa

### APPROXIMATE CONVERSIONS FROM SI UNITS

Symbol	When You Know	Multiply By	To Find	Symbol
<b>LENGTH</b>				
mm	millimeters	0.039	inches	in
m	meters	3.28	feet	ft
m	meters	1.09	yards	yd
km	kilometers	0.621	miles	mi
<b>AREA</b>				
mm <sup>2</sup>	square millimeters	0.0016	square inches	in <sup>2</sup>
m <sup>2</sup>	square meters	10.764	square feet	ft <sup>2</sup>
m <sup>2</sup>	square meters	1.195	square yards	yd <sup>2</sup>
ha	hectares	2.47	acres	ac
km <sup>2</sup>	Square kilometers	0.386	square miles	mi <sup>2</sup>
<b>VOLUME</b>				
mL	milliliters	0.034	fluid ounces	oz
L	liters	0.264	gallons	gal
m <sup>3</sup>	cubic meters	35.314	cubic feet	ft <sup>3</sup>
m <sup>3</sup>	cubic meters	1.307	cubic yards	yd <sup>3</sup>
<b>MASS</b>				
g	grams	0.035	ounces	oz
kg	kilograms	2.202	pounds	lb
Mg (or "t")	megagrams (or "metric ton")	1.103	short tons (2000lb)	T
<b>TEMPERATURE (exact degrees)</b>				
°C	Celsius	1.8C+32	Fahrenheit	°F
<b>FORCE and PRESSURE or STRESS</b>				
N	newtons	0.225	poundforce	lbf
kPa	kilopascals	0.145	poundforce per square inch	lb/in <sup>2</sup>

\*SI is the symbol for the International System of Units

## ACKNOWLEDGMENTS

This research project was performed under a pooled fund program between the following States and Agencies. The authors acknowledge and appreciate their guidance and assistance.

### Roadside Safety Research Pooled Fund Committee

Revised February 2020

---

#### ALABAMA

**Stanley (Stan) C. Biddick, P.E.**

Assistant State Design Engineer  
Design Bureau, Final Design Division  
Alabama Dept. of Transportation  
1409 Coliseum Boulevard, T-205  
Montgomery, AL 36110  
(334) 242-6833  
[biddicks@dot.state.al.us](mailto:biddicks@dot.state.al.us)

**Steven E. Walker**

Alabama Dept. of Transportation  
(334) 242-6488  
[walkers@dot.state.al.us](mailto:walkers@dot.state.al.us)

#### ALASKA

**Jeff C. Jeffers, P.E.**

Statewide Standard Specifications  
Alaska Depart. of Transportation & Public  
Facilities  
3132 Channel Drive  
P.O. Box 112500  
Juneau, AK 99811-2500  
(907) 465-8962  
[Jeff.Jeffers@alaska.gov](mailto:Jeff.Jeffers@alaska.gov)

#### CALIFORNIA

**Bob Meline, P.E.**

Caltrans  
Office of Materials and Infrastructure  
Division of Research and Innovation  
5900 Folsom Blvd  
Sacramento, CA 95819  
(916) 227-7031  
[Bob.Meline@dot.ca.gov](mailto:Bob.Meline@dot.ca.gov)

**John Jewell, P.E.**

Senior Crash Testing Engineer  
Office of Safety Innovation & Cooperative  
Research  
(916) 227-5824  
[John\\_Jewell@dot.ca.gov](mailto:John_Jewell@dot.ca.gov)

#### COLORADO

**Joshua Keith, P.E.**

Standards & Specifications Engineer  
Project Development Branch  
Colorado Dept. of Transportation  
4201 E Arkansas Ave, 4th Floor  
Denver, CO 80222  
(303) 757-9021  
[Josh.Keith@state.co.us](mailto:Josh.Keith@state.co.us)

**Joshua Palmer, P.E.**

Guardrail Engineer  
Colorado Dept. of Transportation  
2829 W. Howard Pl  
Denver, CO 80204  
(303) 757-9229  
[Joshua.j.palmer@state.co.us](mailto:Joshua.j.palmer@state.co.us)

**Chih Shawn Yu**

(303) 757-9474  
[Shawn.yu@state.co.us](mailto:Shawn.yu@state.co.us)

**Andrew Pott, P.E. II**

Staff Bridge  
(303) 512-4020  
[Andrew.pott@state.co.us](mailto:Andrew.pott@state.co.us)

#### CONNECTICUT

**David Kilpatrick**

State of Connecticut Depart. of  
Transportation  
2800 Berlin Turnpike  
Newington, CT 06131-7546  
(806) 594-3288  
[David.Kilpatrick@ct.gov](mailto:David.Kilpatrick@ct.gov)

## DELAWARE

### **Mark Buckalew, P.E.**

Safety Program Manager  
Delaware Depart. of Transportation  
169 Brick Store Landing Road  
Smyrna, DE 19977  
(302) 659-4073  
[Mark.Buckalew@state.de.us](mailto:Mark.Buckalew@state.de.us)

## FLORIDA

### **Derwood C. Sheppard, Jr., P.E.**

Standard Plans Publication Engineer  
Florida Depart. of Transportation  
Roadway Design Office  
605 Suwannee Street, MS-32  
Tallahassee, FL 32399-0450  
(850) 414-4334  
[Derwood.Sheppard@dot.state.fl.us](mailto:Derwood.Sheppard@dot.state.fl.us)

## IDAHO

### **Kevin Sablan**

Design and Traffic Engineer  
Idaho Transportation Department  
P. O. Box 7129  
Boise, ID 83707-1129  
(208) 334-8558  
[Kevin.Sablan@ITD.idaho.gov](mailto:Kevin.Sablan@ITD.idaho.gov)

### **Rick Jensen, P.E.**

ITD Bridge Design  
(208) 334-8589  
[Rick.jensen@itd.idaho.gov](mailto:Rick.jensen@itd.idaho.gov)

Shanon M. Murgoitio, P.E.  
Engineer Manager 1

ITD Bridge Division  
(208) 334-8589  
[Shanon.murgoitio@ird.idaho.gov](mailto:Shanon.murgoitio@ird.idaho.gov)

### **Marc Danley, P.E.**

Technical Engineer  
(208) 334-8558  
[Marc.danley@itd.idaho.gov](mailto:Marc.danley@itd.idaho.gov)

## ILLINOIS

### **Martha A. Brown, P.E.**

Safety Design Bureau Chief  
Bureau of Safety Programs and Engineering  
Illinois Depart. of Transportation  
2300 Dirksen Parkway, Room 005  
Springfield, IL 62764  
(217) 785-3034  
[Martha.A.Brown@illinois.gov](mailto:Martha.A.Brown@illinois.gov)

### **Tim Craven**

[Tim.craven@illinois.gov](mailto:Tim.craven@illinois.gov)

### **Filberto (Fil) Sotelo**

Safety Evaluation Engineer  
(217) 785-5678  
[Filiberto.Sotelo@illinois.gov](mailto:Filiberto.Sotelo@illinois.gov)

### **Jon M. McCormick**

Safety Policy & Initiatives Engineer  
(217) 785-5678  
[Jon.M.McCormick@illinois.gov](mailto:Jon.M.McCormick@illinois.gov)

## LOUISIANA

### **Chris Guidry**

Bridge Manager  
Louisiana Transportation Center  
Bridge & Structural Design Section  
P.O. Box 94245  
Baton Rouge, LA 79084-9245  
(225) 379-1933  
[Chris.Guidry@la.gov](mailto:Chris.Guidry@la.gov)

### **Kurt Brauner, P.E.**

Bridge Engineer Manager  
Louisiana Transportation Center  
1201 Capital Road, Suite 605G  
Baton Rouge, LA 70802  
(225) 379-1933  
[Kurt.Brauner@la.gov](mailto:Kurt.Brauner@la.gov)

### **Brian Allen, P.E.**

Bridge Design Engineer  
(225) 379-1840  
[Brian.allen@la.gov](mailto:Brian.allen@la.gov)

### **Steve Mazur**

Bridge Design  
(225) 379-1094  
[Steven.Mazur@la.gov](mailto:Steven.Mazur@la.gov)

## MARYLAND

### **Jeff Robert**

Division Chief  
Bridge Design Division  
Office of Structures  
707 N. Calvert Street, Mailstop C-203  
Baltimore, MD 21202  
(410) 545-8327  
[jrobert@sha.state.md.us](mailto:jrobert@sha.state.md.us)

### **Sharon D. Hawkins**

Project Manager  
Office of Policy and Research, Research  
Division  
707 N. Calvert Street, Mailstop C-412  
Baltimore, MD 21202  
(410) 545-2920  
[Shawkins2@sha.state.md.us](mailto:Shawkins2@sha.state.md.us)

## MASSACHUSETTS

### **Alex Bardow**

Director of Bridges and Structure  
Massachusetts Depart. of Transportation  
10 Park Plaza, Room 6430  
Boston, MA 02116  
(517) 335-9430  
[Alexander.Bardow@state.ma.us](mailto:Alexander.Bardow@state.ma.us)

### **James Danila**

**Assistant State Traffic Engineer**  
**(857) 368-9640**  
[James.Danila@state.ma.us](mailto:James.Danila@state.ma.us)

## MICHIGAN

### **Carlos Torres, P.E.**

Crash Barrier Engineer  
Geometric Design Unit, Design Division  
Michigan Depart. of Transportation  
P. O. Box 30050  
Lansing, MI 48909  
(517) 335-2852  
[TorresC@michigan.gov](mailto:TorresC@michigan.gov)

## MINNESOTA

### **Michael Elle, P.E.**

Design Standards Engineer  
Minnesota Depart. of Transportation  
395 John Ireland Blvd, MS 696  
St. Paul, MN 55155-1899  
(651) 366-4622  
[Michael.Elle@state.mn.us](mailto:Michael.Elle@state.mn.us)

### **Michelle Moser**

**Assistant Design Standards Engineer**  
**(651) 366-4708**  
[Michelle.Moser@state.mn.us](mailto:Michelle.Moser@state.mn.us)

## MISSOURI

### **Sarah Kleinschmit, P.E.**

Policy and Innovations Engineer,  
Missouri Department of Transportation  
P.O. Box 270  
Jefferson City, MO 65102  
(573) 751-7412  
[sarah.kleinschmit@modot.mo.gov](mailto:sarah.kleinschmit@modot.mo.gov)

## MISSISSIPPI

### **Heath T. Patterson, P.E.**

MDOT-State Maintenance Engineer  
Emergency Coordinating Officer  
401 N. West Street  
Jackson, MS 39201  
(601) 359-7113  
[hpatterson@mdot.ms.gov](mailto:hpatterson@mdot.ms.gov)

## NEW MEXICO

### **David Quintana, P.E.**

Project Development Engineer  
P.O. Box 1149, Room 203  
Santa Fe, NM 87504-1149  
(505) 827-1635  
[David.quintana@state.nm.us](mailto:David.quintana@state.nm.us)

## OHIO

### **Don P. Fisher, P.E.**

Ohio Depart. of Transportation  
1980 West Broad Street  
Mail Stop 1230  
Columbus, OH 43223  
(614) 387-6214  
[Don.fisher@dot.ohio.gov](mailto:Don.fisher@dot.ohio.gov)

## **OKLAHOMA**

### **Hebret Bokhru, P.E.**

Engineering Manager  
Traffic Engineering Division  
Oklahoma Depart. of Transportation  
200 NE 21st Street, 2-A7  
Oklahoma City, OK 73105-3204  
Office (direct): (405) 522-5373  
Office (Traffic Div.): (405) 521-2861  
[Hebret.Bokhru@odot.org](mailto:Hebret.Bokhru@odot.org)

## **OREGON**

### **Christopher Henson**

**Senior Roadside Design Engineer**  
Oregon Depart. of Transportation  
Technical Service Branch

4040 Fairview Industrial Drive, SE  
Salem, OR 97302-1142

(503) 986-3561

[Christopher.S.Henson@odot.state.or.us](mailto:Christopher.S.Henson@odot.state.or.us)

## **PENNSYLVANIA**

### **Guozhou Li**

**Pennsylvania DOT**

[GuLi@pa.gov](mailto:GuLi@pa.gov)

### **Hassan Raza**

Standards & Criteria Engineer  
Pennsylvania Depart. of Transportation  
Bureau of Project Delivery  
400 North Street, 7<sup>th</sup> Floor  
Harrisburg, PA 17120  
(717) 783-5110  
[HRaza@pa.gov](mailto:HRaza@pa.gov)

## **TENNESSEE**

### **Ali Hangul, P.E., CPESC**

Assistant Director  
Tennessee Depart. of Transportation  
Roadway Design & Office of Aerial Surveys  
James K. Polk State Office Bldg.  
505 Deaderick Street  
Nashville, TN 37243  
(615) 741-0840  
[Ali.Hangul@tn.gov](mailto:Ali.Hangul@tn.gov)

## **TEXAS**

### **Chris Lindsey**

Transportation Engineer  
Design Division  
Texas Department of Transportation  
125 East 11<sup>th</sup> Street  
Austin, TX 78701-2483  
(512) 416-2750  
[Christopher.Lindsey@txdot.gov](mailto:Christopher.Lindsey@txdot.gov)

### **Taya Retterer P.E.**

TXDOT Bridge Standards Engineer  
(512) 416-2719  
[Taya.Retterer@txdot.gov](mailto:Taya.Retterer@txdot.gov)

### **Wade Odell**

Transportation Engineer  
Research & Technology Implementation  
200 E. Riverside Drive  
Austin, TX 78704  
[Wade.Odell@txdot.gov](mailto:Wade.Odell@txdot.gov)

## **UTAH**

### **Shawn Debenham**

Traffic and Safety Division  
Utah Depart. of Transportation  
4501 South 2700 West  
PO Box 143200  
Salt Lake City UT 84114-3200  
(801) 965-4590  
[sdebenham@utah.gov](mailto:sdebenham@utah.gov)

## **WASHINGTON**

### **John Donahue**

Design Policy and Analysis Manager  
Washington State Dept. of Transportation  
Development Division  
P.O. Box 47329  
Olympia, WA 98504-7246  
(360) 704-6381  
[donahjo@wsdot.wa.gov](mailto:donahjo@wsdot.wa.gov)

### **Mustafa Mohamedali**

Assistant Research Project Manager  
P.O. Box 47372  
Olympia, WA 98504-7372  
(360) 704-6307  
[mohamem@wsdot.wa.gov](mailto:mohamem@wsdot.wa.gov)



## WASHINGTON (continued)

### **Anne Freeman**

Program Administrator  
Research & Library Services  
(306) 705-7945  
[Freeann@wsdot.gov](mailto:Freeann@wsdot.gov)

## WEST VIRGINIA

### **Donna J. Hardy, P.E.**

Safety Programs Engineer  
West Virginia Depart. of  
Transportation – Traffic Engineering  
Building 5, Room A-550  
1900 Kanawha Blvd E.  
Charleston, WV 25305-0430  
(304) 558-9576  
[Donna.J.Hardy@wv.gov](mailto:Donna.J.Hardy@wv.gov)

### **Ted Whitmore**

Traffic Services Engineer  
(304) 558-9468  
[Ted.J.Whitmore@wv.gov](mailto:Ted.J.Whitmore@wv.gov)

### **Joe Hall, P.E., P.S.**

Division of Highways & Engineering  
Technical Policy QA/QC Engineer  
Value Engineering Coordinator  
1334 Smith Street  
Charleston, WV 25305-0430  
(304) 558-9733  
[Joe.H.Hall@wv.gov](mailto:Joe.H.Hall@wv.gov)

## WISCONSIN

### **Erik Emerson, P.E.**

Standards Development Engineer –  
Roadside Design  
Wisconsin Department of Transportation  
Bureau of Project Development  
4802 Sheboygan Avenue, Room 651  
P. O. Box 7916  
Madison, WI 53707-7916  
(608) 266-2842  
[Erik.Emerson@wi.gov](mailto:Erik.Emerson@wi.gov)

## CANADA – ONTARIO

### **Kenneth Shannon, P. Eng.**

Senior Engineer, Highway Design (A)  
Ontario Ministry of Transportation  
301 St. Paul Street  
St. Catharines, ON L2R 7R4  
CANADA  
(904) 704-3106  
[Kenneth.Shannon@ontario.ca](mailto:Kenneth.Shannon@ontario.ca)

## FEDERAL HIGHWAY ADMINISTRATION (FHWA)

WebSite: [safety.fhwa.dot.gov](http://safety.fhwa.dot.gov)

### **Richard B. (Dick) Albin, P.E.**

Safety Engineer  
FHWA Resource Center Safety & Design  
Technical Services Team  
711 S. Capital  
Olympia, WA 98501  
(303) 550-8804  
[Dick.Albin@dot.gov](mailto:Dick.Albin@dot.gov)

### **Eduardo Arispe**

Research Highway Safety Specialist  
U.S. Department of Transportation  
Federal Highway Administration  
Turner-Fairbank Highway Research Center  
Mail Code: HRDS-10  
6300 Georgetown Pike  
McLean, VA 22101  
(202) 493-3291  
[Eduardo.arispe@dot.gov](mailto:Eduardo.arispe@dot.gov)

### **Greg Schertz, P.E.**

FHWA – Federal Lands Highway Division  
Safety Discipline Champion  
12300 West Dakota Ave. Ste. 210  
Lakewood, CO 80228  
(720)-963-3764  
[Greg.Schertz@dot.gov](mailto:Greg.Schertz@dot.gov)

### **Christine Black**

Highway Safety Engineer  
Central Federal Lands Highway Division  
12300 West Dakota Ave.  
Lakewood, CO 80228  
(720) 963-3662  
[Christine.black@dot.gov](mailto:Christine.black@dot.gov)

**TEXAS A&M TRANSPORTATION  
INSTITUTE (TTI)**

WebSite: [tti.tamu.edu](http://tti.tamu.edu)  
[www.roadsidepooledfund.org](http://www.roadsidepooledfund.org)

**D. Lance Bullard, Jr., P.E.**

Senior Research Engineer  
Roadside Safety & Physical Security Div.  
Texas A&M Transportation Institute  
3135 TAMU  
College Station, TX 77843-3135  
(979) 317-2855  
[L-Bullard@tti.tamu.edu](mailto:L-Bullard@tti.tamu.edu)

**Roger P. Bligh, Ph.D., P.E.**

Senior Research Engineer  
(979) 317-2703  
[R-Bligh@tti.tamu.edu](mailto:R-Bligh@tti.tamu.edu)

**Chiara Silvestri Dobrovolny, Ph.D.**

Associate Research Scientist  
(979) 317-2687  
[C-Silvestri@tti.tamu.edu](mailto:C-Silvestri@tti.tamu.edu)

# REPORT AUTHORIZATION

---

## REPORT REVIEWED BY:

---

Glenn Schroeder, Research Specialist  
Drafting & Reporting

---

Ken Reeves, Research Specialist  
Electronics Instrumentation

---

Gary Gerke, Research Specialist  
Construction

---

Richard Badillo, Research Specialist  
Photographic Instrumentation

---

Scott Dobrovolny, Research Specialist  
Mechanical Instrumentation

---

Wanda L. Menges, Research Specialist  
Research Evaluation and Reporting

---

---

Bill L. Griffith, Research Specialist  
Deputy Quality Manager

---

Darrell L. Kuhn, P.E., Research Specialist  
Quality Manager

---

Matthew N. Robinson, Research Specialist  
Test Facility Manager & Technical Manager

---

Chiara Silvestri Dobrovolny, Ph.D.  
Research Scientist

---

*This page intentionally left blank.*

# TABLE OF CONTENTS

	Page
<b>Disclaimer</b> .....	ii
<b>Report Authorization</b> .....	x
<b>List of Figures</b> .....	xvi
<b>List of Tables</b> .....	xix
<b>Chapter 1. Introduction</b> .....	1
1.1. Problem Statement .....	1
1.2. Background.....	1
1.3. Objective.....	2
1.4. Work Plan.....	2
1.4.1. Task 1 – System Drawings and Construction.....	2
1.4.2. Task 2 – Full-Scale Crash Test (Test 3-11 on LON, no Curb) .....	2
1.4.3. Task 3 – Full-Scale Crash Test (Test 3-10 on LON, no Curb) .....	2
1.4.4. Task 4 – Full-Scale Crash Test (Test 3-11 on LON, with Curb).....	2
1.4.5. Task 5 – Full-Scale Crash Test (Test 3-10 on LON, with Curb).....	3
1.4.6. Task 6 – Full-Scale Crash Test (Test 3-21 on Transition).....	3
1.4.7. Task 7 – Full-Scale Crash Test (Test 3-20 on Transition).....	3
1.4.8. Task 8 – Report and Recommendations.....	3
<b>Chapter 2. Test Requirements and Evaluation Criteria</b> .....	5
2.1. Crash Test Performed/Matrix.....	5
2.2. Evaluation Criteria .....	6
<b>Chapter 3. Test Conditions</b> .....	9
3.1. Test Facility .....	9
3.2. Vehicle Tow and Guidance System .....	9
3.3. Data Acquisition Systems .....	9
3.3.1. Vehicle Instrumentation and Data Processing.....	9
3.3.2. Anthropomorphic Dummy Instrumentation .....	10
3.3.3. Photographic Instrumentation Data Processing.....	11
<b>Chapter 4. Merritt Parkway Guiderail with Curb</b> .....	13
4.1. Test Article Details.....	13
4.1.1. Installation Details .....	13
4.1.2. Design Modifications during Tests.....	13
4.1.3. Material Specifications.....	15
4.1.4. Soil Conditions .....	16
4.2. <i>MASH</i> Test 3-10 (Crash Test No. 612061-03-1).....	16
4.2.1. Test Designation and Actual Impact Conditions .....	<b>Error! Bookmark not defined.</b>
4.2.2. Weather Conditions.....	<b>Error! Bookmark not defined.</b>
4.2.3. Test Vehicle.....	<b>Error! Bookmark not defined.</b>
4.2.5. Test Description.....	<b>Error! Bookmark not defined.</b>
4.2.5. Damage to Test Installation .....	<b>Error! Bookmark not defined.</b>
4.2.6. Damage to Test Vehicle.....	<b>Error! Bookmark not defined.</b>
4.2.7. Occupant Risk Factors.....	<b>Error! Bookmark not defined.</b>

## TABLE OF CONTENTS (CONTINUED)

	Page
4.3. <i>MASH</i> Test 3-11 (Crash Test No. 612061-02-1).....	<b>Error! Bookmark not defined.</b>
4.3.1. Test Designation and Actual Impact Conditions .....	<b>Error! Bookmark not defined.</b>
4.3.2. Weather Conditions.....	<b>Error! Bookmark not defined.</b>
4.3.3. Test Vehicle.....	<b>Error! Bookmark not defined.</b>
4.3.4. Test Description.....	<b>Error! Bookmark not defined.</b>
4.3.5. Damage to Test Installation .....	<b>Error! Bookmark not defined.</b>
4.3.6. Damage to Test Vehicle.....	<b>Error! Bookmark not defined.</b>
4.3.7. Occupant Risk Factors.....	<b>Error! Bookmark not defined.</b>
<b>Chapter 5. Modified Merritt Parkway Guiderail with Curb.....</b>	<b>25</b>
5.1. Test Article Details.....	25
5.1.1. Installation Details .....	25
5.1.2. Design Modifications during Tests.....	28
5.1.3. Material Specifications.....	28
5.1.4. Soil Conditions .....	28
5.2. <i>MASH</i> Test 3-11 (Crash Test No. 612061-02-1A).....	29
5.2.1. Test Designation and Actual Impact Conditions .....	29
5.2.2. Weather Conditions.....	29
5.2.3. Test Vehicle.....	29
5.2.4. Test Description.....	30
5.2.5. Damage to Test Installation .....	30
5.2.6. Damage to Test Vehicle.....	33
5.2.7. Occupant Risk Factors.....	33
5.3. <i>MASH</i> Test 3-10 (Crash Test No. 612061-03-1).....	37
5.2.1. Test Designation and Actual Impact Conditions .....	37
5.2.2. Weather Conditions.....	37
5.2.3. Test Vehicle.....	37
5.2.5. Test Description.....	38
5.2.5. Damage to Test Installation .....	38
5.2.6. Damage to Test Vehicle.....	40
5.2.7. Occupant Risk Factors.....	40
<b>Chapter 6. Merritt Parkway Guiderail Transition.....</b>	<b>25</b>
6.1. Test Article Details.....	43
6.1.1. Installation Details .....	43
6.1.2. Design Modifications during Tests.....	44
6.1.3. Material Specifications.....	44
6.1.4. Soil Conditions .....	44
6.2. <i>MASH</i> Test 3-20 (Crash Test No. 612061-07-1).....	48
6.2.1 Test Designation and Actual Impact Conditions .....	48
6.2.2 Weather Conditions.....	48
6.2.3 Test Vehicle.....	48
6.2.4 Test Description.....	49
6.2.5 Damage to Test Installation .....	49





## LIST OF FIGURES (CONTINUED)

	<b>Page</b>
6.2.6 Damage to Test Vehicle .....	50
6.2.7 Occupant Risk Factors .....	51
6.3. <i>MASH</i> Test 3-21 (Crash Test No. 612061-06-1).....	55
6.3.1 Test Designation and Actual Impact Conditions .....	55
6.3.2 Weather Conditions.....	55
6.3.3 Test Vehicle.....	55
6.3.4 Test Description.....	56
6.3.5 Damage to Test Installation .....	56
6.3.6 Damage to Test Vehicle .....	58
6.3.7 Occupant Risk Factors .....	59
<b>Chapter 7. Summary and Conclusions .....</b>	<b>63</b>
7.1. Assessment of Test Results .....	63
7.1.1 Merritt Parkway Guiderail with 4-inch Curb .....	63
7.1.2 Modified Merritt Parkway Guiderail with 4-inch Curb .....	63
7.1.3 Merritt Parkway Guiderail Transition .....	63
7.2. Conclusions.....	63
<b>References.....</b>	<b>71</b>
<b>Appendix A. Merritt Parkway Guiderail with Curb.....</b>	<b>73</b>
A.1. Details of Installation.....	74
A.2. Soil Properties.....	87
A.3. <i>MASH</i> Test 3-10 (Crash Test No. 612061-03-1).....	<b>Error! Bookmark not defined.</b>
A.3.1. Vehicle Properties and Information.....	<b>Error! Bookmark not defined.</b>
A.3.2. Sequential Photographs .....	<b>Error! Bookmark not defined.</b>
A.3.3. Vehicle Angular Displacements.....	<b>Error! Bookmark not defined.</b>
A.3.4. Vehicle Accelerations.....	<b>Error! Bookmark not defined.</b>
A.4. <i>MASH</i> Test 3-11 (Crash Test No. 612061-02-1).....	91
A.4.1. Vehicle Properties and Information.....	91
A.4.2. Sequential Photographs .....	95
A.4.3. Vehicle Angular Displacements.....	98
A.4.4. Vehicle Accelerations.....	99
<b>Appendix B. Supporting Certification Documents .....</b>	<b>103</b>
<b>Appendix C. Modified Merritt Parkway Guiderail with Curb .....</b>	<b>195</b>
C.1. Details of Installation.....	196
C.2. Soil Properties.....	208
C.3. <i>MASH</i> Test 3-11 (Crash Test No. 612061-02-1A).....	211
C.3.1. Vehicle Properties and Information.....	211
C.3.2. Sequential Photographs .....	215
C.3.3. Vehicle Angular Displacements.....	218
C.3.4. Vehicle Accelerations.....	219

## LIST OF FIGURES (CONTINUED)

	<b>Page</b>
C.4. <i>MASH</i> Test 3-10 (Crash Test No. 612061-03-1).....	222
C.4.1. Vehicle Properties and Information.....	222
C.4.2. Sequential Photographs .....	225
C.4.3. Vehicle Angular Displacements.....	227
C.4.4. Vehicle Accelerations.....	228
<b>Appendix D. Merritt Parkway Guiderail Transition .....</b>	<b>233</b>
D.1. Details of Installation.....	234
D.2. Soil Properties.....	246
D.3 <i>MASH</i> Test 3-20 (Crash Test No. 612061-07-1).....	249
D.3.1. Vehicle Properties and Information.....	249
D.3.2. Sequential Photographs .....	252
D.3.3. Vehicle Angular Displacements.....	255
D.3.4. Vehicle Accelerations.....	256
D.4 <i>MASH</i> Test 3-21 (Crash Test No. 612061-06-1).....	259
D.4.1. Vehicle Properties and Information.....	259
D.4.2. Sequential Photographs REPLACE.....	263
D.4.3. Vehicle Angular Displacements.....	267
D.4.4. Vehicle Accelerations.....	268

## LIST OF FIGURES

		<b>Page</b>
Figure 2.1.	Target CIP for <i>MASH</i> Test 3-10 on Merritt Parkway Guiderail with Curb (Test No. 612061-02-1.....	5
Figure 2.2.	Target CIP for <i>MASH</i> Test 3-11 on Modified Merritt Parkway Guiderail with Curb (Test No. 612061-03-1.....	5
Figure 2.3.	Target CIP for <i>MASH</i> Test 3-10 on Modified Merritt Parkway Guiderail with Curb (Test No. 612061-02-1A.....	<b>Error! Bookmark not defined.</b>
Figure 2.4.	Target CIP for <i>MASH</i> Test 3-11 on Modified Merritt Parkway Guiderail with Curb (Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure 2.5.	Target CIP for <i>MASH</i> Test 3-20 on Merritt Parkway Guiderail Transition (Test No. 612061-07-1.....	6
Figure 2.6.	Target CIP for <i>MASH</i> Test 3-21 on Merritt Parkway Guiderail Transition (Test No. 612061-06-1.....	6
Figure 4.1.	Merritt Parkway Guiderail with Curb Details.....	14
Figure 4.2.	Merritt Parkway Guiderail with Curb prior to Testing.....	15
Figure 4.3.	Merritt Parkway Guiderail/Test Vehicle Geometrics for Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.4.	Test Vehicle before Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.5.	Merritt Parkway Guiderail after Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.6.	Damage from Post 5 to Post 6 after Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.7.	Damage from Post 6 to Post 7 after Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.8.	Test Vehicle after Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.9.	Interior of Test Vehicle after Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.10.	Summary of Results for <i>MASH</i> Test 3-10 on Merritt Parkway Guiderail with Curb.....	<b>Error! Bookmark not defined.</b>
Figure 4.11.	Merritt Parkway Guiderail/Test Vehicle Geometrics for Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.12.	Test Vehicle before Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.13.	Merritt Parkway Guiderail after Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.14.	Damage at Posts 5 through 8 after Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.15.	Field Side of Guiderail after Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.16.	Test Vehicle after Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.17.	Interior of Test Vehicle after Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Figure 4.18.	Summary of Results for <i>MASH</i> Test 3-11 on Merritt Parkway Guiderail....	<b>Error! Bookmark not defined.</b>
Figure 5.1.	Merritt Parkway Guiderail with Curb Details.....	26
Figure 5.2.	Merritt Parkway Guiderail with Curb prior to Testing.....	27

Figure 5.3.	Modified Merritt Parkway Guiderail/Test Vehicle Geometrics for Test No. 612061-02-1A.....	29
Figure 5.4.	Test Vehicle before Test No. 612061-02-1A.....	30
Figure 5.5.	Modified Merritt Parkway Guiderail after Test No. 612061-02-1A.....	31
Figure 5.6.	Damage at Posts 5 through 8 after Test No. 612061-02-1A.....	32
Figure 5.7.	Field Side of Guiderail after Test No. 612061-02-1A.....	33
Figure 5.8.	Test Vehicle after Test No. 612061-02-1A.....	34
Figure 5.9.	Interior of Test Vehicle after Test No. 612061-02-1A.....	34

## LIST OF FIGURES (CONTINUED)

	Page
Figure 5.10. Summary of Results for <i>MASH</i> Test 3-11 on Modified Merritt Parkway Guiderail.....	35
Figure 5.11. Modified Merritt Parkway Guiderail/Test Vehicle Geometrics for Test No. 612061-03-1.....	37
Figure 5.12. Test Vehicle before Test No. 612061-03-1.....	38
Figure 5.13. Modified Merritt Parkway Guiderail after Test No. 612061-03-1.....	39
Figure 5.14. Damage from Post 8 to Post 11 after Test No. 612061-03-1.....	40
Figure 5.15. Test Vehicle after Test No. 612061-03-1.....	41
Figure 5.16. Interior of Test Vehicle after Test No. 612061-03-1.....	41
Figure 5.17. Summary of Results for <i>MASH</i> Test 3-10 on Modified Merritt Parkway Guiderail with Curb.....	42
Figure 6.1. Merritt Parkway Guiderail Transition Details.....	45
Figure 6.2. Merritt Parkway Guiderail Transition prior to Testing.....	47
Figure 6.3. Transition/Test Vehicle Geometrics for Test No. 612061-07-1.....	48
Figure 6.4. Test Vehicle before Test No. 612061-07-1.....	49
Figure 6.5. Transition after Test No. 612061-07-1.....	50
Figure 6.6. Test Vehicle after Test No. 612061-07-1.....	51
Figure 6.7. Interior of Test Vehicle after Test No. 612061-07-1.....	51
Figure 6.8. Summary of Results for <i>MASH</i> Test 3-20 on Merritt Parkway Guiderail Transition.....	53
Figure 6.9. Transition/Test Vehicle Geometrics for Test No. 612061-06-1.....	55
Figure 6.10. Test Vehicle before Test No. 612061-06-1.....	56
Figure 6.11. Transition after Test No. 612061-06-1.....	57
Figure 6.12. Field Side of Transition after Test No. 612061-06-1.....	58
Figure 6.13. Test Vehicle after Test No. 612061-06-1.....	59
Figure 6.14. Interior of Test Vehicle after Test No. 612061-06-1.....	59
Figure 6.15. Summary of Results for <i>MASH</i> Test 4-21 on Merritt Parkway Guiderail Transition.....	61
Figure A.1. Sequential Photographs for Test No. 612061-03-1 (Overhead and Frontal Views).....	<b>Error! Bookmark not defined.</b>
Figure A.2. Sequential Photographs for Test No. 612061-03-1 (Rear View).....	<b>Error! Bookmark not defined.</b>
Figure A.3. Vehicle Angular Displacements for Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Figure A.4. Vehicle Longitudinal Accelerometer Trace for Test No. 612061-03-1 (Accelerometer Located at Center of Gravity).....	<b>Error! Bookmark not defined.</b>
Figure A.5. Vehicle Lateral Accelerometer Trace for Test No. 612061-03-1 (Accelerometer Located at Center of Gravity).....	<b>Error! Bookmark not defined.</b>
Figure A.6. Vehicle Vertical Accelerometer Trace for Test No. 612061-03-1 (Accelerometer Located at Center of Gravity).....	<b>Error! Bookmark not defined.</b>
Figure A.7. Sequential Photographs for Test No. 612061-02-1 (Overhead and Frontal Views).....	95
Figure A.8. Sequential Photographs for Test No. 612061-02-1 (Rear View).....	97
Figure A.9. Vehicle Angular Displacements for Test No. 612061-02-1.....	98



Figure A.10.	Vehicle Longitudinal Accelerometer Trace for Test No. 612061-02-1 (Accelerometer Located at Center of Gravity).....	99
--------------	--	----

**LIST OF FIGURES (CONTINUED)**

	<b>Page</b>	
Figure A.11.	Vehicle Lateral Accelerometer Trace for Test No. 612061-02-1 (Accelerometer Located at Center of Gravity).....	100
Figure A.12.	Vehicle Vertical Accelerometer Trace for Test No. 612061-02-1 (Accelerometer Located at Center of Gravity).....	101
Figure C.1.	Sequential Photographs for Test No. 612061-02-1A (Overhead and Frontal Views).....	215
Figure C.2.	Sequential Photographs for Test No. 612061-02-1A (Rear View).....	217
Figure C.3.	Vehicle Angular Displacements for Test No. 612061-02-1A.....	218
Figure C.4.	Vehicle Longitudinal Accelerometer Trace for Test No. 612061-02-1A (Accelerometer Located at Center of Gravity).....	219
Figure C.5.	Vehicle Lateral Accelerometer Trace for Test No. 612061-02-1A (Accelerometer Located at Center of Gravity).....	220
Figure C.6.	Vehicle Vertical Accelerometer Trace for Test No. 612061-02-1A (Accelerometer Located at Center of Gravity).....	221
Figure C.7.	Sequential Photographs for Test No. 612061-03-1 (Overhead and Frontal Views).....	225
Figure C.8.	Vehicle Angular Displacements for Test No. 612061-03-1.....	227
Figure C.9.	Vehicle Longitudinal Accelerometer Trace for Test No. 612061-03-1 (Accelerometer Located at Center of Gravity).....	228
Figure C.10.	Vehicle Lateral Accelerometer Trace for Test No. 612061-03-1 (Accelerometer Located at Center of Gravity).....	229
Figure C.11.	Vehicle Vertical Accelerometer Trace for Test No. 612061-03-1 (Accelerometer Located at Center of Gravity).....	230
Figure D.1.	Sequential Photographs for Test No. 612061-07-1 (Overhead and Frontal Views).....	252
Figure D.2.	Sequential Photographs for Test No. 612061-07-1 (Rear View).....	254
Figure D.3.	Vehicle Angular Displacements for Test No. 612061-07-1.....	255
Figure D4.	Vehicle Longitudinal Accelerometer Trace for Test No. 612061-07-1 (Accelerometer Located at Center of Gravity).....	256
Figure D.5.	Vehicle Lateral Accelerometer Trace for Test No. 612061-07-1 (Accelerometer Located at Center of Gravity).....	257
Figure D.6.	Vehicle Vertical Accelerometer Trace for Test No. 612061-07-1 (Accelerometer Located at Center of Gravity).....	258
Figure D.7.	Sequential Photographs for Test No. 612061-06-1 (Overhead and Frontal Views).....	263
Figure D.8.	Sequential Photographs for Test No. 612061-06-1 (Rear View).....	265
Figure D.9.	Vehicle Angular Displacements for Test No. 612061-06-1.....	267
Figure D.10.	Vehicle Longitudinal Accelerometer Trace for Test No. 612061-06-1 (Accelerometer Located at Center of Gravity).....	268
Figure D.11.	Vehicle Lateral Accelerometer Trace for Test No. 612061-06-1 (Accelerometer Located at Center of Gravity).....	269

Figure D.12. Vehicle Vertical Accelerometer Trace for Test No. 612061-06-1  
(Accelerometer Located at Center of Gravity)..... 270

## LIST OF TABLES

		<b>Page</b>
Table 2.1.	Test Conditions and Evaluation Criteria Specified for <i>MASH</i> TL-3 Longitudinal Barriers and Transitions.....	5
Table 2.2.	Evaluation Criteria Required for <i>MASH</i> TL-3 Longitudinal Barriers and Transitions.....	7
Table 4.1.	Events during Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Table 4.2.	Occupant Risk Factors for Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Table 4.3.	Events during Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Table 4.4.	Occupant Risk Factors for Test No. 612061-02-1.....	<b>Error! Bookmark not defined.</b>
Table 5.1.	Events during Test No. 612061-02-1A.....	30
Table 5.2.	Occupant Risk Factors for Test No. 612061-02-1A.....	34
Table 5.3.	Events during Test No. 612061-03-1.....	38
Table 5.4.	Occupant Risk Factors for Test No. 612061-03-1.....	41
Table 6.1.	Events during Test No. 612061-07-1.....	49
Table 6.2.	Occupant Risk Factors for Test No. 612061-07-1.....	52
Table 6.3.	Events during Test No. 612061-06-1.....	56
Table 6.4.	Occupant Risk Factors for Test No. 612061-06-1.....	60
Table 7.1.	Performance Evaluation Summary for <i>MASH</i> Test 3-10 on Merritt Parkway Guiderail.....	64
Table 7.2.	Performance Evaluation Summary for <i>MASH</i> Test 3-11 on Merritt Parkway Guiderail.....	65
Table 7.3.	Performance Evaluation Summary for <i>MASH</i> Test 3-10 on Modified Merritt Parkway Guiderail.....	66
Table 7.4.	Performance Evaluation Summary for <i>MASH</i> Test 3-11 on Modified Merritt Parkway Guiderail.....	67
Table 7.5.	Performance Evaluation Summary for <i>MASH</i> Test 3-10 on Merritt Parkway Guiderail Transition.....	68
Table 7.6.	Performance Evaluation Summary for <i>MASH</i> Test 3-21 on Merritt Parkway Guiderail Transition.....	69
Table 7.7.	Assessment Summary for <i>MASH</i> TL-3 Tests on Modified Merritt Parkway Guiderail.....	70
Table 7.8.	Assessment Summary for <i>MASH</i> TL-3 Tests on Merritt Parkway Guiderail Transition.....	70
Table A.1.	Summary of Strong Soil Test Results for Establishing Installation Procedure.....	87
Table A.2.	Test Day Static Soil Strength Documentation for Test No. 612061-03-1.....	88
Table A.2.	Test Day Static Soil Strength Documentation for Test No. 612061-02-1.....	89
Table A.3.	Vehicle Properties for Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Table A.4.	Exterior Crush Measurements for Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Table A.5.	Occupant Compartment Measurements for Test No. 612061-03-1.....	<b>Error! Bookmark not defined.</b>
Table A.6.	Vehicle Properties for Test No. 612061-02-1.....	91

Table A.7.	Measurements of Vehicle Vertical Center of Gravity for Test No. 612061-02-1.....	92
Table A.8.	Exterior Crush Measurements for Test No. 612061-02-1.....	93

**LIST OF TABLES (CONTINUED)**

	<b>Page</b>	
Table A.9.	Occupant Compartment Measurements for Test No. 612061-02-1.....	94
Table C.1.	Summary of Strong Soil Test Results for Establishing Installation Procedure.....	208
Table C.2.	Test Day Static Soil Strength Documentation for Test No. 612061-03-1.....	209
Table C.3.	Test Day Static Soil Strength Documentation for Test No. 612061-02-1A.....	210
Table C.1.	Vehicle Properties for Test No. 612061-02-1A.....	211
Table C.2.	Measurements of Vehicle Vertical Center of Gravity for Test No. 612061-02-1A.....	212
Table C.3.	Exterior Crush Measurements for Test No. 612061-02-1A.....	213
Table C.4.	Occupant Compartment Measurements for Test No. 612061-02-1A.....	214
Table C.5.	Vehicle Properties for Test No. 612061-03-1.....	222
Table C.6.	Exterior Crush Measurements for Test No. 612061-03-1.....	223
Table C.7.	Occupant Compartment Measurements for Test No. 612061-03-1.....	224
Table D.1.	Summary of Strong Soil Test Results for Establishing Installation Procedure.....	246
Table D.2.	Test Day Static Soil Strength Documentation for Test No. 612061-07-1.....	247
Table D.3.	Test Day Static Soil Strength Documentation for Test No. 612061-06-1.....	248
Table D.1.	Vehicle Properties for Test No. 612061-07-1.....	249
Table D.2.	Exterior Crush Measurements for Test No. 612061-07-1.....	250
Table D.3.	Occupant Compartment Measurements for Test No. 612061-07-1.....	251
Table D.6.	Vehicle Properties for Test No. 612061-06-1.....	259
Table D.7.	Measurements of Vehicle Vertical Center of Gravity for Test No. 612061-06-1.....	260
Table D.8.	Exterior Crush Measurements for Test No. 612061-06-1.....	261
Table D.9.	Occupant Compartment Measurements for Test No. 612061-06-1.....	262

*This page intentionally left blank.*

# Chapter 1. INTRODUCTION

## 1.1. PROBLEM STATEMENT

With the adoption of the American Association of State Highway Transportation Officials (AASHTO)/Federal Highway Administration (FHWA) Joint Implementation Agreement for *Manual for Assessing Safety Hardware (MASH)* in 2015, specific implementation dates were defined to determine crashworthiness of roadside safety systems to be implemented on projects on the National Highway System (NHS) using the 2016 edition of *AASHTO MASH (1, 2)*. Connecticut Department of Transportation (CTDOT) proposed to review, full-scale crash test, and evaluate the Merritt Parkway Guiderail system performance in accordance to the guidelines specified in the 2016 edition of *MASH*.

## 1.2. BACKGROUND

The State of Connecticut designed an aesthetic guiderail system for use on the Merritt Parkway. Bullard et al. (1996) evaluated this design in accordance to the guidelines specified in National Cooperative Highway Research Program (NCHRP) *Report 350* to allow its implementation on the NHS (3, 4). The Merritt Parkway steel-backed timber guiderail met all *NCHRP Report 350* evaluation criteria for test designations 3-11 (length of need (LON) performance with and without curb), 3-10 (LON performance without curb), and 3-21 (performance of the transition section between the LON of the guiderail and a concrete parapet).

In all tests performed, the Merritt Parkway steel-backed timber guiderail contained and redirected the vehicle through controlled lateral deflection. The vehicle did not penetrate, or go over or under the installation. In all tests, there were no detached elements or debris from the test article to show potential for penetrating the occupant compartment or presenting undue hazard to others in the area. The rail performed in all tests in a manner such that serious injury caused by the deformation of the occupant compartment was not probable. The vehicles remained upright and stable during and after collision with the guiderail. In most cases, there was minimal, if any, intrusion into adjacent traffic lanes. The occupant risk factors were within the limits specified in *NCHRP Report 350*.

The crash test program conducted in 1996 by Bullard et al. demonstrated that this aesthetic guiderail system complied with guidelines specified in *NCHRP Report 350* and was suitable for use by the State of Connecticut on the Merritt Parkway.

With the adoption of the AASHTO/FHWA Joint Implementation Agreement for *MASH* in 2016, specific implementation dates were defined to determine crashworthiness of roadside safety systems to be implemented on projects on the NHS using the 2016 edition of *MASH*. CTDOT was interested in including this guardrail system within its standards as an available roadside safety hardware. However, prior to adding this system to the CTDOT standards, it was necessary to have a *MASH-2016* compliant system. CTDOT proposes to full-scale crash test and evaluate the Merritt Parkway Guiderail system performance in accordance to the guidelines specified in the 2016 edition of *MASH*.



### **1.3. OBJECTIVE**

The testing research objectives are to:

1. Full-scale crash test and evaluate the Merritt Parkway Guiderail LON performance per *MASH* Tests 3-11 and 3-10;
2. Full-scale crash test and evaluate the Merritt Parkway Guiderail LON performance with installation of a curb in front of the guiderail (*MASH* Tests 3-11 and 3-10); and
3. Full-scale crash test and evaluate the performance of the transition section between the LON of the Merritt Parkway Guiderail and a concrete parapet (*MASH* Tests 3-21 and 3-20).

If the results of the full-scale crash tests are deemed successful per *MASH* standards, this research would generate documentation needed to support a request for an FHWA eligibility letter.

### **1.4. WORK PLAN**

#### **1.4.1. Task 1 – System Drawings and Construction**

The TTI research team worked closely with the project Technical Representative to determine the construction characteristics (and the details) of the Merritt Parkway Guiderail system, including details for curb and transition to concrete parapet. The proposed construction characteristics were approved by CTDOT before being considered for construction. A total of six full-scale crash tests were to be conducted according to *MASH* Test Level 3 (TL-3) standard.

#### **1.4.2. Task 2 – Full-Scale Crash Test (Test 3-11 on LON, no Curb)**

This full-scale crash test involves a 5000-lb pickup truck impacting the Merritt Parkway Guiderail LON at 62 mi/h nominal speed and at nominal orientation of 25 degrees (*MASH* Test 3-11). The test investigates vehicle stability, occupant risk, and evaluates the likelihood for the vehicle to experience pocketing or snagging, and undergo excessive occupant compartment deformation. As part of this Task, critical impact point (CIP) was determined according to pertinent information contained in *MASH*.

#### **1.4.3. Task 3 – Full-Scale Crash Test (Test 3-10 on LON, no Curb)**

This full-scale crash test involves a 2420-lb passenger car impacting the Merritt Parkway Guiderail LON at 62 mi/h nominal speed and at nominal orientation of 25 degrees (*MASH* Test 3-10). The test investigates vehicle stability, occupant risk, and evaluates the likelihood for the vehicle to experience pocketing or snagging, and undergo excessive occupant compartment deformation. As part of this Task, CIP was determined according to pertinent information contained in *MASH*.

#### **1.4.4. Task 4 – Full-Scale Crash Test (Test 3-11 on LON, with Curb)**

This full-scale crash test involves a 5000-lb pickup truck impacting the Merritt Parkway Guiderail LON, with a curb installed in front of the guiderail. The pickup truck vehicle impacts the system at 62 mi/h nominal speed and at nominal orientation of 25 degrees (*MASH* Test 3-11).

The test will investigate vehicle stability, occupant risk and evaluates the likelihood for the vehicle to experience pocketing or snagging, and undergo excessive occupant compartment deformation. As part of this Task, CIP was determined according to pertinent information contained in *MASH*.

#### **1.4.5. Task 5 – Full-Scale Crash Test (Test 3-10 on LON, with Curb)**

This full-scale crash test involves a 2420-lb passenger car impacting the Merritt Parkway Guiderail LON, with a curb installed in front of the guiderail. The passenger car vehicle impacts the system at 62 mi/h nominal speed and at nominal orientation of 25 degrees (*MASH* Test 3-10). The test investigates vehicle stability, occupant risk, and evaluates the likelihood for the vehicle to experience pocketing or snagging, and undergo excessive occupant compartment deformation. As part of this Task, CIP was determined according to pertinent information contained in *MASH*.

#### **1.4.6. Task 6 – Full-Scale Crash Test (Test 3-21 on Transition)**

This full-scale crash test involves a 5000-lb pickup truck impacting the transition system connecting the Merritt Parkway Guiderail to the concrete parapet. The pickup truck vehicle will impact the system at 62 mi/h nominal speed and at nominal orientation of 25 degrees (*MASH* Test 3-21). The test investigates vehicle stability, occupant risk and evaluates the likelihood for the vehicle to experience pocketing or snagging, and undergo excessive occupant compartment deformation. As part of this Task, CIP was determined according to pertinent information contained in *MASH*.

#### **1.4.7. Task 7 – Full-Scale Crash Test (Test 3-20 on Transition)**

This full-scale crash test involves a 2420-lb passenger car impacting the transition system connecting the Merritt Parkway Guiderail to the concrete parapet. The passenger car vehicle impacts the system at 62 mi/h nominal speed and at nominal orientation of 25degrees (*MASH* Test 3-20). The test investigates vehicle stability, occupant risk, and evaluates the likelihood for the vehicle to experience pocketing or snagging, and undergo excessive occupant compartment deformation. As part of this Task, CIP was determined according to pertinent information contained in *MASH*.

#### **1.4.8. Task 8 – Report and Recommendations**

The TTI research team generated this final report of the findings from the research testing. Results are reported in terms of the system performance, vehicle stability, and occupant risk factors, and was compared with respect to *MASH* crashworthiness criteria. The TTI research team provided drawings of the railing system and of each of their components.

If the results of the full-scale crash tests are deemed successful per *MASH*, this project will culminate with a request for a FHWA eligibility letter(s) for the tested and evaluated systems.

This report provides details on the Merritt Parkway Guiderail with no curb, the crash tests and results, and the performance assessment of the Merritt Parkway Guiderail with no curb for *MASH* TL-3 longitudinal barrier evaluation criteria.

*This page intentionally left blank.*

## Chapter 2. TEST REQUIREMENTS AND EVALUATION CRITERIA


### 2.1. CRASH TEST PERFORMED/MATRIX

Table 2.1. shows the test conditions and evaluation criteria for *MASH* TL-3 for longitudinal barriers and transitions. The target CIPs for each test were determined using the information provided in *MASH* Section 2.2.1 and Section 2.3.2. **Error! Reference source not found.** and **Error! Reference source not found.** show the target CIPs for *MASH* Tests on the Modified Merritt Parkway Guiderail with no curb, and Figure 2.3 and Figure 2.4 show the target CIPs for the *MASH* tests on the Merritt Parkway Guiderail Transition.


**Table 2.1. Test Conditions and Evaluation Criteria Specified for *MASH* TL-3 Longitudinal Barriers and Transitions.**

Test Article	Test Designation	Test Vehicle	Impact Conditions		Evaluation Criteria
			Speed	Angle	
Longitudinal Barriers	3-10	1100C	62 mi/h	25°	A, D, F, H, I
	3-11	2270P	62 mi/h	25°	A, D, F, H, I
Transitions	3-20	1100C	62 mi/h	25°	A, D, F, H, I
	3-21	2270P	62 mi/h	25°	A, D, F, H, I
	3-21	2270P	62 mi/h	25°	A, D, F, H, I


**Figure 2.1. Target CIP for *MASH* Test 3-10 on Merritt Parkway Guiderail with Curb (Test No. 612061-03-1).**



**Figure 2.2. Target CIP for *MASH* Test 3-11 on Modified Merritt Parkway Guiderail with Curb (Test No. 612061-03-1).**



**Figure 2.3. Target CIP for *MASH* Test 3-20 on Merritt Parkway Guiderail Transition (Test No. 612061-07-1).**



**Figure 2.4. Target CIP for *MASH* Test 3-21 on Merritt Parkway Guiderail Transition (Test No. 612061-06-1).**

The crash tests and data analysis procedures were in accordance with guidelines presented in *MASH*. Chapter 4 presents brief descriptions of these procedures.

## 2.2. EVALUATION CRITERIA

The appropriate safety evaluation criteria from Tables 2-2 and 5-1 of *MASH* were used to evaluate the crash tests reported herein. Table 2.1. lists the test conditions and evaluation criteria required for *MASH* TL-3, and Table 2.2 provides detailed information on the evaluation criteria. An evaluation of the crash test results is presented in Chapter 7.

**Table 2.2. Evaluation Criteria Required for MASH TL-3 Longitudinal Barriers and Transitions.**

<b>Evaluation Factors</b>	<b>Evaluation Criteria</b>	<b>MASH Test</b>
<b>Structural Adequacy</b>	A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	10, 11, 20, 21
<b>Occupant Risk</b>	D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present undue hazard to other traffic, pedestrians, or personnel in a work zone.  Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	10, 11, 20, 21
	F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	10, 11, 20, 21
	H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	10, 11, 20, 21
	I. <i>The occupant ridedown accelerations should satisfy the following: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	10, 11, 20, 21

*This page intentionally left blank.*

## **Chapter 3. TEST CONDITIONS**

### **3.1. TEST FACILITY**

The full-scale crash tests reported herein were performed at the TTI Proving Ground, an International Standards Organization (ISO)/International Electrotechnical Commission (IEC) 17025-accredited laboratory with American Association for Laboratory Accreditation (A2LA) Mechanical Testing Certificate 2821.01. The full-scale crash tests were performed according to TTI Proving Ground quality procedures, as well as *MASH* guidelines and standards.

The test facilities of the TTI Proving Ground are located on The Texas A&M University System RELIS Campus, which consists of a 2000-acre complex of research and training facilities situated 10 mi northwest of the flagship campus of Texas A&M University. The site, formerly a United States Army Air Corps base, has large expanses of concrete runways and parking aprons well suited for experimental research and testing in the areas of vehicle performance and handling, vehicle-roadway interaction, highway pavement durability and efficacy, and roadside safety hardware and perimeter protective device evaluation. The site selected for construction and testing of the Merritt Parkway Guiderail installation was along the edge of an out-of-service apron. The apron consists of an unreinforced jointed-concrete pavement in 12.5-ft × 15-ft blocks nominally 6 inches deep. The aprons were built in 1942, and the joints have some displacement but are otherwise flat and level.

### **3.2. VEHICLE TOW AND GUIDANCE SYSTEM**

Each vehicle was towed into the test installation using a steel cable guidance and reverse tow system. A steel cable for guiding the test vehicle was tensioned along the path, anchored at each end, and threaded through an attachment to the front wheel of the test vehicle. An additional steel cable was connected to the test vehicle, passed around a pulley near the impact point and through a pulley on the tow vehicle, and then anchored to the ground such that the tow vehicle moved away from the test site. A 2:1 speed ratio between the test and tow vehicle existed with this system. Just prior to impact with the installation, the test vehicle was released and ran unrestrained. The vehicle remained freewheeling (i.e., no steering or braking inputs) until it cleared the immediate area of the test site.

### **3.3. DATA ACQUISITION SYSTEMS**

#### **3.3.1. Vehicle Instrumentation and Data Processing**

Each test vehicle was instrumented with a self-contained onboard data acquisition system. The signal conditioning and acquisition system is a 16-channel Tiny Data Acquisition System (TDAS) Pro produced by Diversified Technical Systems Inc. The accelerometers, which measure the x, y, and z axis of vehicle acceleration, are strain gauge type with linear millivolt output proportional to acceleration. Angular rate sensors, measuring vehicle roll, pitch, and yaw rates, are ultra-small, solid-state units designed for crash test service. The TDAS Pro hardware and software conform to the latest SAE J211, Instrumentation for Impact Test. Each of the 16 channels is capable of providing precision amplification, scaling, and filtering based on



transducer specifications and calibrations. During the test, data are recorded from each channel at a rate of 10,000 samples per second with a resolution of one part in 65,536. Once data are recorded, internal batteries back these up inside the unit in case the primary battery cable is severed. Initial contact of the pressure switch on the vehicle bumper provides a time zero mark and initiates the recording process. After each test, the data are downloaded from the TDAS Pro unit into a laptop computer at the test site. The Test Risk Assessment Program (TRAP) software then processes the raw data to produce detailed reports of the test results.

Each of the TDAS Pro units is returned to the factory annually for complete recalibration and to ensure that all instrumentation used in the vehicle conforms to the specifications outlined by SAE J211. All accelerometers are calibrated annually by means of an ENDEVCO® 2901 precision primary vibration standard. This standard and its support instruments are checked annually and receive a National Institute of Standards Technology (NIST) traceable calibration. The rate transducers used in the data acquisition system receive calibration via a Genisco Rate-of-Turn table. The subsystems of each data channel are also evaluated annually, using instruments with current NIST traceability, and the results are factored into the accuracy of the total data channel per SAE J211. Calibrations and evaluations are also made anytime data are suspect. Acceleration data are measured with an expanded uncertainty of  $\pm 1.7$  percent at a confidence factor of 95 percent ( $k = 2$ ).

TRAP uses the data from the TDAS Pro to compute the occupant/compartiment impact velocities, time of occupant/compartiment impact after vehicle impact, and highest 10-millisecond (ms) average ridedown acceleration. TRAP calculates change in vehicle velocity at the end of a given impulse period. In addition, maximum average accelerations over 50-ms intervals in each of the three directions are computed. For reporting purposes, the data from the vehicle-mounted accelerometers are filtered with an SAE Class 180-Hz low-pass digital filter, and acceleration versus time curves for the longitudinal, lateral, and vertical directions are plotted using TRAP.

TRAP uses the data from the yaw, pitch, and roll rate transducers to compute angular displacement in degrees at 0.0001-s intervals, and then plots yaw, pitch, and roll versus time. These displacements are in reference to the vehicle-fixed coordinate system with the initial position and orientation being initial impact. Rate of rotation data is measured with an expanded uncertainty of  $\pm 0.7$  percent at a confidence factor of 95 percent ( $k = 2$ ).

### **3.3.2. Anthropomorphic Dummy Instrumentation**

An Alderson Research Laboratories Hybrid II, 50th percentile male anthropomorphic dummy, restrained with lap and shoulder belts, was placed in the front seat on the impact side of the 1100C vehicle. The dummy was not instrumented.

According to *MASH*, use of a dummy in the 2270P vehicle is optional, and no dummy was used in the test. However, *MASH* recommends that a dummy be used when testing “any longitudinal barrier with a height greater than or equal to 33 inches.” More specifically, use of the dummy in the 2270P vehicle is recommended for tall rails to evaluate the “potential for an occupant to extend out of the vehicle and come into direct contact with the test article.” Although this information is reported, it is not part of the impact performance evaluation. Since the rail height of the concrete parapet was 33 inches, a dummy was placed in the front seat of the 2270P vehicle on the impact side and restrained with lap and shoulder belts.

### **3.3.3. Photographic Instrumentation Data Processing**

Photographic coverage of each test included three digital high-speed cameras:

- One overhead with a field of view perpendicular to the ground and directly over the impact point.
- One placed upstream from the installation at an angle to have a field of view of the interaction of the rear of the vehicle with the installation.
- A third placed with a field of view parallel to and aligned with the installation at the downstream end.

A flashbulb on the impacting vehicle was activated by a pressure-sensitive tape switch to indicate the instant of contact with the guiderail/transition installation. The flashbulb was visible from each camera. The video files from these digital high-speed cameras were analyzed to observe phenomena occurring during the collision and to obtain time-event, displacement, and angular data. A digital camera recorded and documented conditions of each test vehicle and the installation before and after the test.

*This page intentionally left blank.*

## Chapter 4. MERRITT PARKWAY GUIDERAIL WITH CURB

### 4.1. TEST ARTICLE DETAILS

#### 4.1.1. Installation Details

The installation was comprised of a timber single rail system supported by timber blockouts attached to steel W6×15 by 78-inch long posts embedded 49¼ inches below grade. The top of the rail was 30 inches above grade. The timber rails were secured to blockouts and posts with a standard steel backup plate attached to the field side of the timbers, which were in turn both attached to a splice plate attached to the posts and blockouts. A concrete parapet with an adjoining transition section was constructed on the downstream end of the system, and a sloped and flared anchor section was constructed on the upstream end. The total length of the system measured 166 ft-0 inches.

The parapet measured 16 ft long, 33 inches high above grade, and 12 inches wide at the top, stepping to 10½ inches wide at the base on the field side at 20 inches above grade. The concrete parapet was anchored with U-bars to a 16-ft long, 56-inch wide, and 18-inch deep concrete slab cast below grade.

The timber rail transition section extended 21 ft-2 inches upstream from the end of the parapet with four post spacings at 30 inches and two post spacings at 60 inches. A terminal curb section extended from the parapet approximately 20 feet upstream. It commenced 8 inches above grade, sloped downward, and terminated flush with grade just downstream of post 13.

The LON measured 100 ft with eleven posts (Nos. 3–13) spaced on 10-ft centers. The upstream anchor section measured 29 ft-½ inch in length and flared 34¼ inches to the field side while sloping down before terminating into an anchor block located below grade. The concrete anchor block measured approximately 36×36 inches × 39 inches tall and was cast 59½ inches deep into the surrounding soil.

Figure 4.1 presents the overall information on the Merritt Parkway Guiderail, and Figure 4.2 provides photographs of the installation. Appendix A.1 provides further details on the Merritt Parkway Guiderail. Drawings were provided by the Texas A&M Transportation Institute (TTI) Proving Ground, and construction was performed by Bryan Construction and DMA Construction, Inc., and supervised by TTI Proving Ground personnel.

#### 4.1.2. Design Modifications during Tests

No modification was made to the installation during this testing phase. No modification was made to the installation during this testing phase. However, due to the results of this testing phase, modifications were made to the system as described in Chapter 5 of this report.

**Figure 4.1. Details of Merritt Parkway Guiderail with No Curb.**



**Figure 4.2. Merritt Parkway Guiderail with No Curb prior to Testing.**

#### **4.1.3. Material Specifications**

The specified minimum compressive strengths of concrete were as follows:

- Parapet and foundation – 3600 psi.
- Parapet terminal transition curb – 3000 psi.
- 50 ft curb in LON – 4000 psi.
- Anchor block – 3000 psi.



Concrete samples from the parapet foundation were broken on 2020-06-01. Concrete samples from the parapet, transition curb, 50 ft curb, and anchor block were broken on 2020-07-07. The average compressive strengths of the concrete were as follows:

- Parapet foundation: 4893 psi at 32 days of age.
- Parapet: 5573 psi at 46 days of age. parapet terminal transition curb: 5573 psi at 46 days of age.
- 50 ft curb in LON: 4573 psi at 26 days of age.
- Anchor block: 5573 psi at 46 days of age

Appendix B provides material certification documents for the materials used to install/construct the Merritt Parkway Guiderail.

#### 4.1.4. Soil Conditions

The test installation was installed in standard soil meeting grading B of AASHTO standard specification M147-65(2004) “Materials for Aggregate and Soil Aggregate Subbase, Base and Surface Courses.” A soil strength test was not performed.

### 4.2. MASH TEST 3-11 (CRASH TEST NO. 612061-02-1)

#### 4.2.1. Test Designation and Actual Impact Conditions

MASH Test 3-11 involves a 2270P vehicle weighing 5000 lb  $\pm$  110 lb impacting the CIP of the longitudinal barrier at an impact speed of 62 mi/h  $\pm$  2.5 mi/h and an angle of 25 degrees  $\pm$  1.5 degrees. The CIP for MASH Test 3-11 on the Merritt Parkway Guiderail with no curb was 14.0 ft  $\pm$  1 ft upstream of centerline of post 11. Figure 2.1 and **Error! Reference source not found.** depict the target impact setup.



**Figure 4.3. Merritt Parkway Guiderail/Test Vehicle Geometrics for Test No. 612061-02-1.**

The 2270P vehicle weighed 5012 lb, and the actual impact speed and angle were 62.4 mi/h and 24.3 degrees. The actual impact point was 13.6 ft upstream of the centerline of post 11. Minimum target impact severity (IS) was 106 kip-ft, and actual IS was 111 kip-ft.

#### 4.2.2. Weather Conditions

The test was performed on the morning of December 17, 2020. Weather conditions at the time of testing were as follows: wind speed: 4 mi/h; wind direction: 196 degrees (vehicle was traveling at a heading of 195 degrees); temperature: 44°F; relative humidity: 80 percent.

#### 4.2.3. Test Vehicle

**Error! Reference source not found.** shows the 2014 RAM 1500 pickup truck used for the crash test. The vehicle's test inertia weight was 5012 lb, and its gross static weight was 5177 lb. The height to the lower edge of the vehicle bumper was 11.8 inches, and height to the upper edge of the bumper was 27.0 inches. The height to the vehicle's center of gravity was 28.5 inches. Tables A.6 and A.7 in Appendix A.4.1 give additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.



**Figure 4.4. Test Vehicle before Test No. 612061-02-1.**

#### 4.2.4. Test Description

**Error! Reference source not found.** lists events that occurred during Test No. 612061-02-1. Figures A.7 and A.8 in Appendix A.4.2 present sequential photographs during the test.

**Table 4.1. Events during Test No. 612061-02-1.**

Time (s)	Events
0.0000	Vehicle impacts the installation
0.0160	Post 9 and 8 begins to deflect toward field side
0.0380	Post 8 and 10 begins to deflect back toward field side
0.0470	Vehicle begins to redirect
0.1470	Upstream end of rail at post 11 impacts front of vehicle
0.2890	Forward momentum of truck ceased and truck begins to yaw clockwise
1.0000	Vehicle loses contact with guide rail while traveling at 8.4 mi/h, trajectory of 86.2 degrees, and heading of 75.6 degrees



For longitudinal barriers, it is desirable for the vehicle to redirect and exit the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. After loss of contact with the guide rail, the vehicle came to rest 17.5 ft downstream of the point of impact and against 5 ft toward traffic lanes.

#### 4.2.5. Damage to Test Installation

**Error! Reference source not found.** through **Error! Reference source not found.** show the damage to the Merritt Parkway Guiderail with no curb. The traffic face of the wood rail was scuffed and gouged at impact. The rail between posts 9 and 11 had extensive damage and was shattered with large pieces removed that came to rest 25 ft behind the rail in line with post 12. Post 8 was leaning 6 degrees toward the field side from vertical, and there was a 3½-inch gap in the soil on the traffic side. Post 9 was leaning 10 degrees toward the field side from vertical, and there was a 2-inch gap in the soil on the field side. Post 10 was leaning 28 degrees toward the field side and downstream from vertical, and the blockout was split in half vertically. Post 11 was severely deformed and was leaning 51 degrees toward field side and downstream from vertical. Post 12 was leaning 6 degrees toward field side from vertical, and there was a 2½-inch gap in the soil on the traffic side. Post 13 had a ¼-inch gap in the soil on both the traffic and field side. Working width\* was 44.8 inches, and height of working width was 46.3 inches. Maximum dynamic deflection during the test was 22.6 inches. The maximum permanent deformation of the metal backup rail was 22.9 inches.

---

\* Per *MASH*, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.



**Figure 4.5. Merritt Parkway Guiderail after Test No. 612061-02-1.**





**Figure 4.6. Damage at Posts 8 through 13 after Test No. 612061-02-1.**





**Figure 4.7. Field Side of Guiderail after Test No. 612061-02-1.**

#### **4.2.6. Damage to Test Vehicle**

**Error! Reference source not found.** shows the damage sustained by the vehicle. **The front bumper, hood, grill, radiator and support, right front fender, right frame rail, right upper and lower control arms, right front tire and rim, right A-post, right front door, right front floor pan, right rear cab corner, right exterior bed, and rear rear spring were damaged. The windshield had stress cracks radiating upward and inward from the right lower corner. The windshield sustained stress cracks radiating upward and inward from the lower right corner. No fuel tank damage was observed. Maximum exterior crush to the vehicle was 16.0 inches in the front plane at the right front corner at bumper height. Maximum occupant compartment deformation was 6.0 inches in the right front firewall/toe pan area. Error! Reference source not found.** shows the interior of the vehicle. Tables A.9 and A.10 in Appendix A.4.1 provide exterior crush and occupant compartment measurements.

#### **4.2.7. Occupant Risk Factors**

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in **Error! Reference source not found.** Figure A.9 in Appendix A.4.3 shows the vehicle angular displacements, and Figures A.10 through A.12 in Appendix A.4.4 show acceleration versus time traces. **Error! Reference source not found.** summarizes pertinent information from the test.



**Figure 4.8. Test Vehicle after Test No. 612061-02-1.**




**Figure 4.9. Interior of Test Vehicle after Test No. 612061-02-1.**

**Table 4.2. Occupant Risk Factors for Test No. 612061-02-1.**

<b>Occupant Risk Factor</b>	<b>Value</b>	<b>Time</b>
<b>Occupant Impact Velocity (OIV)</b>		
Longitudinal	23.3 ft/s	at 0.1386 s on right side of interior
Lateral	14.4 ft/s	
<b>Occupant Ridedown Accelerations</b>		
Longitudinal	25.0 g	0.1516 - 0.1616 s
Lateral	10.6 g	0.1473 - 0.1573 s
<b>Theoretical Head Impact Velocity (THIV)</b>	7.7 m/s	at 0.1319 s on right side of interior
<b>Acceleration Severity Index (ASI)</b>	1.2	0.1564 - 0.2064 s
<b>Maximum 50-ms Moving Average</b>		
Longitudinal	-14.0 g	0.1803 - 0.2303 s
Lateral	-5.4 g	0.0408 - 0.0908 s
Vertical	-5.3 g	1.1199 - 1.1699 s
<b>Maximum Yaw, Pitch, and Roll Angles</b>		
Roll	19 degrees	1.5955 s
Pitch	16 degrees	0.6788 s
Yaw	60 degrees	1.2362 s





**General Information**

Test Agency..... Texas A&M Transportation Institute (TTI)  
 Test Standard Test No..... MASH Test 3-11  
 TTI Test No..... 612061-02-1  
 Test Date..... 2020-12-17

**Test Article**

Type..... Longitudinal Barrier—Guardrail  
 Name ..... Merritt Parkway Guiderail with no curb  
 Installation Length..... 166 ft  
 Material or Key Elements.... Metal back timber rail on steel posts and timber blockouts

**Soil Type and Condition**..... AASHTO M147-65, grading B Soil (crushed limestone)

**Test Vehicle**

Type/Designation..... 2270P  
 Make and Model..... 2014 RAM 1500 Pickup  
 Curb..... 4962 lb  
 Test Inertial..... 5012 lb  
 Dummy..... 165 lb  
 Gross Static..... 5177 lb

**Impact Conditions**

Speed .....62.4 mi/h  
 Angle.....24.3°  
 Location/Orientation.....13.6 ft upstream of post 11

**Impact Severity** .....111 kip-ft

**Exit Conditions**

Speed .....8.4 m/h  
 Trajectory/Heading Angle ...86.2°/75.6°

**Occupant Risk Values**

Longitudinal OIV .....23.3 ft/s  
 Lateral OIV.....14.4 ft/s  
 Longitudinal Ridedown .....25.0 g  
 Lateral Ridedown.....10.6 g  
 THIV .....7.7 m/s  
 ASI.....1.2

**Max. 0.050-s Average**

Longitudinal.....-14.0 g  
 Lateral.....-5.4 g  
 Vertical.....-5.3 g

**Post-Impact Trajectory**

Stopping Distance..... 17.5 ft downstream  
 5 ft twd traffic lanes

**Vehicle Stability**

Maximum Roll Angle ..... 19°  
 Maximum Pitch Angle..... 16°  
 Maximum Yaw Angle..... 60°  
 Vehicle Snagging..... Yes  
 Vehicle Pocketing..... Yes

**Test Article Deflections**

Dynamic..... 22.6 inches  
 Permanent..... 22.9 inches-backup  
 Working Width ..... 44.8 inches  
 Height of Working Width..... 46.3 inches

**Vehicle Damage**

VDS ..... 01RFQ5  
 CDC..... 01FREW3  
 Max. Exterior Deformation ..... 16.0 inches  
 OCDI..... RF0020000  
 Max. Occupant Compartment Deformation..... 6.0 inches

**Figure 4.10. Summary of Results for MASH Test 3-11 on Merritt Parkway Guiderail with No Curb.**

### 4.3. DISCUSSION

*MASH* Test 3-11 for longitudinal barriers was performed on the Merritt Parkway Guiderail with no curb. During this test, the longitudinal occupant ridedown acceleration of 25.0 g exceeded the limit of 20.49 g specified in *MASH*. Therefore, modifications were made to the design and the guiderail was retested.

## Chapter 5. MODIFIED MERRITT PARKWAY GUIDERAIL WITH NO CURB

### 5.1. TEST ARTICLE DETAILS

#### 5.1.1. Installation Details

The Modified Merritt Parkway Guiderail incorporated 21 posts in the LON such that the post spacing was decreased from 10 ft to 5 ft. Furthermore, the ten additional posts (with blockouts) were not bolted to the timber rails and steel backup plates. To wit:

The installation was comprised of a timber single rail system supported by timber blockouts attached to steel W6×15 by 78-inch long posts embedded 53¼ inches below grade. The top of the rail was 30 inches above grade. For odd numbered posts (Nos. 3-23), the timber rails were secured to blockouts and posts with a standard steel backup plate attached to the field side of the timbers, which were in turn both attached to a splice plate attached to the posts and blockouts. For even numbered posts (Nos. 4-22) the timber rail and steel backup plates were not bolted to the posts and blockouts. A concrete parapet with an adjoining transition section was constructed on the downstream end of the system, and a sloped and flared anchor section was constructed on the upstream end. The total length of the system measured 166 ft-0 inches.

The parapet measured 16 ft long, 33 inches high above grade, and 12 inches wide at the top, stepping to 10½ inches wide at the base on the field side at 20 inches above grade. The concrete parapet was anchored with U-bars to a 16-ft long, 56-inch wide, and 18-inch deep concrete slab cast below grade.

The timber rail transition section extended 21 ft-2 inches upstream from the end of the parapet with four post spacings at 30 inches and two post spacings at 60 inches. A terminal curb section extended from the parapet approximately 20 feet upstream. It commenced 8 inches above grade, sloped downward, and terminated flush with grade just downstream of post 23.


The LON measured 100 ft with eleven posts (Nos. 3–23) spaced on 5 ft centers. A 50-foot long curb section (spanning from posts Nos. 7-17) was constructed with its face located 12 inches from the traffic side of the rail. The top of the curb was at grade as referenced to the rail height. The bottom of the curb was 4 inches below grade at the roadway elevation. The 4-inch tall, sloped-face curb was 5¾ inches wide at the bottom with a 12-inch deep by 31¾-inch wide base below grade.

The upstream anchor section measured 29 ft-½ inch in length and flared 34¼ inches to the field side while sloping down before terminating into an anchor block located below grade. The concrete anchor block measured approximately 36×36 inches × 39 inches tall and was cast 59½ inches deep into the surrounding soil.

Figure 4.1 presents the overall information on the Modified Merritt Parkway Guiderail, and Figure 4.2 provides photographs of the installation. Appendix C.1 provides further details on the Modified Merritt Parkway Guiderail. Drawings were provided by the Texas A&M Transportation Institute (TTI) Proving Ground, and construction was performed by Bryan Construction and DMA Construction, Inc., and supervised by TTI Proving Ground personnel.



**Figure 5.1. Details of Merritt Parkway Guiderail with No Curb.**



**Figure 5.2. Modified Merritt Parkway Guiderail with No Curb prior to Testing.**



### 5.1.2. Design Modifications during Tests

Other than described above, no additional modifications were made to the Modified Merritt Parkway Guiderail with no curb during this testing phase.

### 5.1.3. Material Specifications

The specified minimum compressive strengths of concrete were as follows:

- Parapet and foundation – 3600 psi.
- Parapet terminal transition curb – 3000 psi.
- 50 ft curb in LON – 4000 psi.
- Anchor block – 3000 psi.

Concrete samples from the parapet foundation were broken on 2020-06-01. concrete samples from the parapet, transition curb, and anchor block were broken on 2020-07-07. The reconstructed 50 ft Curb samples were broken on 2020-09-02. The average compressive strengths of the concrete were as follows:

- Parapet foundation: 4893 psi at 32 days of age.
- Parapet: 5573 psi at 46 days of age. parapet terminal transition curb: 5573 psi at 46 days of age.
- 50 ft curb in LON: 5187 psi at 43 days of age.
- Anchor block: 5573 psi at 46 days of age

Appendix B provides material certification documents for the materials used to install/construct the Modified Merritt Parkway Guiderail with no curb.

### 5.1.4. Soil Conditions

The test installation was installed in standard soil meeting grading B of AASHTO standard specification M147-65(2004) “Materials for Aggregate and Soil Aggregate Subbase, Base and Surface Courses.”

In accordance with Appendix B of *MASH*, soil strength was measured the day of the crash test. During installation of the Merritt Parkway Guiderail for full-scale crash testing, two 6-ft long W6×16 posts were installed in the immediate vicinity of the Merritt Parkway Guiderail using the same fill materials and installation procedures used in the test installation and the standard dynamic test. Table C.1 in Appendix C.2 presents minimum soil strength properties established through the dynamic testing performed in accordance with *MASH* Appendix B.

As determined by the tests summarized in Appendix C.2, Table C.1, the minimum post loads required for deflections at 5 inches, 10 inches, and 15 inches, measured at a height of 25 inches, are 3940 lb, 5500 lb, and 6540 lb (90 percent of static load for the initial standard installation).

On the day of Crash Test No. 612061-02-1A, October 2, 2020, loads on the post at deflections of 5 inches, 10 inches, and 15 inches were 8543 lbf, 8333 lbf, and 8030 lbf. On the

day of the rash Test No. 612061-03-1, September 2, 2020, loads on the post at deflections of 5 inches, 10 inches, and 15 inches were 10,909 lbf, 9848 lbf, and 7575 lbf. Table C.2 and Table C.3 in Appendix C.2 show the strength of the backfill material in which the Merritt Parkway Guiderail was installed met minimum *MASH* requirements for soil strength.

## 5.2. *MASH* TEST 3-11 (CRASH TEST NO. 612061-02-1A)

### 5.2.1. Test Designation and Actual Impact Conditions

*MASH* Test 3-11 involves a 2270P vehicle weighing 5000 lb ± 110 lb impacting the CIP of the longitudinal barrier at an impact speed of 62 mi/h ± 2.5 mi/h and an angle of 25 degrees ± 1.5 degrees. The CIP for *MASH* Test 3-11 on the Modified Merritt Parkway Guiderail with no curb was 14.0 ft ± 1 ft upstream of centerline of post 11. **Error! Reference source not found.** and Figure 5.3 depict the target impact setup.



**Figure 5.3. Modified Merritt Parkway Guiderail with No Curb/Test Vehicle Geometrics for Test No. 612061-02-1A.**

The 2270P vehicle weighed 5033 lb, and the actual impact speed and angle were 61.5 mi/h and 25.1 degrees. The actual impact point was 14.2 ft upstream of the centerline of post 11. Minimum target IS was 106 kip-ft, and actual IS was 115 kip-ft.

### 5.2.2. Weather Conditions

The test was performed on the afternoon of September 2, 2020. Weather conditions at the time of testing were as follows: wind speed: 1 mi/h; wind direction: 252 degrees (vehicle was traveling at a heading of 195 degrees); temperature: 84°F; relative humidity: 75 percent.

### 5.2.3. Test Vehicle

Figure 5.4 shows the 2014 RAM 1500 pickup truck used for the crash test. The vehicle's test inertia weight was 5033 lb, and its gross static weight was 5033 lb. The height to the lower edge of the vehicle bumper was 11.75 inches, and height to the upper edge of the bumper was 27.0 inches. The height to the vehicle's center of gravity was 29.5 inches. Tables C.1 and C.2 in Appendix C.3.1 give additional dimensions and information on the vehicle. The vehicle was

directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.



**Figure 5.4. Test Vehicle before Test No. 612061-02-1A.**

#### 5.2.4. Test Description

Table 5.1 lists events that occurred during Test No. 612061-02-1A. Figures C.1 and C.2 in Appendix C.3.2 present sequential photographs during the test.

**Table 5.1. Events during Test No. 612061-02-1A.**

Time (s)	Events
-0.011	Vehicle right front tire contacts curb
0.000	Vehicle impacts guiderail
0.018	Post 9 and 8 deflect toward field side
0.040	Vehicle begins to redirect
0.065	Wooden rail element between post 9 and 11 fractured
0.092	Front of vehicle contacts post 10
0.163	Front of vehicle contacts upstream end of rail between post 11 and 12
0.355	Vehicle forward momentum stopped and begins rotating clockwise

For longitudinal barriers, it is desirable for the vehicle to redirect and exit the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. Brakes on the vehicle were not applied. The vehicle came to rest 17 ft downstream of the point of impact and against the traffic face of the guiderail.

#### 5.2.5. Damage to Test Installation

Figure 5.5 through Figure 5.7 show the damage to the Modified Merritt Parkway Guiderail. There was no movement noted between posts 1 through 4 and 6. The soil was disturbed at post 5. Post 7 had a 1/8-inch gap in the soil at both the traffic and field side of the post, and was leaning 1 degree from vertical toward field side. Post 8 had a 1 1/2-inch gap in the soil on the traffic side, and 1/4-inch gap on the field side, with the post leaning 3 degrees from vertical toward the field side. Post 9 had a 3 1/2-inch gap in the soil at the back, and was leaning



2 degrees from vertical toward field side. Post 10 was detached from the rail, rotated 90 degrees clockwise, and was leaning 32 degrees from vertical over. Post 11 was similarly detached from the rail, rotated 90 degrees clockwise, and was leaning 48 degrees from vertical. Post 12 had a 1-inch gap in the soil at the front, and was leaning 1.6° degrees from vertical toward the field side. The rail at post 12 was 9¾ inches from the front face of the blockout. Post 13 had a ½-inch gap in the soil on the field side, and was leaning 1 degree from vertical toward the filed side. The upstream rail at this post was 2 inches from the front face of the blockout. Posts 14 through 17 had a slight soil disturbance, and no movement was noted from post 18 to the end. The debris field extended from impact toward the field side of the rail, and ended at post 16. A large section of the wooden rail came to rest 20 ft behind the posts and 16 ft downstream from impact. There was another smaller section of rail that came to rest 43 ft behind and in line with post 16. Working width\* was 70.1 inches, and height of working width was 35.5 inches. Maximum dynamic deflection during the test was 30.4 inches. The maximum permanent deformation of the installation was 12.5 inches at 4 ft downstream of post 9.



**Figure 5.5. Modified Merritt Parkway Guiderail after Test No. 612061-02-1A.**

---

\* Per *MASH*, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.





**Figure 5.6. Damage at Posts 5 through 8 after Test No. 612061-02-1A.**





**Figure 5.7. Field Side of Guiderail after Test No. 612061-02-1A.**

### **5.2.6. Damage to Test Vehicle**

Figure 5.8 shows the damage sustained by the vehicle. The front bumper, hood, grill, radiator and support, fan, water pump, right frame rail, right upper and lower control arms, right front tire and rim, right front fender, right front floor pan, and right front door. The windshield had a few stress cracks radiating upward and inward from the right lower corner. No fuel tank damage was observed. Maximum exterior crush to the vehicle was 12.0 inches in the side plane at the right front corner at bumper height. Maximum occupant compartment deformation was 4.25 inches in the right front firewall area. Figure 5.9 shows the interior of the vehicle. Tables C.3 and C.4 in Appendix C.3.1 provide exterior crush and occupant compartment measurements.

### **5.2.7. Occupant Risk Factors**

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in Table 5.2. Figure C.3 in Appendix C.3.3 shows the vehicle angular displacements, and Figures C.4 through C.6 in Appendix C.3.4 show acceleration versus time traces. Figure 5.10 summarizes pertinent information from the test.






**Figure 5.8. Test Vehicle after Test No. 612061-02-1A.**



**Figure 5.9. Interior of Test Vehicle after Test No. 612061-02-1A.**

**Table 5.2. Occupant Risk Factors for Test No. 612061-02-1A.**

<b>Occupant Risk Factor</b>	<b>Value</b>	<b>Time</b>
<b>Occupant Impact Velocity (OIV)</b>		
Longitudinal	27.9 ft/s	at 0.1280 s on right side of interior
Lateral	14.4 ft/s	
<b>Occupant Ridedown Accelerations</b>		
Longitudinal	15.6 g	0.2228 – 0.2328 s
Lateral	5.9 g	0.1494 – 0.1594 s
<b>Theoretical Head Impact Velocity (THIV)</b>	9.7 m/s	at 0.1354 s on right side of interior
<b>Acceleration Severity Index (ASI)</b>	1.1	0.2156 – 0.2656 s
<b>Maximum 50-ms Moving Average</b>		
Longitudinal	-12.3 g	0.1885 – 0.2385 s
Lateral	-6.8 g	0.0533 – 0.1033 s
Vertical	4.3 g	0.1906 – 0.2406 s
<b>Maximum Yaw, Pitch, and Roll Angles</b>		
Yaw	43°	1.8577 s
Pitch	27°	0.8183 s
Roll	37°	1.5956 s



**General Information**

Test Agency..... Texas A&M Transportation Institute (TTI)  
 Test Standard Test No..... MASH Test 3-11  
 TTI Test No..... 612061-02-1A  
 Test Date..... 2020-09-02

**Test Article**

Type..... Longitudinal Barrier—Guardrail  
 Name..... Modified Merritt Parkway Guiderail with 4-inch Curb  
 Installation Length..... 166 ft  
 Material or Key Elements.... Metal back timber rail on steel posts and timber blockouts

**Soil Type and Condition**

..... AASHTO M147-65, grading B Soil (crushed limestone)

**Test Vehicle**

Type/Designation..... 2270P  
 Make and Model..... 2014 RAM 1500 Pickup  
 Curb..... 5040 lb  
 Test Inertial..... 5033 lb  
 Dummy..... No dummy  
 Gross Static..... 5033 lb

**Impact Conditions**

Speed.....61.5 mi/h  
 Angle.....25.1°  
 Location/Orientation.....14.2 ft upstream of post 11

**Impact Severity**

.....115 kip-ft

**Exit Conditions**

Speed.....Stopped  
 Trajectory/Heading Angle ...Against rail

**Occupant Risk Values**

Longitudinal OIV.....27.9 ft/s  
 Lateral OIV.....14.4 ft/s  
 Longitudinal Ridedown.....15.6 g  
 Lateral Ridedown.....5.9 g  
 THIV.....9.7 m/s  
 ASI.....1.1

**Max. 0.050-s Average**

Longitudinal.....-12.3 g  
 Lateral.....-6.8 g  
 Vertical.....4.3 g

**Post-Impact Trajectory**

Stopping Distance..... 17 ft downstream Against rail

**Vehicle Stability**

Maximum Yaw Angle..... 43°  
 Maximum Pitch Angle..... 27°  
 Maximum Roll Angle..... 37°  
 Vehicle Snagging..... Yes  
 Vehicle Pocketing..... Yes

**Test Article Deflections**

Dynamic..... 30.4 inches  
 Permanent..... 12.5 inches  
 Working Width..... 70.1 inches  
 Height of Working Width..... 35.5 inches

**Vehicle Damage**

VDS..... 01RFQ5  
 CDC..... 01FREW3  
 Max. Exterior Deformation..... 12.0 inches  
 OCDI..... FR0010000  
 Max. Occupant Compartment Deformation..... 4.25 inches

**Figure 5.10. Summary of Results for MASH Test 3-11 on Modified Merritt Parkway Guiderail.**



### 5.3. MASH TEST 3-10 (CRASH TEST NO. 612061-03-1)

#### 5.2.1. Test Designation and Actual Impact Conditions

MASH Test 3-10 involves a 1100C vehicle weighing 2420 lb  $\pm$  55 lb impacting the CIP of the longitudinal barrier at an impact speed of 62 mi/h  $\pm$  2.5 mi/h and an angle of 25 degrees  $\pm$  1.5 degrees. The CIP for MASH Test 3-10 on the Modified Merritt Parkway Guiderail was 5.0 ft  $\pm$  1 ft upstream of the centerline of post 9. **Error! Reference source not found.** and Figure 5.11 depict the target impact setup.



**Figure 5.11. Modified Merritt Parkway Guiderail/Test Vehicle Geometrics for Test No. 612061-03-1.**

The 1100C vehicle weighed 2421 lb, and the actual impact speed and angle were 63.0 mi/h and 24.8 degrees. The actual impact point was 4.5 ft upstream of the centerline of post 9. Minimum target IS was 51 kip-ft, and actual IS was 57 kip-ft.

#### 5.2.2. Weather Conditions

The test was performed on the morning of October 2, 2020. Weather conditions at the time of testing were as follows: wind speed: 7 mi/h; wind direction: 63 degrees (vehicle was traveling at a heading of 195 degrees); temperature: 73°F; relative humidity: 45 percent.

#### 5.2.3. Test Vehicle

Figure 5.12 shows the 2014 Nissan Versa used for the crash test. The vehicle's test inertia weight was 2421 lb, and its gross static weight was 2586 lb. The height to the lower edge of the vehicle bumper was 7.0 inches, and the height to the upper edge of the bumper was 22.25 inches. Table C.5 in Appendix C.4.1 gives additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.





**Figure 5.12. Test Vehicle before Test No. 612061-03-1.**

### 5.2.5. Test Description

Table 5.3 lists events that occurred during Test No. 612061-03-1. Figures C.7 and C.8 in Appendix C.4.2 present sequential photographs during the test.

**Table 5.3. Events during Test No. 612061-03-1.**

<b>Time (s)</b>	<b>Events</b>
-0.015	Vehicle right front tire contacts curb
0.000	Vehicle contacts rail
0.024	Post 8 and 9 deflect toward field side
0.028	Vehicle begins to redirect
0.055	Post 10 deflects toward field side
0.217	Vehicle traveling parallel with rail
0.426	Vehicle loses contact with guardrail while traveling 34.3 mi/h, trajectory of 9.2 degrees, and heading of 12.1 degrees

For longitudinal barriers, it is desirable for the vehicle to redirect and exit the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. After loss of contact with the barrier, the vehicle came to rest 120 ft downstream of the point of impact and 36 ft toward traffic lanes.

### 5.2.5. Damage to Test Installation

Figure 5.13 through Figure 5.14 show the damage to the Modified Merritt Parkway Guiderrail. The soil was disturbed at posts 2, 3, 5, 7, and 11. Post 8 had a 2½-inch gap in the soil on the traffic side, and the post was leaning 3 degrees back from vertical. Post 9 had a 6-inch gap on the traffic side, a 1½-inch gap on the field side, and was leaning 12 degrees back from vertical. The upstream traffic side of post 9 had a slight deformation. Post 10 was leaning 16 degrees back from vertical and had a slight clockwise rotation. The blockout at post 10 was split in half vertically. There was also gouging noted on the rail for the duration of contact.



Working width\* was 34.4 inches, and height of working width was 24.0 inches. Maximum dynamic deflection during the test was 16.1 inches. The maximum permanent deformation of the installation was 11.25 inches.




**Figure 5.13. Modified Merritt Parkway Guiderail after Test No. 612061-03-1.**

---

\* Per *MASH*, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.





**Figure 5.14. Damage from Post 8 to Post 11 after Test No. 612061-03-1.**

### **5.2.6. Damage to Test Vehicle**

Figure 5.15 shows the damage sustained by the vehicle. The front bumper, hood, grill, radiator and support, right front strut and tower, right front tire and rim, right control arm, right front fender, right front floor pan, right front and rear doors, right rear quarter panel, and rear bumper were damaged. The windshield sustained stress cracks radiating upward and inward from the right lower corner. No fuel tank damage was observed. Maximum exterior crush to the vehicle was 9.0 inches in the side plane at the right front corner at bumper height. Maximum occupant compartment deformation was 3.0 inches in the right front kick panel. Figure 5.16 shows the interior of the vehicle. Tables C.6 and C.7 in Appendix C.4.1 provide exterior crush and occupant compartment measurements.

### **5.2.7. Occupant Risk Factors**

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in Table 5.4. Figure C.8 in Appendix C.4.3 shows the vehicle angular displacements, and Figures C.9 through C.11 in Appendix C.4.4 show acceleration versus time traces. Figure 5.17 summarizes pertinent information from the test.



**Figure 5.15. Test Vehicle after Test No. 612061-03-1.**




**Figure 5.16. Interior of Test Vehicle after Test No. 612061-03-1.**

**Table 5.4. Occupant Risk Factors for Test No. 612061-03-1.**

<b>Occupant Risk Factor</b>	<b>Value</b>	<b>Time</b>
<b>OIV</b>		
Longitudinal	24.0 ft/s	at 0.1054 s on right side of interior
Lateral	23.0 ft/s	
<b>Occupant Ridedown Accelerations</b>		
Longitudinal	13.8 g	0.1392 – 0.1492 s
Lateral	8.7 g	0.1213 – 0.1313 s
<b>THIV</b>	9.7 m/s	at 0.1021 s on right side of interior
<b>ASI</b>	1.3	0.0517 – 0.1017 s
<b>Maximum 50-ms Moving Average</b>		
Longitudinal	-9.9 g	0.0389 – 0.0889 s
Lateral	-10.2 g	0.0342 – 0.0842 s
Vertical	2.6 g	0.0182 – 0.0682 s
<b>Maximum Yaw, Pitch, and Roll Angles</b>		
Yaw	41°	0.8146 s
Pitch	6°	0.5203 s
Roll	9°	0.1758 s





**General Information**

Test Agency..... Texas A&M Transportation Institute (TTI)  
 Test Standard Test No..... MASH Test 3-10  
 TTI Test No..... 612061-03-1  
 Test Date..... 2020-10-02

**Test Article**

Type..... Longitudinal Barrier—Guardrail  
 Name..... Modified Merritt Parkway Guiderail w/4-  
 inch Curb  
 Installation Length..... 166 ft  
 Material or Key Elements.... 166 ft  
 Metal back timber rail on steel posts and  
 timber blockouts

**Soil Type and Condition.....**

AASHTO M147-65, grading B Soil

**Test Vehicle**

Type/Designation.....  
 Make and Model..... 1100C  
 Curb..... 2014 Nissan Versa  
 Test Inertial..... 2444 lb  
 Dummy..... 2421 lb  
 Gross Static..... 165 lb  
 2586 lb

**Impact Conditions**

Speed.....63.0 mi/h  
 Angle.....24.8°  
 Location/Orientation.....4.5 ft upstream of  
 post 9

**Impact Severity**.....57 kip-ft

**Exit Conditions**

Speed.....34.3 mi/h  
 Trajectory/Heading Angle...9.2°/12.1°

**Occupant Risk Values**

Longitudinal OIV.....24.0 ft/s  
 Lateral OIV.....23.0 ft/s  
 Longitudinal Ridedown.....13.8 g  
 Lateral Ridedown.....8.7 g  
 THIV.....9.7 m/s  
 ASI.....1.3

**Max. 0.050-s Average**

Longitudinal.....-9.9 g  
 Lateral.....-10.2 g  
 Vertical.....2.6 g

**Post-Impact Trajectory**

Stopping Distance..... 120 ft downstream  
 36 ft twd traffic lanes

**Vehicle Stability**

Maximum Yaw Angle..... 41°  
 Maximum Pitch Angle..... 6°  
 Maximum Roll Angle..... 9°  
 Vehicle Snagging..... No  
 Vehicle Pocketing..... No

**Test Article Deflections**

Dynamic..... 16.1 inches  
 Permanent..... 11.25 inches  
 Working Width..... 34.4 inches  
 Height of Working Width..... 24.0 inches

**Vehicle Damage**

VDS..... 01RFQ4  
 CDC..... 01FREW4  
 Max. Exterior Deformation..... 9.0 inches  
 OCDI..... RF0000010  
 Max. Occupant Compartment  
 Deformation..... 3.0 inches

**Figure 5.17. Summary of Results for MASH Test 3-10 on Modified Merritt Parkway Guiderail with Curb.**

## Chapter 6. MERRITT PARKWAY GUIDERAIL TRANSITION

### 6.1. TEST ARTICLE DETAILS

#### 6.1.1. Installation Details

The timber rail Transition Section that abutted a concrete parapet extended 21 ft-2 inches upstream from the end of the parapet with four post spacings at 30 inches and two post spacings at 60 inches. A terminal curb section extended from the parapet approximately 20 feet upstream. It commenced 8 inches above grade, sloped downward, and terminated flush with grade just downstream of post 23.

The remained of the installation was that of the Modified Merritt Parkway Guiderail with Curb as utilized under tests 612061-02-1A (*MASH* 3-11) and -03-1 (*MASH* 3-10). To wit:

The installation was comprised of a timber single rail system supported by timber blockouts attached to steel W6×15 by 78-inch long posts embedded 53¼ inches below grade. The top of the rail was 30 inches above grade. For odd numbered posts (Nos. 3-23), the timber rails were secured to blockouts and posts with a standard steel backup plate attached to the field side of the timbers, which were in turn both attached to a splice plate attached to the posts and blockouts. For even numbered posts (Nos. 4-22) the timber rail and steel backup plates were not bolted to the posts and blockouts. A concrete parapet with an adjoining transition section was constructed on the downstream end of the system, and a sloped and flared anchor section was constructed on the upstream end. The total length of the system measured 166 ft-0 inches.

The parapet measured 16 ft long, 33 inches high above grade, and 12 inches wide at the top, stepping to 10½ inches wide at the base on the field side at 20 inches above grade. The concrete parapet was anchored with U-bars to a 16-ft long, 56-inch wide, and 18-inch deep concrete slab cast below grade.

The timber rail transition section extended 21 ft-2 inches upstream from the end of the parapet with four post spacings at 30 inches and two post spacings at 60 inches. A terminal curb section extended from the parapet approximately 20 feet upstream. It commenced 8 inches above grade, sloped downward, and terminated flush with grade just downstream of post 23.

The LON measured 100 ft with eleven posts (Nos. 3–23) spaced on 5 ft centers. A 50-foot long curb section (spanning from posts Nos. 7-17) was constructed with its face located 12 inches from the traffic side of the rail. The top of the curb was at grade as referenced to the rail height. The bottom of the curb was 4 inches below grade at the roadway elevation. The 4-inch tall, sloped-face curb was 5¾ inches wide at the bottom with a 12-inch deep by 31¾-inch wide base below grade.

The upstream anchor section measured 29 ft-½ inch in length and flared 34¼ inches to the field side while sloping down before terminating into an anchor block located below grade. The concrete anchor block measured approximately 36×36 inches × 39 inches tall and was cast 59½ inches deep into the surrounding soil.

Figure 4.1 presents the overall information on the Merritt Parkway Guiderail Transition, and Figure 6.2 provides photographs of the installation. Appendix D.1 provides further details on the Merritt Parkway Guiderail Transition. Drawings were provided by the Texas A&M

Transportation Institute (TTI) Proving Ground, and construction was performed by Bryan Construction and DMA Construction, Inc., and supervised by TTI Proving Ground personnel.

### **6.1.2. Design Modifications during Tests**

No modification was made to the transition installation during the testing phase.

### **6.1.3. Material Specifications**

The specified minimum compressive strengths of concrete were as follows:

- Parapet and foundation – 3600 psi.
- Parapet terminal transition curb – 3000 psi.
- 50 ft curb in LON – 4000 psi.
- Anchor block – 3000 psi.

Concrete samples from the parapet foundation were broken on 2020-06-01. concrete samples for the parapet, transition curb, and anchor block were broken on 2020-07-07. The reconstructed 50 ft Curb samples were broken on 2020-09-02. The average compressive strengths of the concrete were as follows:

- Parapet foundation: 4893 psi at 32 days of age.
- Parapet: 5573 psi at 46 days of age.
- Parapet terminal transition c: 5573 psi at 46 days of age.
- 50 ft curb in LON: 5187 psi at 43 days of age.
- Anchor block: 5573 psi at 46 days of age


Appendix B provides material certification documents for the materials used to install/construct the Merritt Parkway Guiderail.

### **6.1.4. Soil Conditions**

The test installation was installed in standard soil meeting grading B of AASHTO standard specification M147-65(2004) “Materials for Aggregate and Soil Aggregate Subbase, Base and Surface Courses.”

In accordance with Appendix B of *MASH*, soil strength was measured the day of the crash test. During installation of the Merritt Parkway Guiderail for full-scale crash testing, two 6-ft long W6×16 posts were installed in the immediate vicinity of the Merritt Parkway Guiderail Transition using the same fill materials and installation procedures used in the test installation and the standard dynamic test. Table D.1 in Appendix D.2 presents minimum soil strength properties established through the dynamic testing performed in accordance with *MASH* Appendix B.

As determined by the tests summarized in Appendix D.2, Table D.1, the minimum post loads required for deflections at 5 inches, 10 inches, and 15 inches, measured at a height of 25 inches, are 3940 lb, 5500 lb, and 6540 lb (90 percent of static load for the initial standard installation).



Q:\Accreditation-17025-2017\EIR-000 Project Files\612061-Pooled Fund-Merritt Parkway-Chiara Drafting, 612061 with curb\612061 w curb Drawing

Figure 6.1. Merritt Parkway Guiderail Transition Details.







**Figure 6.2. Merritt Parkway Guiderail Transition prior to Testing.**

On the day of the Crash Test No. 612061-07-1, October 7, 2020, loads on the post at deflections of 5 inches, 10 inches, and 15 inches were 9898 lbf, 10,101 lbf, and 10,404 lbf. On the day of the Crash Test No. 612061-06-1, October 12, 2020, loads on the post at deflections of 5 inches, 10 inches, and 15 inches were 7676 lbf, 8434 lbf, and 6540 lbf. Table D.2 and Table D.3 in Appendix D.2 show the strength of the backfill material in which the Merritt Parkway Guiderail Transition was installed met minimum *MASH* requirements for soil strength.

## 6.2. MASH TEST 3-20 (CRASH TEST NO. 612061-07-1)

### 6.2.1 Test Designation and Actual Impact Conditions

MASH Test 3-20 involves a 1100C vehicle weighing 2420 lb  $\pm$  55 lb impacting the CIP of the longitudinal barrier transition at an impact speed of 62 mi/h  $\pm$  2.5 mi/h and an angle of 25 degrees  $\pm$  1.5 degrees. The CIP for MASH Test 3-20 on the Merritt Parkway Guiderail Transition was 4 ft  $\pm$  1 ft upstream of edge of concrete parapet. Figure 2.3 and Figure 6.3 depict the target impact setup.



**Figure 6.3. Transition/Test Vehicle Geometrics for Test No. 612061-07-1.**

The 1100C vehicle weighed 2420 lb, and the actual impact speed and angle were 62.5 mi/h and 25.6 degrees. The actual impact point was 3.6 ft upstream of edge of concrete parapet. Minimum target IS was 51 kip-ft, and actual IS was 59 kip-ft.


### 6.2.2 Weather Conditions

The test was performed on the afternoon of October 7, 2020. Weather conditions at the time of testing were as follows: wind speed: 2 mi/h; wind direction: 44 degrees (vehicle was traveling at a heading of 195 degrees); temperature: 85°F; relative humidity: 45 percent.

### 6.2.3 Test Vehicle

Figure 6.4 shows the 2014 Nissan Versa used for the crash test. The vehicle's test inertia weight was 2420 lb, and its gross static weight was 2585 lb. The height to the lower edge of the vehicle bumper was 7.0 inches, and the height to the upper edge of the bumper was 22.25 inches. Table D.1 in Appendix D.3.1 gives additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.





**Figure 6.4. Test Vehicle before Test No. 612061-07-1.**

#### 6.2.4 Test Description

Table 6.1 lists events that occurred during Test No. 612061-07-1. Figures D.1 and D.2 in Appendix C.3.2 present sequential photographs during the test.

**Table 6.1. Events during Test No. 612061-07-1.**

<b>Time (s)</b>	<b>Events</b>
0.000	Vehicle impacts transition
0.031	Vehicle begins to redirect
0.210	Right left tire lifts off the ground
0.288	Vehicle travelling parallel to transition
0.310	Rear bumper contacts the parapet
0.444	Vehicle loses contact with transition while traveling at 41.1 mi/h, trajectory of 3.9 degrees, and heading 4.3 degrees

For longitudinal barriers, it is desirable for the vehicle to redirect and exit the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. Brakes on the vehicle were applied after the vehicle exited the test site, and the vehicle subsequently came to rest 176 ft downstream of the point of impact and 95 ft toward traffic lanes.

#### 6.2.5 Damage to Test Installation

Figure 6.5 shows the damage to the transition. There was a 1/8-inch gap in the soil on the field side of posts 28 and 29. The curb section at post 28 was pushed 1/2-inch back, and there was spalling and exposed rebar on the concrete curb section at post 29. The rail at post 29 was splintered and scuffed, and there was some cracking present on the concrete parapet. Working width\* was 19.9 inches, and height of working width was 33.0 inches. Maximum dynamic deflection during the test was 1.5 inches, and no permanent deformation was observed.

---

\* Per *MASH*, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words,





**Figure 6.5. Transition after Test No. 612061-07-1.**

### 6.2.6 Damage to Test Vehicle

Figure 6.6 shows the damage sustained by the vehicle. The front bumper, hood, radiator and support, right front fender, right front strut and tower, right front control arm, right CV joint and shaft, sway bar, tie rod end, right front tire and rim, right A-post, right front floor pan, right front door and window glass, right rear door, right rear quarter panel, and rear bumper were

---

working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.



damaged. The roof was deformed over the right B-post, and the windshield was shattered due to deformation in the right front A-post. No fuel tank damage was observed. Maximum exterior crush to the vehicle was 12.0 inches in the side plane at the right front corner at bumper height. Maximum occupant compartment deformation was 7.25 inches in the kick panel area on the right front side. Figure 6.7 shows the interior of the vehicle. Tables D.2 and D.3 in Appendix D.3.1 provide exterior crush and occupant compartment measurements.



**Figure 6.6. Test Vehicle after Test No. 612061-07-1.**




**Figure 6.7. Interior of Test Vehicle after Test No. 612061-07-1.**

### **6.2.7 Occupant Risk Factors**

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in Table 6.2. Figure D.3 in Appendix D.3.3 shows the vehicle angular displacements, and Figures D.4 through D.6 in Appendix D.3.4 show acceleration versus time traces. Figure 6.8 summarizes pertinent information from the test.

**Table 6.2. Occupant Risk Factors for Test No. 612061-07-1.**

<b>Occupant Risk Factor</b>	<b>Value</b>	<b>Time</b>
<b>OIV</b>		
Longitudinal	28.9 ft/s	at 0.0862 s on right side of interior
Lateral	31.5 ft/s	
<b>Occupant Ridedown Accelerations</b>		
Longitudinal	6.1 g	0.0863 – 0.0963 s
Lateral	9.2 g	0.0862 – 0.0962 s
<b>THIV</b>	13.3 m/s	at 0.0843 s on right side of interior
<b>ASI</b>	2.6	0.0556 – 0.1056 s
<b>Maximum 50-ms Moving Average</b>		
Longitudinal	-16.1 g	0.0276 – 0.0776 s
Lateral	-17.5 g	0.0345 – 0.0845 s
Vertical	5.6 g	0.0118 – 0.0618 s
<b>Maximum Yaw, Pitch, and Roll Angles</b>		
Yaw	41°	1.8716 s
Pitch	8°	1.9835 s
Roll	8°	1.3041 s



**General Information**

Test Agency..... Texas A&M Transportation Institute (TTI)  
 Test Standard Test No..... MASH Test 3-20  
 TTI Test No..... 612061-07-1  
 Test Date..... 2020-10-07

**Test Article**

Type..... Longitudinal Barrier—Transition  
 Name..... Merritt Parkway Guiderail Transition  
 Installation Length..... 166 ft  
 Material or Key Elements.... Metal back timber rail on steel posts and timber blockouts

**Soil Type and Condition**

..... AASHTO M147-65, grading B Soil (crushed limestone)

**Test Vehicle**

Type/Designation..... 1100C  
 Make and Model..... 2014 Nissan Versa  
 Curb..... 2414 lb  
 Test Inertial..... 2420 lb  
 Dummy..... 165 lb  
 Gross Static..... 2585 lb

**Impact Conditions**

Speed.....62.5 mi/h  
 Angle.....25.6°  
 Location/Orientation.....3.6 ft upstream of edge of concrete

**Impact Severity**

.....59 kip-ft

**Exit Conditions**

Speed.....41.1 mi/h  
 Trajectory/Heading Angle...3.9°/4.3°

**Occupant Risk Values**

Longitudinal OIV.....28.9 ft/s  
 Lateral OIV.....31.5 ft/s  
 Longitudinal Ridedown.....6.1 g  
 Lateral Ridedown.....9.2 g  
 THIV.....13.3 m/s  
 ASI.....2.6  
 Max. 0.050-s Average  
 Longitudinal.....-16.1 g  
 Lateral.....-17.5 g  
 Vertical.....5.6 g

**Post-Impact Trajectory**

Stopping Distance..... 176 ft downstream  
 95 ft twd traffic lanes

**Vehicle Stability**

Maximum Yaw Angle..... 41°  
 Maximum Pitch Angle..... 8°  
 Maximum Roll Angle..... 8°  
 Vehicle Snagging..... No  
 Vehicle Pocketing..... No

**Test Article Deflections**

Dynamic..... 1.5 inches  
 Permanent..... None  
 Working Width..... 19.9 inches  
 Height of Working Width..... 33.0 inches

**Vehicle Damage**

VDS..... 01RFQ5  
 CDC..... 01FREW5  
 Max. Exterior Deformation..... 12.0 inches  
 OCDI..... RF1101020  
 Max. Occupant Compartment Deformation..... 7.25 inches

**Figure 6.8. Summary of Results for MASH Test 3-20 on Merritt Parkway Guiderail Transition.**





### 6.3. MASH TEST 3-21 (CRASH TEST NO. 612061-06-1)

#### 6.3.1 Test Designation and Actual Impact Conditions

MASH Test 3-21 involves a 2270P vehicle weighing 5000 lb  $\pm$  110 lb impacting the CIP of the longitudinal barrier at an impact speed of 62 mi/h  $\pm$  2.5 mi/h and an angle of 25 degrees  $\pm$  1.5 degrees. The CIP for MASH Test 3-21 on the Merritt Parkway Guiderail Transition was 7 ft  $\pm$  1 ft upstream of the edge of the concrete parapet. Figure 2.4 and Figure 6.9 depict the target impact setup.



**Figure 6.9. Transition/Test Vehicle Geometrics for Test No. 612061-06-1.**

The 2270P vehicle weighed 5006 lb, and the actual impact speed and angle were 63.0 mi/h and 25.2 degrees. The actual impact point was 7.1 ft upstream of the edge of the concrete parapet. Minimum target IS was 106 kip-ft, and actual IS was 120 kip-ft.

#### 6.3.2 Weather Conditions

The test was performed on the morning of October 12, 2020. Weather conditions at the time of testing were as follows: wind speed: 8 mi/h; wind direction: 305 degrees (vehicle was traveling at a heading of 195 degrees); temperature: 82°F; relative humidity: 77 percent.

#### 6.3.3 Test Vehicle

Figure 6.10 shows the 2014 RAM 1500 pickup truck used for the crash test. The vehicle's test inertia weight was 5006 lb, and its gross static weight was 5171 lb. The height to the lower edge of the vehicle bumper was 11.75 inches, and height to the upper edge of the bumper was 27.0 inches. The height to the vehicle's center of gravity was 28.0 inches. Tables D.6 and D.7 in Appendix D.4.1 give additional dimensions and information on the vehicle. The vehicle was directed into the installation using a cable reverse tow and guidance system, and was released to be freewheeling and unrestrained just prior to impact.



**Figure 6.10. Test Vehicle before Test No. 612061-06-1.**

### 6.3.4 Test Description

Table 6.3 lists events that occurred during Test No. 612061-06-1. Figures D.7 and D.8 in Appendix D.2 present sequential photographs during the test.

**Table 6.3. Events during Test No. 612061-06-1.**

Time (s)	Events
0.000	Vehicle impacts transition
0.015	Vehicle begins to redirect
0.030	Left front tire contacts the rail and curb
0.119	Left rear tire leaves the ground
0.182	Left front tire leaves the ground
0.220	Vehicle traveling parallel with transition
0.360	Vehicle loses contact with transition while traveling at 42.1 mi/h, trajectory of 5.5 degrees, and heading of 6.9 degrees

For longitudinal barriers, it is desirable for the vehicle to redirect and exit the barrier within the exit box criteria (not less than 32.8 ft downstream from loss of contact for cars and pickups). The test vehicle exited within the exit box criteria defined in *MASH*. Brakes on the vehicle were applied at 4.25 s after impact. The vehicle subsequently came to rest 166 ft downstream of the point of impact and 24 ft toward the field side.

### 6.3.5 Damage to Test Installation

Figure 6.11 and Figure 6.12 show the damage to the transition. There was no movement noted from post 1 through post 25. The downstream rail at post 25 was lifted 7/8-inch up from level. Post 26 had a 1/4-inch gap in the soil on the field side, and it was leaning 1° toward the field side from vertical. Post 27 also had a 1/4-inch gap on the field side, and it was leaning 1° toward field side from vertical. Post 28 had a 1/2-inch gap on the field side, and was leaning 3° toward the field side from vertical. Post 29 had a 1/4-inch gap on the field side and was leaning 2° toward the field side from vertical. The rail bolts at post 29 were deformed but remained attached to the post. The curb between post 27 and 28 was pushed toward the field side 3/4-inch and large



portions of the curb were broken off and rebar exposed due to the right front tire becoming lodged between the curb and rail at the upstream end of post 28. The bolts connecting the rail to the concrete barrier were deformed and bent downstream. There was some cracking on the barrier, and the rail was splintered, gouged, and had several large pieces broken off. There were two large pieces lying on the roadway at impact measuring 46½ inches and 41 inches. A piece of 34-inch long wooden rail came to rest 37 ft downstream and 36 ft toward traffic lanes. A 34½-inch long piece of rail came to rest 50 ft downstream and in-line with the rail. A 37½-inch long piece of rail came to rest 60 ft downstream and 4 ft toward traffic lanes. Working width\* was 28.4 inches, and height of working width was 52.0 inches. Maximum dynamic deflection during the test was 4.7 inches, and maximum permanent deformation was undeterminable.




**Figure 6.11. Transition after Test No. 612061-06-1.**

---

\* Per *MASH*, “The working width is the maximum dynamic lateral position of any major part of the system or vehicle. These measurements are all relative to the pre-impact traffic face of the test article.” In other words, working width is the total barrier width plus the maximum dynamic intrusion of any portion of the barrier or test vehicle past the field side edge of the barrier.





**Figure 6.12. Field Side of Transition after Test No. 612061-06-1.**

### **6.3.6 Damage to Test Vehicle**

Figure 6.13 shows the damage sustained by the vehicle. The front bumper, hood, grill, radiator and support, right frame rail, right front upper and lower control arms, sway bar, right tie rod, right front tire and rim, right front fender, right front floor pan, right front door and window glass, right rear door, right rear cab corner, right rear exterior bed, and right rear tire and rim were damaged. The windshield sustained stress cracks radiating upward along the lower right edge of the frame. No fuel tank damage was observed. Maximum exterior crush to the vehicle was 18.0 inches in the front plane at the right front corner at bumper height. Maximum occupant compartment deformation was 6.5 inches in the right front kick panel area. Figure 6.14 shows the interior of the vehicle. Tables D.8 and D.9 in Appendix D.4.1 provide exterior crush and occupant compartment measurements.





**Figure 6.13. Test Vehicle after Test No. 612061-06-1.**




**Figure 6.14. Interior of Test Vehicle after Test No. 612061-06-1.**

### **6.3.7 Occupant Risk Factors**

Data from the accelerometers were digitized for evaluation of occupant risk, and the results are shown in Table 6.4. Figure D.9 in Appendix D.4.3 shows the vehicle angular displacements, and Figures D.10 through D.12 in Appendix D.4.4 show acceleration versus time traces. Figure 6.15 summarizes pertinent information from the test.

**Table 6.4. Occupant Risk Factors for Test No. 612061-06-1.**

<b>Occupant Risk Factor</b>	<b>Value</b>	<b>Time</b>
<b>Occupant Impact Velocity (OIV)</b> Longitudinal Lateral	25.3 ft/s 25.3 ft/s	at 0.1123 s on right side of interior
<b>Occupant Ridedown Accelerations</b> Longitudinal Lateral	9.8 g 8.5 g	0.2598 – 0.2698 s 0.1123 – 0.1223 s
<b>Theoretical Head Impact Velocity (THIV)</b>	10.8 m/s	at 0.1092 s on right side of interior
<b>Acceleration Severity Index (ASI)</b>	1.4	0.0978 – 0.1478 s
<b>Maximum 50-ms Moving Average</b> Longitudinal Lateral Vertical	-10.1 g -10.0 g 4.1 g	0.0186 – 0.0686 s 0.0596 – 0.1096 s 0.2725 – 0.3225 s
<b>Maximum Yaw, Pitch, and Roll Angles</b> Yaw Pitch Roll	45° 10° 21°	0.9265 s 0.4281 s 0.7154 s



**General Information**

Test Agency..... Texas A&M Transportation Institute (TTI)  
 Test Standard Test No..... MASH Test 4-21  
 TTI Test No..... 612061-06-1  
 Test Date..... 2020-10-12

**Test Article**

Type..... Longitudinal Barrier—Transition  
 Name..... Merritt Parkway Guiderail Transition  
 Installation Length..... 166 ft  
 Material or Key Elements.... Metal back timber rail on steel posts and timber blockouts

**Soil Type and Condition**..... AASHTO M147-65, grading B Soil (crushed limestone)

**Test Vehicle**

Type/Designation..... 2270P  
 Make and Model..... 2014 RAM 1500 Pickup  
 Curb..... 5076 lb  
 Test Inertial..... 5006 lb  
 Dummy..... 165 lb  
 Gross Static..... 5171 lb

**Impact Conditions**

Speed.....63.0 mi/h  
 Angle.....25.2°  
 Location/Orientation.....7.1 ft upstream of edge of concrete

**Impact Severity** .....120 kip-ft

**Exit Conditions**

Speed.....42.1 mi/h  
 Trajectory/Heading Angle...5.5°/6.9°

**Occupant Risk Values**

Longitudinal OIV.....25.3 ft/s  
 Lateral OIV.....25.3 ft/s  
 Longitudinal Ridedown.....9.8 g  
 Lateral Ridedown.....8.5 g  
 THIV.....10.8 m/s  
 ASI.....1.4

**Max. 0.050-s Average**

Longitudinal.....-10.1 g  
 Lateral.....-10.0 g  
 Vertical.....4.1

**Post-Impact Trajectory**

Stopping Distance..... 166 ft downstream  
 24 ft twd field side

**Vehicle Stability**

Maximum Yaw Angle..... 45°  
 Maximum Pitch Angle..... 10°  
 Maximum Roll Angle..... 21°  
 Vehicle Snagging..... No  
 Vehicle Pocketing..... No

**Test Article Deflections**

Dynamic..... 4.7 inches  
 Permanent..... Undeterminable  
 Working Width..... 28.4 inches  
 Height of Working Width..... 52.0 inches

**Vehicle Damage**

VDS..... 01 RFQ5  
 CDC..... 01FREW5  
 Max. Exterior Deformation..... 18.0 inches  
 OCDI..... RF0031330  
 Max. Occupant Compartment Deformation..... 6.5 inches

**Figure 6.15. Summary of Results for MASH Test 4-21 on Merritt Parkway Guiderail Transition.**

*This page intentionally left blank.*



## Chapter 7. SUMMARY AND CONCLUSIONS

### 7.1. ASSESSMENT OF TEST RESULTS

#### 7.1.1 Merritt Parkway Guiderail with 4-inch Curb

Two crash tests were performed on the Merritt Parkway Guiderail with 4-inch curb. These tests were in accordance with *MASH* Tests 3-10 and 3-11 for longitudinal barriers. Table 7.2 and Table 7.2 provide an assessment of each test based on the applicable safety evaluation criteria for *MASH* TL-3 longitudinal barriers. The Merritt Parkway Guiderail with 4-inch curb performed acceptably for *MASH* Test 3-10. However, during *MASH* Test 3-11, the longitudinal occupant ridedown acceleration exceeded the limit specified in *MASH*.

#### 7.1.2 Modified Merritt Parkway Guiderail with 4-inch Curb

The Merritt Parkway Guiderail with 4-inch curb was modified by decreasing the post spacing in the LON from 10 ft to 5 ft by adding extra posts that are not attached to the Guiderail between each pair of posts that are bolted to the guiderail.

*MASH* Tests 3-10 and 3-11 were performed on the Modified Merritt Parkway Guiderail with 4-inch curb. Table 7.3 and Table 7.4 provide an assessment of each test.

#### 7.1.3 Merritt Parkway Guiderail Transition

Two crash tests were performed on the Merritt Parkway Guiderail Transition. These tests were in accordance with *MASH* Tests 3-20 and 3-21 for transitions. Table 7.5 and Table 7.6 provide an assessment of each test based on the applicable safety evaluation criteria for *MASH* TL-3 transitions.

### 7.2. CONCLUSIONS

Table 7.7 shows that the Modified Merritt Parkway Guiderail with 4-inch curb met the performance criteria for *MASH* TL-3 longitudinal barriers. Table 7.8 shows that the Merritt Parkway Guiderail Transition met the performance criteria for *MASH* TL-3 transitions.

**Table 7.1. Performance Evaluation Summary for MASH Test 3-10 on Merritt Parkway Guiderail.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 612061-03-1

Test Date: 2020-07-08

<b>MASH Test 3-10 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The Merritt Parkway Guiderail with 4-inch curb contained and redirected the 1100C vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 16.4 inches.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present undue hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 3.5 inches in the right front kick panel.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 1100C vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 7° and 6°.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 23.6 ft/s, and lateral OIV was 19.7 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 11.8 g, and lateral occupant ridedown acceleration was 10.7 g.	Pass

**Table 7.2. Performance Evaluation Summary for MASH Test 3-11 on Merritt Parkway Guiderail.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 612061-02-1

Test Date: 2020-07-10

<b>MASH Test 3-11 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The Merritt Parkway Guiderail with 4-inch curb contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 26.2 inches.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	None of the fragments, or other debris from the test article penetrated or showed potential for penetrating the occupant compartment, or present undue hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 2.0 inches in the right front firewall area.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 17° and 17°.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 19.4 ft/s, and lateral OIV was 14.4 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 25.5 g, and lateral occupant ridedown acceleration was 14.2 g.	Fail

**Table 7.3. Performance Evaluation Summary for MASH Test 3-10 on Modified Merritt Parkway Guiderail.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 612061-03-1

Test Date: 2020-10-02

<b>MASH Test 3-10 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The Modified Merritt Parkway Guiderail with 4-inch curb contained and redirected the 1100C vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 16.1 inches.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present undue hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 3.0 inches in the right front kick panel.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 1100C vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 9° and 6°.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 24.0 ft/s, and lateral OIV was 23.0 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 13.8 g, and lateral occupant ridedown acceleration was 8.7 g.	Pass



**Table 7.4. Performance Evaluation Summary for MASH Test 3-11 on Modified Merritt Parkway Guiderail.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 612061-02-1A

Test Date: 2020-09-02

<b>MASH Test 3-11 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The Modified Merritt Parkway Guiderail with 4-inch curb contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 30.4 inches.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	None of the fragments, or other debris from the test article penetrated or showed potential for penetrating the occupant compartment, or present undue hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 4.25 inches in the right front firewall area.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 37° and 27°.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 27.9 ft/s, and lateral OIV was 14.4 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 15.6 g, and lateral occupant ridedown acceleration was 5.9 g.	Pass

**Table 7.5. Performance Evaluation Summary for MASH Test 3-10 on Merritt Parkway Guiderail Transition.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 612061-07-1

Test Date: 2020-10-07

<b>MASH Test 3-20 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The Merritt Parkway Guiderail Transition contained and redirected the 1100C vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 1.5 inches.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present undue hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 7.25 inches in the kick panel area on the right front side.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 1100C vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 8° and 8°.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 28.9 ft/s, and lateral OIV was 31.5 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 6.1 g, and lateral occupant ridedown acceleration was 9.2 g.	Pass

**Table 7.6. Performance Evaluation Summary for MASH Test 3-21 on Merritt Parkway Guiderail Transition.**

Test Agency: Texas A&amp;M Transportation Institute

Test No.: 612061-06-1

Test Date: 2020-10-12

<b>MASH Test 3-21 Evaluation Criteria</b>	<b>Test Results</b>	<b>Assessment</b>
<b><u>Structural Adequacy</u></b>		
A. <i>Test article should contain and redirect the vehicle or bring the vehicle to a controlled stop; the vehicle should not penetrate, underride, or override the installation although controlled lateral deflection of the test article is acceptable.</i>	The Merritt Parkway Guiderail Transition contained and redirected the 2270P vehicle. The vehicle did not penetrate, underride, or override the installation. Maximum dynamic deflection during the test was 4.7 inches.	Pass
<b><u>Occupant Risk</u></b>		
D. <i>Detached elements, fragments, or other debris from the test article should not penetrate or show potential for penetrating the occupant compartment, or present an undue hazard to other traffic, pedestrians, or personnel in a work zone.</i>	No detached elements, fragments, or other debris were present to penetrate or show potential for penetrating the occupant compartment, or present undue hazard to others in the area.	Pass
<i>Deformations of, or intrusions into, the occupant compartment should not exceed limits set forth in Section 5.2.2 and Appendix E of MASH.</i>	Maximum occupant compartment deformation was 6.5 inches in the right front kick panel area.	
F. <i>The vehicle should remain upright during and after collision. The maximum roll and pitch angles are not to exceed 75 degrees.</i>	The 2270P vehicle remained upright during and after the collision event. Maximum roll and pitch angles were 21° and 10°.	Pass
H. <i>Occupant impact velocities (OIV) should satisfy the following limits: Preferred value of 30 ft/s, or maximum allowable value of 40 ft/s.</i>	Longitudinal OIV was 25.3 ft/s, and lateral OIV was 25.3 ft/s.	Pass
I. <i>The occupant ridedown accelerations should satisfy the following limits: Preferred value of 15.0 g, or maximum allowable value of 20.49 g.</i>	Longitudinal occupant ridedown acceleration was 9.8 g, and lateral occupant ridedown acceleration was 8.5 g.	Pass

**Table 7.7. Assessment Summary for MASH TL-3 Tests on Modified Merritt Parkway Guiderail.**

<b>Evaluation Factors</b>	<b>Evaluation Criteria</b>	<b>Test No. 612061-03-1</b>	<b>Test No. 612061-02-1A</b>
<b>Structural Adequacy</b>	A	S	S
<b>Occupant Risk</b>	D	S	S
	F	S	S
	H	S	S
	I	S	S
<b>Test No.</b>		<b>MASH Test 3-10</b>	<b>MASH Test 3-11</b>
<b>Pass/Fail</b>		Pass	Pass

Note: S = Satisfactory; N/A = Not Applicable.

**Table 7.8. Assessment Summary for MASH TL-3 Tests on Merritt Parkway Guiderail Transition.**

<b>Evaluation Factors</b>	<b>Evaluation Criteria</b>	<b>Test No. 612061-07-1</b>	<b>Test No. 612061-06-1</b>
<b>Structural Adequacy</b>	A	S	S
<b>Occupant Risk</b>	D	S	S
	F	S	S
	H	S	S
	I	S	S
<b>Test No.</b>		<b>MASH Test 3-20</b>	<b>MASH Test 3-21</b>
<b>Pass/Fail</b>		Pass	Pass

Note: S = Satisfactory; N/A = Not Applicable.



## REFERENCES

1. AASHTO/FHWA Joint Implementation Agreement for Manual for Assessing Safety Hardware (*MASH*). <https://design.transportation.org/wp-content/uploads/sites/21/2018/06/MASH-Implementation-Agreement-Final.pdf>, January 7, 2016 (last access 2020-10-21).
2. AASHTO. *Manual for Assessing Roadside Safety Hardware, Second Edition*. American Association of State Highway and Transportation Officials: Washington, DC, 2016.
3. D. Lance Bullard, Wanda L. Menges, and Dean C. Alberson. *Testing and Evaluation of the Merritt Parkway Guiderail*. Test Report 405501. Texas A&M Transportation Institute, College Station, TX, April 1996.
4. H. E. Ross, Jr., D. L. Sicking, and R. A. Zimmer, "Recommended Procedures for the Safety Performance Evaluation of Highway Features," *NCHRP Report 350*. National Cooperative Highway Research Program, Washington, DC, 1993.

*This page intentionally left blank.*

# **APPENDIX A. MERRITT PARKWAY GUIDERAIL WITH NO CURB**

### Notes

**1a.** Drill Ø24" holes for Posts. Backfill Post holes and around Anchor Block with AASHTO M147-65(2004), grade B crushed limestone road base, compacted to MASH standard.

**1b.** Threads not shown on Bolts, Nuts, etc for clarity.

**1c. Material:**


**Steel:** All steel posts, back-up rails, splice plates and channel rubrails which are to be used as "Weathering Steel", shall meet the requirements of ASTM A588. The fabricator shall notify the manufacturer that it is "Weathering Steel" (structural steel for use in bare, unpainted applications) and that the steel shall not be marked with paint or steel die stamped, but identification shall be stenciled with permanent ink. The dimensions of each component shall conform to the plans and ASTM A6. All steel posts shall be galvanized after fabrication to meet the requirements of ASTM A123 and conform to the galvanizing limits and tolerances shown on the plans. A single ¾" diameter hole may be drilled 2" from the top of each post, in the center of the web, to facilitate the galvanizing process on the bottom of all posts.


**Timber:** All timber rail and block-out components shall conform with the following:

- a) Commercial lumber grade No. 1 or better after treatment;
- b) AASHTO M 168;
- c) Minimum stress rating of 1350 psi
- d) Rough sawn (non-planed) or S4S (surface four side) Southern Yellow Pine or Douglas Fir- Larch with nominal dimensions as indicated on the plans. Variations in the size of any dimension shall not be more than ± ¼"
- e) All timber components shall be pressure treated with CCA or ACZA depending on species supplied conforming to AWWPA Standard P5 to a minimum net retention of 0.60lb/cubic foot in the assay zone in accordance with AWWPA Standard C14.
- f) All timber components shall be fabricated (including but not necessarily limited to cutting, drilling, dapping and chamfering) prior to treatment.
- g) All timber components shall be free of excess preservative and solvent at the conclusion of the treating process. Post treatment cleaning shall be by expansion bath or steaming in accordance with AWWPA Standard C2;
- h) Kiln or air dried to a maximum moisture content of 25% after treatment (KDAT - 25);
- i) Grade-marked after treatment by an agency certified by the American Lumber Standard Committee (ALSC).

**Fasteners:**


- a) Round head bolts shall be manufactured in accordance with the sizes designated on the plans, the geometric specifications included in ANSI B18.5.1.2.2 and the material specifications for ASTM A588 steel. All round head bolts shall be marked with the manufacturers symbol and A588.
- b) Hex Lag Screws shall be manufactured in accordance with ASTM A307 Grade A specifications. All Hex Lag Screws shall be hot-dipped galvanized in accordance with ASTM A153 Class C.
- c) Nuts, and Washers shall be ASTM A588 steel.

		Roadside Safety and Physical Security Division - Proving Ground	
Project #612061-02-1 and -03-1		Merritt Parkway	
Drawn by GESWS		Scale 1:250	
		2020-07-10	
		Sheet 1 of 12 Notes	




C:\Accreditation-17025-2017\EIR-000 Project Files\612061-Pooled Fund\Merritt Parkway-Chiara\Drafting, 612061 with curb\612061 w curb Drawing






Roadside Safety and Physical Security Division - Proving Ground

Project #612061-02-1 and -03-1	Merritt Parkway	2020-07-10
Drawn by GESWS	Scale 1:50	Sheet 3 of 12 Transition Details




Roadside Safety and  
Physical Security Division -  
Proving Ground

Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-10
Drawn by GESWS	Scale 1:10	Sheet 4 of 12 Curb Sections	





C:\accreditation-17025-2017\EIR-000 Project Files\612061-Pooled Fund\Merritt Parkway-Chiara\Drafting, 612061 with curb\612061 w curb Drawing


# Anchor Block




## Elevation Views



**U-bar, bottom**  
Grade 60 rebar



**U-bar, middle**  
Grade 60 rebar




**U-bar, top**  
Grade 60 rebar



Roadside Safety and  
Physical Security Division -  
Proving Ground


Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-10
Drawn by GESWS	Scale 1:20	Sheet 6 of 12 Anchor Block	



Roadside Safety and  
Physical Security Division -  
Proving Ground


Project #612061-02-1 and -03-1 Merritt Parkway		2020-07-10
Drawn by GESWS	Scale 1:20	Sheet 7 of 12 Post and Rail Assemblies






Roadside Safety and Physical Security Division - Proving Ground

Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-10
Drawn by GESWS	Scale 1:20	Sheet 8 of 12 Rail Parts	




Roadside Safety and Physical Security Division - Proving Ground


Project #612061-02-1 and -03-1	Merritt Parkway	2020-07-10
Drawn by GESWS	Scale 1:20	Sheet 9 of 12 Transition Rails



Roadside Safety and  
Physical Security Division -  
Proving Ground

Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-10
Drawn by GESWS	Scale 1:20	Sheet 10 of 12 Backup Plates	











**Table A.1. Summary of Strong Soil Test Results for Establishing Installation Procedure.**





Percent Finer Vs. Grain Size of Fill Soil for Dynamic and Static Load Tests



**Dynamic Test Installation Details**




**Static Load Test Installation Details**




Date .....	2008-11-05
Test Facility and Site Location .....	TTI Proving Ground, 3100 SH 47, Bryan, TX 77807
In Situ Soil Description (ASTM D2487) .....	Sandy gravel with silty fines
Fill Material Description (ASTM D2487) and sieve analysis .....	AASHTO M147 Grade B Soil-Aggregate (see sieve analysis above)
Description of Fill Placement Procedure .....	6-inch lifts tamped with a pneumatic compactor
Bogie Weight .....	5009 lb
Impact Velocity .....	20.5 mph

**Table A.2. Test Day Static Soil Strength Documentation for Test No. 612061-03-1.**



Date.....	<u>2020-07-08 for Test No. 612061-03-1</u>
Test Facility and Site Location .....	<u>TTI Proving Ground – 3100 SH 47, Bryan, Tx</u>
In Situ Soil Description (ASTM D2487).....	<u>Sandy gravel with silty fines</u>
Fill Material Description (ASTM D2487) and sieve analysis ..	<u>AASHTO M147 Grade B Soil-Aggregate</u>
Description of Fill Placement Procedure.....	<u>6-inch lifts tamped with a pneumatic compactor</u>

**Table A.2. Test Day Static Soil Strength Documentation for Test No. 612061-02-1.**



Date.....	<u>2020-07-10 for Test No. 612061-02-1</u>
Test Facility and Site Location .....	<u>TTI Proving Ground – 3100 SH 47, Bryan, Tx</u>
In Situ Soil Description (ASTM D2487).....	<u>Sandy gravel with silty fines</u>
Fill Material Description (ASTM D2487) and sieve analysis ..	<u>AASHTO M147 Grade B Soil-Aggregate</u>
Description of Fill Placement Procedure.....	<u>6-inch lifts tamped with a pneumatic compactor</u>





### A.3 MASH TEST 3-11 (CRASH TEST NO. 612061-02-1)

#### A.3.1. Vehicle Properties and Information

**Table A.6. Vehicle Properties for Test No. 612061-02-1.**

Date: 2020-12-17 Test No.: 612061-02-1 VIN No.: 1C66RFT8ES100464  
 Year: 2014 Make: RAM Model: 1500  
 Tire Size: 265/70 R 17 Tire Inflation Pressure: 35 psi  
 Tread Type: Highway Odometer: 210267  
 Note any damage to the vehicle prior to test: None

• Denotes accelerometer location.


NOTES: None

Engine Type: V-8  
 Engine CID: 5.7 L

Transmission Type:  
 Auto or  Manual  
 FWD  RWD  4WD

Optional Equipment:  
None

Dummy Data:  
 Type: 50th percentile male  
 Mass: 165 lb  
 Seat Position: Front passenger



Geometry:		inches	
A	78.50	F	40.00
B	74.00	G	28.50
C	227.50	H	61.75
D	44.00	I	11.75
E	140.50	J	27.00
		K	20.00
		L	30.00
		M	68.50
		N	68.00
		O	46.00
		P	3.00
		Q	30.50
		R	18.00
		S	13.00
		T	77.00
		U	26.75
		V	30.25
		W	61.75
		X	79.00
Wheel Center Height Front	14.75	Wheel Well Clearance (Front)	6.00
Wheel Center Height Rear	14.75	Wheel Well Clearance (Rear)	9.25
		Bottom Frame Height - Front	12.50
		Bottom Frame Height - Rear	22.50

RANGE LIMIT: A=78 ±2 inches; C=237 ±13 inches; E=148 ±12 inches; F=39 ±3 inches; G = > 28 inches; H = 63 ±4 inches; O=43 ±4 inches; (M+N)/2=67 ±1.5 inches

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front	3700	M <sub>front</sub>	2859	2809
Back	3900	M <sub>rear</sub>	2103	2203
Total	6700	M <sub>total</sub>	4962	5012
				2894
				2283
				5177

(Allowable Range for TIM and GSM = 5000 lb ±110 lb)

Mass Distribution:	lb	LF:	RF:	LR:	RR:
		1396	1413	1132	1071

**Table A.7. Measurements of Vehicle Vertical Center of Gravity for Test No. 612061-02-1.**

Date: 2020-12-17 Test No.: 612061-02-1 VIN: 1C66RFT8ES100464  
 Year: 2014 Make: RAM Model: 1500  
 Body Style: Quad Cab Mileage: 210267  
 Engine: 5.7 L V-8 Transmission: Automatic  
 Fuel Level: Empty Ballast: 170 (440 lb max)  
 Tire Pressure: Front: 35 psi Rear: 35 psi Size: 265/70 R 17

Measured Vehicle Weights: (lb)					
LF:	<u>1396</u>		RF:	<u>1413</u>	Front Axle: <u>2809</u>
LR:	<u>1132</u>		RR:	<u>1071</u>	Rear Axle: <u>2203</u>
Left:	<u>2528</u>		Right:	<u>2484</u>	Total: <u>5012</u>
					5000 ±110 lb allowed
Wheel Base:	<u>140.50</u>	inches	Track: F:	<u>68.50</u>	inches R: <u>68.00</u> inches
	<u>148</u>	±12 inches allowed		Track = (F+R)/2 = <u>67</u> ±1.5 inches allowed	
Center of Gravity, SAE J874 Suspension Method					
X:	<u>61.76</u>	inches	Rear of Front Axle	(63 ±4 inches allowed)	
Y:	<u>-0.30</u>	inches	Left -	Right +	of Vehicle Centerline
Z:	<u>28.50</u>	inches	Above Ground	(minumum 28.0 inches allowed)	

Hood Height: 46.00 inches Front Bumper Height: 27.00 inches  
 43 ±4 inches allowed

Front Overhang: 40.00 inches Rear Bumper Height: 30.00 inches  
 39 ±3 inches allowed

Overall Length: 227.50 inches  
 237 ±13 inches allowed

**Table A.8. Exterior Crush Measurements for Test No. 612061-02-1.**

Date: 2020-12-17 Test No.: 612061-02-1 VIN No.: 1C66RFT8ES100464  
 Year: 2014 Make: RAM Model: 1500

**VEHICLE CRUSH MEASUREMENT SHEET<sup>1</sup>**

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____	Bowing: B1 _____ X1 _____
Corner shift: A1 _____	B2 _____ X2 _____
A2 _____	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} =$ _____
< 4 inches _____	
≥ 4 inches _____	

Note: Measure C<sub>1</sub> to C<sub>6</sub> from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L**	C <sub>1</sub>	C <sub>2</sub>	C <sub>3</sub>	C <sub>4</sub>	C <sub>5</sub>	C <sub>6</sub>	±D
		Width*** (CDC)	Max**** Crush								
1	Front plane at bmp ht	12	16	48	-	-	-	-	-	-	10
2	Side plane at bmp ht	12	12	48	-	-	-	-	-	-	68
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

<sup>1</sup>Table taken from National Accident Sampling System (NASS).

\*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




\*\*Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

\*\*\*Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

**Table A.9. Occupant Compartment Measurements for Test No. 612061-02-1.**

Date: 2020-12-17 Test No.: 612061-02-1 VIN No.: 1C66RFT8ES100464  
 Year: 2014 Make: RAM Model: 1500




\*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.


**OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT**

	Before	After (inches)	Differ.
A1	65.00	65.00	0.00
A2	63.00	63.00	0.00
A3	65.50	65.50	0.00
B1	45.00	45.00	0.00
B2	38.00	38.00	0.00
B3	45.00	45.00	0.00
B4	39.50	39.50	0.00
B5	43.00	43.00	0.00
B6	39.50	39.50	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	20.00	-6.00
D1	11.00	11.00	0.00
D2	0.00	0.00	0.00
D3	11.50	11.50	0.00
E1	61.50	64.25	2.75
E2	63.50	63.50	0.00
E3	63.50	63.50	0.00
E4	63.50	63.50	0.00
F	59.00	59.00	0.00
G	59.00	59.00	0.00
H	37.50	37.50	0.00
I	37.50	36.50	-1.00
J*	25.00	20.00	-5.00

### A.4.2. Sequential Photographs



0.000 s



0.100 s



0.200 s



0.300 s



**Figure A.7. Sequential Photographs for Test No. 612061-02-1 (Overhead and Frontal Views).**






0.400 s



0.500 s



0.600 s



0.700 s



**Figure A.7. Sequential Photographs for Test No. 612061-02-1 (Overhead and Frontal Views) (Continued).**





0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s




0.300 s




0.700 s

**Figure A.8. Sequential Photographs for Test No. 612061-02-1 (Rear View).**




Axes are vehicle-fixed.  
Sequence for determining orientation:

1. Yaw.
2. Pitch.
3. Roll.




Test Number: 612061-02-1  
 Test Standard Test Number: MASH Test 3-11  
 Test Article: Merritt Parkway Guiderail with No Curb  
 Test Vehicle: 2014 RAM 1500 Pickup  
 Inertial Mass: 5012 lb  
 Gross Mass: 5177 lb  
 Impact Speed: 62.4 mi/h  
 Impact Angle: 24.3°

**Figure A.9. Vehicle Angular Displacements for Test No. 612061-02-1.**




**Figure A.10. Vehicle Longitudinal Accelerometer Trace for Test No. 612061-02-1 (Accelerometer Located at Center of Gravity).**



**Figure A.11. Vehicle Lateral Accelerometer Trace for Test No. 612061-02-1 (Accelerometer Located at Center of Gravity).**





**Figure A.12. Vehicle Vertical Accelerometer Trace for Test No. 612061-02-1 (Accelerometer Located at Center of Gravity).**

*This page intentionally left blank.*

# APPENDIX B. SUPPORTING CERTIFICATION DOCUMENTS

**OLYMPIC STEEL**  
 5080 RICHMOND ROAD  
 BEDFORD HEIGHTS, OH 44146 USA  
 PHONE: 216-292-3800

## METALLURGICAL TEST REPORT

>>>>> CERTIFICATE OF ANALYSIS AND TESTS <<<<<<

Sold To: AMERICAN TIMBER AND STEEL  
 4832 PLANK RD.  
 NORWALK, OH 44857

Ship To: AMERICAN TIMBER AND STEEL  
 4832 PLANK RD.  
 NORWALK, OH 44857

Sales Order: 614083 - 02	B/L No: 983730	Release: 3	Date: 20-May-2020
Reference: FORRAI, HALLIE (11855) 2nd B/L:		Cus Ord #: 21885	
		Cus Name: AMERICAN TIMBER AND STEEL	

**Description of Material and Specification**

Hot Rolled Sheet A606/606 3.75IN x 48IN x 117IN	TAG#: 27719332,27719330,27719331,27719333,27719334,27719335, 27719336,27719337,27719338
	HEAT#: 32016780/STEEL DYNAMICS, INC. - FLAT ROLLED
	MC # 27699054
	MS # 20B528734

**Chem Elem Symbol / Elem Content Value:**

<C : .05> <MN : .86> <P : .02> <S : .001> <SI : .45> <AL : .035> <V : .031> <CB : .002> <CU : .33> <NI : .16>  
 <CR : .43> <MO : .02> <N : .009> <TI : .001> <B : 0> <CA : .002> <ZR : .0008> <PB : 0> <SN : .006>

YIELD STRENGTH	MIN:	60800 PSI	MAX	60800 PSI
TENSILE STRENGTH	MIN:	76100 PSI	MAX	76100 PSI
ELONGATION 2"	MIN:	34 %	MAX	34 %

We hereby certify the above is correct as contained in the records of the corporation

*Dianna Romo*

\_\_\_\_\_  
 Branch Certification Manager

USER: REPORTS@SEMSP01  
 REPORT: ST\_MSR\_OSI

20-May-2020 4:44 AM  
 Page 2 of 2

**OLYMPIC STEEL**  
5080 RICHMOND ROAD  
BEDFORD HEIGHTS, OH 44146 USA  
PHONE: 216-292-3800

### METALLURGICAL TEST REPORT

>>>>> CERTIFICATE OF ANALYSIS AND TESTS <<<<<<

Sold To: AMERICAN TIMBER AND STEEL  
4832 PLANK RD.  
NORWALK, OH 44857

Ship To: AMERICAN TIMBER AND STEEL  
4832 PLANK RD.  
NORWALK, OH 44857

Sales Order: 601477 - 02      B/L No: 962816      Release: 2      Date: 18-Feb-2020  
Reference: FORRAI, HALLIE (11855) 2nd B/L:      Cus Ord #: 21392  
Cus Name: AMERICAN TIMBER AND STEEL

#### Description of Material and Specification

Hot Rolled Sheet A1018/A36  
.375IN x 49IN x 117IN

TAG#: 27528647,27528648,27528649,27528646,27528650,27528651

HEAT#: 247973/NORTH STAR BLUESCOPE STEEL LLC

MC # 27494860

MS # 1995323

#### Chem Elem Symbol / Elem Content Value:

<C : .2> <MN : .53> <P : .01> <S : .002> <SI : .08> <AL : .02> <V : .001> <CU : .12> <NI : .06> <CR : .07> <MO : .01> <N : .006> <TI : .001> <B : 0> <CA : .001> <SN : 0> <NB : 0>

YIELD STRENGTH	MIN:	43600	PSI	MAX	54000	PSI
TENSILE STRENGTH	MIN:	74100	PSI	MAX	75200	PSI
ELONGATION 2"	MIN:	40.4	%	MAX	42	%

We hereby certify the above is correct as contained in the records of the corporation



Branch Certification Manager

USER: REPORTS@SEMSP01  
REPORT: ST\_MSR\_OSI

18-Feb-2020 6:05 PM  
Page 2 of 2

American Timber and Steel Co.  
4832 Plank Rd. P.O. Box 767  
Norwalk, OH 44857  
PHONE: 419-668-1610 FAX: 419-668-7535



MATERIAL TEST REPORT

Customer: Bryan Construction Company  
P.O. Box 4087  
Bryan, TX 77805

Customer P.O. 302-10  
Shipped to: Bryan, TX  
Project: #302 TTI Merritt Parkway  
ATS Order No.: 263300

MILL SERIAL# / HEAT#	LOT#	QUANTITY	PART DESCRIPTION	MATERIAL TYPE	DATE OF MANUFACTURE
32016780	27719330 - 27719338	39	3/8" x 6" x 114" MP RAIL PLATE (CORTEN) - 4906114-3400	A606	4/28/2020
247973	27528646 - 27528651	2	3/8" x 6" x 114" MP RAIL PLATE (HDG) - 4906114-3200	A1018 / A36	4/28/2020
B160675 / 5505477607 / B166884 / B160678	-	48	W6x15# - 6' 6" MP (2H) I-BEAM POST (CORTEN/HDG) - MP00078-7901	A588	5/15/2020
A175660 / B175825 / B171455	-	2	W6x15# - 6' 6" MP (2H) I-BEAM POST (HDG) - MP00078-7201	A992	5/15/2020
247973	27528646 - 27528651	2	3/8" x 6" x 30" MP SPLICE PLATE (HDG) - 4906030-31MP	A1018 / A36	4/28/2020
DL17105083	217962	24	5/8" x 7" CARRIAGE BOLT (CORTEN) DOM - 4958070-2400	A242	-
JK17105350	217961	4	5/8" x 7" CARRIAGE BOLT (HDG) DOM - 4958070-2201	F1554-36	-
198530	D7926	96	5/8" FLAT WASHER (CORTEN) DOM - 4958001-9909	F436	-
0017266	-	4	5/8" FLAT WASHER (HDG) DOM - 4958000-6101	F844	-
DL14104775	407090B	96	5/8" HEX NUT (CORTEN) DOM - 4958110-9900	AWWA C111	-
62148230	P38707 R71433-01	4	5/8" HEX NUT (HDG) DOM - 4958000-8101	A563	-
10592090 / DL18100861	86911 / 107531	304	3/4" x 8-1/2" CARRIAGE BOLT (CORTEN) DOM - 4934090-9900	AWWA C111	-
100101783	32693	20	3/4" x 8-1/2" CARRIAGE BOLT (HDG) DOM - 4934085-2101	A325	-
227567 / 198520	286127 / D7926	304	3/4" FLAT WASHER (CORTEN) DOM - 4934000-9900	F436 T3	-
9515612/9514538 / 21933130	P38363 R69206 / P39299 R73245	20	3/4" FLAT WASHER (HDG) DOM - 4934000-6101	F436-10	-
75068613	5/104088	304	3/4" HEX NUT (CORTEN) DOM - 4934100-9900	A563	-
75070667 / 62150514 / 75078628	P38936 R71968 / P38696 R72790 / P39289 R73494	20	3/4" HEX NUT (HDG) DOM - 4934000-8101	A563	-
481990	-	1	WT15x86.5# - 24" MP END ANCHOR T MOUNT (HDG) - MPWT150-9101	A992	5/4/2020
32016780	27719330 - 27719338	37	3/8" x 6" x 30" MP SPLICE PLATE (CORTEN) - 4906030-34MP	A606	4/28/2020
32016780	27719329	3	3/8" x 6" x 162" MP LEADING END PLATE (CORTEN) - 4906162-3401	A606	5/26/2020
DL18104710	92212	10	5/8" x 12" CARRIAGE BOLT (CORTEN) DOM - 4958120-2401	A242	-
DL17105083	217962	62	5/8" x 6" CARRIAGE BOLT (CORTEN) DOM - 4958060-2400	A242	5/27/2020
10575880	32361	234	5/8" x 4" LAG BOLT (CORTEN) DOM - 4958040-9900	AWWA C111	-
DL18109063	32688	12	5/8" x 4" LAG BOLT (HDG) DOM - 4958040-3101	A325	-

All steel used in the manufacture is of Domestic Origin, "Made and Milled in the United States"  
Supporting documentation included for verification of Mill Test Reports

By:   
Tristan Hildebrandt  
Project Engineer  
American Timber and Steel Corp.

STATE OF OHIO: COUNTY OF HURON  
Sworn to and subscribed before me, a Notary Public,  
On this 10th day of June, 2020



Kristen Baker  
NOTARY PUBLIC  
STATE OF OHIO  
Comm. Expires  
June 6, 2023  
Recorded in  
Erie County



TR No. 612061-08-01

106

2024-02-06



**Steel Dynamics, Inc.**  
 Long Products Group  
 Steel, Cast and Flat Division  
 (260) 625-8100 (260) 625-8950 FAX  
**Quality Steel 100% EAF Melted  
 and Manufactured in the USA**  
 Recycled content: PC = 75.0%, PI = 22.8%  
 ISO 9001:2015 and ABS Certified  
 CMTR complies with EN 10204 3.1.

### CERTIFIED MILL TEST REPORT

Ship to:  
**The A588 & A572 Steel Co**  
 785 Arch Street  
 Carnegie PA, 15108 US  
 Attn: Denise Yarusai

Customer # 000469

Bill to:  
**THE A588 & A572 STEEL- PA**  
 133 Sebago Lake Drive  
 Sewickley PA, 15143 US  
 Attn: Rick Gurburg

Printed: 07 / 21 / 2019  
 Produced: 07 / 15 / 2019

GENERAL INFORMATION		SPECIFICATIONS		SHIPMENT DETAILS	
Product	Wide Flange Beam	Standards	Grades*	Bundle / ASN #	Length pcs
Size	W6X15	ASTM A618/A618 - 17a	A588/A588M grB	Cust PO	Job/Reference
Heat Number	W150X22.5	ASTM A588/A588M - 15	A709 g50Wtg34SW	061090418	40' 0" 12 23057
Condition(s)	B160675	A709/A709M - 17e1	M270 g34SW/50W	061090417	40' 0" 12 23057
	As-Rolled	AASHTO M270/M270 - 15	50A350A	BOL # 000557190 - 14400.00 lbs	
	Fine Grained	CSA G40.21-13			
	Fully Killed				
	No Weld Repair				

**CHEMICAL ANALYSIS** (weight percent)

C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn	V	Nb/Cb	Al	N	B	*C1	*C2	*C3	*PC	*I	Analysis Type
.07	1.13	.010	.025	.19	.34	.22	.48	.04	.020	.032	.003	.002	.0145	.0004	.41	.438	.32	.18	6.32	Heat

MECHANICAL TESTING					CHARPY IMPACT TESTS (available only when specified at time of order)					
Test	Yield (fy)	Tensile (fu)	fy / fu ratio	% Elong. (8" gage)	Temp F / C	Absorbed Energy ft-lbf / J			Average	Minimum
	ksi / MPa	ksi / MPa				Specimen 1	Specimen 2	Specimen 3		
1	51 / 350	62 / 565	.82	23						
2	54 / 370	79 / 545	.89	25						
3										
4										

**Notes:** \*Calculated Chemistry Values: Carbon Equivalents (C1, C2, C3, PC), Corrosion Index (I) (ASTM G101) = 26.01(Cu)+3.68(Ni)+1.20(Cr)+1.48(Si)+17.29(P)+7.29(Cu)(P)+8.18(Ni)(P)+32.35(Cr) Pcm (NBS) = C+0.36+0.0025(Cu)(Si)+0.0008(Cu)(Ni)+0.00015(Cu)(P)+0.00015(Cu)(S) CET (CET) = C + (MnS) + (S2S) + (CrS) + (NiS) + (MoS) + (P1S)

I hereby certify that the material described herein has been made to the applicable specification by the electric arc furnace process and tested in accordance with the requirements of American Bureau of Shipping Rules with satisfactory results.

Signed:

I hereby certify that the content of this report are accurate and correct. All tests and operations performed by this material manufacturer are in compliance with the requirements of the material specifications and applicable purchaser designated requirements.

Signed: **Todd Bashford** *Todd A. Bashford*  
 Quality Manager

**ABS CERTIFICATION**

State of Indiana, County of Whitley Sworn to and subscribed before me

this \_\_\_\_\_ day of \_\_\_\_\_

Signed: \_\_\_\_\_ My commission expires: \_\_\_\_\_  
 Notary Public

ASTM A6 - 14.6: A signature is not required on the test report; however, the document shall clearly identify the organization submitting the report. Notwithstanding the absence of a signature, the organization submitting the report is responsible for the content of the report.

TR No. 612061-08-01

107

2024-02-06



**GERDAU**

US-ML-CARTERSVILLE  
384 OLD GRASSDALE ROAD NE  
CARTERSVILLE, GA 30121  
USA

**CERTIFIED MATERIAL TEST REPORT**

Page 1/1

<b>CUSTOMER SHIP TO</b> A588 & A572 STEEL COMPANY 62 ARCH ST CARNEGIE, PA 15106-2040 USA		<b>CUSTOMER BILL TO</b> A588 & A572 STEEL COMPANY 133 SEBAGO LAKE DR SEWICKLEY, PA 15143-9374 USA		<b>GRADE</b> A588-B	<b>SHAPE / SIZE</b> Wide Flange Beam / 6 X 15# / 150 X 22.5	<b>DOCUMENT ID:</b> 0000200904	
<b>SALES ORDER</b> 6931811/000010		<b>CUSTOMER MATERIAL N°</b> 48.80 W GRADE EXTRA		<b>LENGTH</b> 40'00"	<b>PCS</b> 75	<b>WEIGHT</b> 45,000 LB	<b>HEAT / BATCH</b> 66054776/07
<b>CUSTOMER PURCHASE ORDER NUMBER</b> 21809		<b>BILL OF LADING</b> 1323-0000122232	<b>DATE</b> 10/29/2018	<b>SPECIFICATION / DATE or REVISION</b> ASTM A588-15 ASTM A6-17 ASTM A709-17			

CHEMICAL COMPOSITION												
C%	Mn%	P%	S%	Si%	Cr%	Ni%	Cu%	Mo%	Sn%	V%	Nb%	
0.17	0.93	0.018	0.021	0.34	0.31	0.11	0.56	0.027	0.010	0.026	0.000	

MECHANICAL PROPERTIES						
YS 0.2%	UTS	YS	UTS	G.I.	Elong.	
PSI	PSI	MPa	MPa	inch	%	%
64900	92100	448	635	8.000	18.80	
65300	90200	450	622	8.000	18.90	

COMMENTS / NOTES

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

*Bhaskar*

**BHASKAR YALAMANCHILI**  
QUALITY DIRECTOR

Phone: (409) 267-1071 Email: Bhaskar.Yalamanchili@gerdau.com

**TAN WANG**  
QUALITY ASSURANCE MGR.

Phone: (770) 357 5718 Email: yan.wang@gerdau.com



**Steel Dynamics, Inc.**  
 Long Products Group  
 2001 S. Cooney Road 700 East  
 Columbia City, Indiana 46725  
 (260) 625-8100 (260) 625-6988 FAX  
 Quality Steel 100% EAF Melted and Manufactured in the USA  
 Recycled content: PC = 75.0%, PI = 22.0%  
 ISO 9001:2015 and ABS Certified  
 CMTR complies with EN 10204 3.1.

**CERTIFIED MILL TEST REPORT**

Printed: 10 / 22 / 2019  
 Produced: 10 / 19 / 2019

Ship to:  
 The A588 & A572 Steel Co  
 785 Arch Street  
 Carnegie PA, 15108 US  
 Attn: Denise Yarusi

Customer # 000469  
 Bill to:  
 THE A588 & A572 STEEL - PA  
 133 Sebago Lake Drive  
 Sawickley PA, 15143 US  
 Attn: Rick Ganzburg

GENERAL INFORMATION		SPECIFICATIONS		SHIPMENT DETAILS	
Product	Wide Flange Beam	Standards	Grades*	Bundle / ASN #	Length pcs
Size	W6X15	ASTM A588/A588M - 17a	A588/A588M grB	061131015	40' 12
Heat Number	B166884	ASTM A588/A588M - 15	A709 g50W/g34SW	061131016	40' 12
Condition(s)	As-Rolled	A709/A709M - 17e1	M270 g34SH/30W	061131018	40' 12
	Fine Grained	AASHTO M270/M1270 - 15	50A/350A	061131014	40' 12
	Fully Killed	CSA G40.21-15			
	No Weld Repair	*S08-MULTI meets the requirements of ASTM A982, A572-60, A529-50, A709-50, M270-60, A36, A709-36, M270-36, CSA300W, CSA340WM, CSA350W.		BOL # 030058788 - 28800.00 lbs	
				Job/Reference	

**CHEMICAL ANALYSIS** (weight percent)

C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn	V	Nb/Cb	Al	N	B	*C1	*C2	*C3	*PC	*I	Analysis Type
.06	1.15	.019	.008	.19	.38	.25	.47	.04	.016	.035	.002	.003	.0119	.0003	.40	.434	.32	.18	6.47	Heat

MECHANICAL TESTING					CHARPY IMPACT TESTS (available only when specified at time of order)						
Test	Yield (fy) Strength	Tensile (fu) Strength	fy / fu ratio	% Elong. (8" gage)	Temp	Absorbed Energy			Average	Minimum	
	ksi / MPa	ksi / MPa				F / C	Specimen 1	Specimen 2			Specimen 3
1	52 / 360	81 / 580	.64	27							
2	55 / 380	80 / 560	.88	24							
3											
4											

**Notes:** \*Calculated Chemistry Values: Carbon Equivalents (C1, C2, C3, PC), Corrosion Index (C) (ASTM G101) - 36.0(C) + 3.05(P) + 1.50(Cu) + 1.62(S) + 17.22(P) - 7.2M(Cu) + 2.18(Ni) - 33.25(Cu) Pmax(MNS) = C+(Mn) + Ni/20 + Cu/20 + Nb/10 + V/15 + W/10 + Sn/10 + Mo/15 + Cr/15 + Cu/15 CEI (AWS) = C+(Mn) + Si/2 + Nb/5 + V/5 + Ni/10 + Cu/15 CEI (AISI) = C + (Mn) + (Si) + (Cu) + (Nb) + (V) + (Ni) + (Cu)

I hereby certify that the material described herein has been made to the applicable specification by the electric arc furnace/continuous cast process and tested in accordance with the requirements of American Bureau of Shipping Rules with satisfactory results.

Signed: **Todd Bashford**

I hereby certify that the content of this report are accurate and correct. All tests and operations performed by this material manufacturer are in compliance with the requirements of the material specifications and applicable purchaser designated requirements.

Signed: **Todd Bashford**

Form F-6100-02-064 rev B Quality Manager

**ABS CERTIFICATION**

State of Indiana, County of Whitey Sworn to and subscribed before me

this \_\_\_\_\_ day of \_\_\_\_\_

Signed: \_\_\_\_\_ My commission expires: \_\_\_\_\_

Notary Public

ASTM A6 - 14.6: A signature is not required on the test report; however, the document shall clearly identify the organization submitting the report. Notwithstanding the absence of a signature, the organization submitting the report is responsible for the content of the report. Page 3 of 3

TR No. 612061-08-01

109

2024-02-06

**SD** **Steel Dynamics, Inc.**  
 Long Products Group  
 Structural and Rail Division  
 2001 S. County Road 700 East  
 Columbia City, Indiana 46725  
 (260) 626-8100 (260) 626-8000 FAX  
 Quality Steel 100% EAF Melted and Manufactured in the USA  
 Recycled content: PC = 75.0%, PI = 22.8%  
 ISO 9001:2015 and ABS Certified  
 CRTR complies with EN 10204 3.1.

### CERTIFIED MILL TEST REPORT

Printed: 08 / 20 / 2019  
Produced: 07 / 15 / 2019

Ship to:  
 The A588 & A572 Steel Co  
 785 Arch Street  
 Carnegie PA, 15106 US  
 Attn: Denise Yarusal

Customer # 000469

Bill to:  
 THE A588 & A572 STEEL - PA  
 133 Sabago Lake Drive  
 Sewickley PA, 15143 US  
 Attn: Rick Guntzburg

GENERAL INFORMATION		SPECIFICATIONS		SHIPMENT DETAILS	
		<i>Standards</i>		BOL # 0000561285 - 7580.00 lbs	
Product	Wide Flange Beam	ASTM A6/AGM - 17a		Bundle / ASN #	Length pcs Cust PO   Job/Reference
Size	W6X15	ASTMA588/A588M - 15	A588/A588M grB	061054766	42' 0" 12 23227
Heat Number	W150X22.5	A709/A709M - 17e1	A709 gr50W/g345W		
Condition(s)	B160678 As-Rolled Fine Grained Fully Killed No Weld Repair	AASHTO M270/M270 - 15	M270 gr345W/50W		

**CHEMICAL ANALYSIS** (weight percent)

C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn	V	Nb/Cb	Al	N	B	*C1	*C2	*C3	*PC	*I	Analysis Type
.07	1.16	.012	.025	.22	.34	.22	.51	.04	.020	.035	.003	.002	.0145	.0004	.42	.454	.33	.19	6.41	Heat

MECHANICAL TESTING					CHARPY IMPACT TESTS (available only when specified at time of order)						
Test	Yield (fy) Strength	Tensile (fu) Strength	fy / fu ratio	% Elong. (8" gage)	Temp	Absorbed Energy		Average	Minimum	R-Ibf / J	
	kSI / MPa	kSI / MPa				Specimen 1	Specimen 2			Specimen 3	F / C
1	50 / 345	83 / 570	.61	24							
2	54 / 370	79 / 545	.68	24							
3											
4											

**Notes:** \*Calculated Chemistry Values: Carbon Equivalent (C1, C2, C3, PC), Corrosion Index (I) (ASTM G101) = 28.0(Ni) + 3.68(Mn) + 1.20(Cr) + 1.45(Si) + 17.24(P) + 7.26(Cu) + 9.10(C) + (S) + 33.38(Ca) Formulas: C = C; Mn = Mn; P = P; S = S; Si = Si; Cu = Cu; Ni = Ni; Cr = Cr; Mo = Mo; Sn = Sn; V = V; Nb/Cb = Nb/Cb; Al = Al; N = N; B = B; \*C1 = C + (Mn) + (Si) + (Cu) + (Ni) + (Cr) + (Mo) + (Sn) + (V) + (Nb/Cb) + (Al) + (N) + (B); \*C2 = C + (Mn) + (Si) + (Cu) + (Ni) + (Cr) + (Mo) + (Sn) + (V) + (Nb/Cb) + (Al) + (N) + (B); \*C3 = C + (Mn) + (Si) + (Cu) + (Ni) + (Cr) + (Mo) + (Sn) + (V) + (Nb/Cb) + (Al) + (N) + (B); \*PC = C + (Mn) + (Si) + (Cu) + (Ni) + (Cr) + (Mo) + (Sn) + (V) + (Nb/Cb) + (Al) + (N) + (B)

<p>I hereby certify that the material described herein has been made to the applicable specification by the electric arc furnace/continuous cast process and tested in accordance with the requirements of American Bureau of Shipping Rules with satisfactory results.</p> <p>Signed: <b>Todd Bashford</b> </p> <p>Form F-6100-002-054 rev B Quality Manager</p>	<p><b>ABS CERTIFICATION</b></p> <p>State of Indiana, County of Whitley Sworn to and subscribed before me</p> <p>this _____ day of _____</p> <p>Signed: _____ My commission expires: _____</p> <p style="text-align: center;">Notary Public</p>
---	--

ASTM A6 - 14.6: A signature is not required on the test report; however, the document shall clearly identify the organization submitting the report. Notwithstanding the absence of a signature, the organization submitting the report is responsible for the content of the report. Page 2 of 3

TR No. 612061-08-01

110

2024-02-06

**SDI Steel Dynamics, Inc.**  
 Long Products Group  
 Structural and Rail Division  
 2801 S. County Road 700 East  
 Columbia City, Indiana 46726  
 (260) 625-8100 (260) 625-8950 FAX  
**Quality Steel 100% EAF Melted and Manufactured in the USA**  
 Recycled content: PC = 75.0%, PI = 22.0%  
 ISO 9001:2015 and ABS Certified  
 CMTR complies with EN 10204 3.1.

### CERTIFIED MILL TEST REPORT

**Ship to:** Contractors Steel Co.  
 48649 Schooner Dr.  
 Trucks to enter from  
 Belleville MI, 48111 US  
 Attn: Mike M.

**Customer #** 000097

**Bill to:** Contractors Steel Co  
 36555 Amrhein Rd.  
 Livonia MI, 48150 US  
 Attn: Cathy

Printed: 03 / 17 / 2020  
 Produced: 03 / 10 / 2020

GENERAL INFORMATION		SPECIFICATIONS		SHIPMENT DETAILS	
<b>Product</b>	Wide Flange Beam	<b>Standards</b>	<b>Grades*</b>	BOL # 0000588772 - 7425.00 lbs	
<b>Size</b>	W6X15 W150X22.5	ASTM A6/A6M - 19		<b>Bundle / ASN #</b>	<b>Length pcs</b>
<b>Heat Number</b>	A175660	» ASTM A992/A992M - 11	A992 / A992M	061208018	55' 0" 9
<b>Condition(s)</b>	As-Rolled Fine Grained Fully Killed No Weld Repair	ASTM A572/A572M - 18	A572 gr50/gr345	<b>Cust PO   Job/Reference</b>	VB-133598
		ASTM A709/A709M - 17e1	A709 gr50/gr345		
		AASHTO M270M/M270 - 15	M270 gr345/gr50		
		CSA G40.21-13	50WM345WM		
		*SDI-MULTI meets the requirements of ASTM A992, A572-50, A529-50, A709-50, M270-50, A36, A709-36, M270-36, CSA300W, CSA345WM, CSA350W.			

#### CHEMICAL ANALYSIS (weight percent)

C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn	V	Nb/Cb	Al	N	B	*C1	*C2	*C3	*PC	*I	Analysis Type
.06	1.05	.015	.029	.23	.36	.14	.15	.04	.014	.022	<.001	.003	.0134	.0003	.31	.349	.26	.16	5.97	Heat

#### MECHANICAL TESTING

Test	Yield (fy) Strength	Tensile (fu) Strength	fy / fu ratio	% Elong. {8" gage}
	ksi / MPa	ksi / MPa		
1	55 / 380	76 / 525	.72	29
2	51 / 350	81 / 560	.63	28
3				
4				


#### CHARPY IMPACT TESTS (available only when specified at time of order)

Test	Temp		Absorbed Energy		Specimen 3	Average	Minimum
	F / C		Specimen 1	Specimen 2			
1							
2							
3							
4							
5							
6							
7							

**Notes:** \*Calculated Chemistry Values: Carbon Equivalents (C1, C2, C3, PC), Corrosion Index (I) (ASTM G101)= 26.01(Cu)+3.88(Ni)+1.20(Cr)+1.49(Si)+17.29(P)+7.29(Cu)(Ni)-9.10(Ni)(P)-33.39(Cu)<sup>2</sup> Pcm(AWS) = C+Si/30+Mn/20+Cu/20+N/60+Cr/20+mo/15+V/10+5B  
 CE1 (IIW)=C+Mn/8+(Cr+Mo+V)/5+(Ni+Cu)/15 CE2 (AWS)=C+(Mn+Si)/8+(Cr+Mo+V)/5+(Ni+Cu)/15 CE3 (CET) = C + (Mn/8) + (Si/24) + (Cr/5) + (Ni/40) + (Mo/4) + (V/14)

I hereby certify that the material described herein has been made to the applicable specification by the electric arc furnace/continuous cast process and tested in accordance with the requirements of American Bureau of Shipping Rules with satisfactory results.  
 Signed: \_\_\_\_\_

#### ABS CERTIFICATION

I hereby certify that the content of this report are accurate and correct. All tests and operations performed by this material manufacturer are in compliance with the requirements of the material specifications and applicable purchaser designated requirements.  
 Signed: **Todd Bashford**   
 Quality Manager

State of Indiana, County of Whitley Sworn to and subscribed before me  
 this \_\_\_\_\_ day of \_\_\_\_\_  
 Signed: \_\_\_\_\_ My commission expires: \_\_\_\_\_  
 Notary Public

ASTM A6 - 14.6: A signature is not required on the test report; however, the document shall clearly identify the organization submitting the report.  
 Notwithstanding the absence of a signature, the organization submitting the report is responsible for the content of the report





2601 S. County Road 700 East  
Columbia City, Indiana 46725  
(260) 625-8100 (260) 625-8850 FAX

# CERTIFIED MILL TEST REPORT

Ship to: **Contractors Steel Co.**  
8383 Boyle Parkway  
Twinsburg OH, 44087 US  
Attn: Travis Lance

Customer # 000097

Bill to: **Contractors Steel Co**  
36555 Amrhein Rd.  
Livonia MI, 48150 US  
Attn: Cathy

Printed: 04 / 07 / 2020  
Produced: 03 / 10 / 2020

Quality Steel 100% EAF Melted and Manufactured in the USA  
Recycled content: PC = 68.0%, PI = 27.0%  
ISO 9001:2015 and ABS Certified  
CMTR complies with EN 10204 3.1.

GENERAL INFORMATION		SPECIFICATIONS		SHIPMENT DETAILS	
		<u>Standards</u>	<u>Grades*</u>	BOL # 0000591887 - 9900.00 lbs	
Product	Wide Flange Beam	ASTM A6/A6M - 19		Bundle / ASN #	Length pcs Cust PO   Job/Reference
Size	W6X15	» ASTM A992/A992M - 11	A992 / A992M	061207791	55' 0" 12 TW-137171
	W150X22.5	ASTM A572/A572M - 18	A572 gr50/gr345		
Heat Number	B175825	ASTM A709/A709M - 17e1	A709 gr50/gr345		
Condition(s)	As-Rolled	AASHTO M270M/M270 - 15	M270 gr345/gr50		
	Fine Grained	CSA G40.21-13	50WM/345WM		
	Fully Killed	ASTM A36/A36M - 19	A36 / A36M		
	No Weld Repair	*SDI-MULTI meets the requirements of ASTM A992, A572-50, A709-50, A529-50, A36 and A709-36; AASHTO M270-50 and M270-36; CSA 300W, 345W and 350W.			

### CHEMICAL ANALYSIS (weight percent)

C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn	V	Nb/Cb	Al	N	B	*C1	*C2	*C3	*PC	*I	Analysis Type
.08	.98	.009	.025	.22	.23	.09	.08	.03	.012	.020	<.001	.002	.0098	.0003	.29	.327	.26	.15	5.01	Heat

### MECHANICAL TESTING

Test	Yield (fy)	Tensile (fu)	fy / fu ratio	% Elong. (8" gage)
	Strength	Strength		
	ksi / MPa	ksi / MPa		
1	53 / 365	69 / 475	.76	30
2	52 / 360	69 / 475	.76	31
3				
4				

### CHARPY IMPACT TESTS (available only when specified at time of order)

Test	Temp	Absorbed Energy		Specimen 3	Average	Minimum
	F / C	Specimen 1	Specimen 2			
		ft-lbf / J				
1						
2						
3						
4						
5						
6						
7						

**Notes:** \*Calculated Chemistry Values: Carbon Equivalents (C1, C2, C3, PC), Corrosion Index (I) (ASTM G101) = 26.01(Cu)+3.88(Ni)+1.20(Cr)+1.49(Si)+17.23(P)+7.29(Cu)(N)-8.10(N)(P)-33.38(Cu) Perm(AWS) = C+Si30+Mn20+Cu20+Ni60+Cr20+Mn15+V10+58 CE1 (IW) = C+Mn+Si+(Cr+Mo+V)/5+(Ni+Cu)/15 CE2 (AWS) = C+(Mn+Si)/5+(Cr+Mo+V)/5+(Ni+Cu)/15 CE3 (CET) = C + (Mo/6) + (Si/24) + (C/5) + (Ni/40) + (Mn/4) + (V/14)

I hereby certify that the material described herein has been made to the applicable specification by the electric arc furnace/continuous cast process and tested in accordance with the requirements of American Bureau of Shipping Rules with satisfactory results.

Signed:

I hereby certify that the content of this report are accurate and correct. All tests and operations performed by this material manufacturer are in compliance with the requirements of the material specifications and applicable purchaser designated requirements.

Signed: **Todd Bashford**

Quality Manager

Form F-6100-002-054 rev 8

### ABS CERTIFICATION

State of Indiana, County of Whitley Sworn to and subscribed before me

this \_\_\_\_\_ day of \_\_\_\_\_

Signed: \_\_\_\_\_ My commission expires: \_\_\_\_\_

Notary Public

ASTM A6 - 14.6: A signature is not required on the test report; however, the document shall clearly identify the organization submitting the report. Notwithstanding the absence of a signature, the organization submitting the report is responsible for the content of the report

TR No. 612061-08-01

112

2024-02-06



### CERTIFIED MILL TEST REPORT

Printed: 01 / 08 / 2020  
Produced: 12 / 03 / 2019

Ship to:  
**Contractors Steel Co.**  
8383 Boyle Parkway  
Twinsburg OH, 44087 US  
Attn: Travis Lance

Customer # 000097

Bill to:  
**Contractors Steel Co**  
36555 Amrhein Rd.  
Livonia MI, 48150 US  
Attn: Cathy

Quality Steel 100% EAF Melted and Manufactured in the USA  
Recycled content: PC = 75.0%, PI = 22.0%  
ISO 9001:2015 and ABS Certified  
CMTR complies with EN 10204 3.1.

GENERAL INFORMATION		SPECIFICATIONS		SHIPMENT DETAILS	
<b>Product</b>	Wide Flange Beam	<u>Standards</u>	<u>Grades*</u>	BOL # 0000578378 - 5400.00 lbs	
<b>Size</b>	W6X15	ASTM A6/A6M - 19		<b>Bundle / ASN #</b>	<b>Length pcs</b>
	W150X22.5	» ASTM A992/A992M - 11	A992 / A992M	061152194	30' 0" 12
<b>Heat Number</b>	B171455	ASTM A572/A572M - 18	A572 gr50/gr345	<b>Cust PO</b>	<b>Job/Reference</b>
<b>Condition(s)</b>	As-Rolled	ASTM A709/A709M - 17e1	A709 gr50/gr345	TW-132928	
	Fine Grained	AASHTO M270M/M270 - 15	M270 gr345/gr50		
	Fully Killed	CSA G40.21-13	50WM/345WM		
	No Weld Repair	ASTM A36/A36M - 14	A36 / A36M		
		*SDI-MULTI meets the requirements of ASTM A992, A572-50, A529-50, A709-50, M270-50, A36, A709-36, M270-36, CSA300W, CSA345WM, CSA350W.			

**CHEMICAL ANALYSIS** (weight percent)

C	Mn	P	S	Si	Cu	Ni	Cr	Mo	Sn	V	Nb/Cb	Al	N	B	*C1	*C2	*C3	*PC	*I	Analysis Type
.07	1.04	.008	.018	.22	.37	.12	.14	.04	.014	.022	.002	.002	.0120	.0004	.32	.353	.27	.16	5.81	Heat

MECHANICAL TESTING					CHARPY IMPACT TESTS (available only when specified at time of order)							
Test	Yield (fy) Strength ksi / MPa	Tensile (fu) Strength ksi / MPa	fy / fu ratio	% Elong. (8" gage)	Test	Temp		Absorbed Energy		Specimen 3	Average	Minimum
						F / C		Specimen 1	Specimen 2			
1	56 / 385	75 / 515	.75	28	1							
2	59 / 405	76 / 525	.78	27	2							
3					3							
4					4							
					5							
					6							
					7							

**Notes:** \*Calculated Chemistry Values: Carbon Equivalents (C1, C2, C3, PC), Corrosion Index (I) (ASTM G101)= 26.01(Cu)+3.88(Ni)+1.20(Cr)+1.49(Si)+17.29(P)+7.29(Cu)-9.10(Ni)-33.39(Cu)  
 CE1 (IIR)=C+Mn/6+(Cr+Mo+V)/5+(Ni+Cu)/15 CE2 (AWS)=C+(Mn+Si)/8+(Cr+Mo+V)/5+(Ni+Cu)/15 CE3 (CET) = C + (Mn/8) + (Si/24) + (Cr/5) + (Ni/40) + (Mo/4) + (V/14)  
 Fcm(AWS) = C+Si/30+Mn/20+Cu/20+Ni/60+Cr/20+mo/15+v/10+5B

I hereby certify that the material described herein has been made to the applicable specification by the electric arc furnace/continuous cast process and tested in accordance with the requirements of American Bureau of Shipping Rules with satisfactory results.  
Signed:

**ABS CERTIFICATION**

I hereby certify that the content of this report are accurate and correct. All tests and operations performed by this material manufacturer are in compliance with the requirements of the material specifications and applicable purchaser designated requirements.

State of Indiana, County of Whitley Sworn to and subscribed before me  
this \_\_\_\_\_ day of \_\_\_\_\_

Signed: **Todd Bashford**  
Quality Manager

Signed: \_\_\_\_\_ My commission expires: \_\_\_\_\_  
Notary Public

ASTM A6 - 14.6: A signature is not required on the test report; however, the document shall clearly identify the organization submitting the report.  
Notwithstanding the absence of a signature, the organization submitting the report is responsible for the content of the report  
Page 4 of 7

# Birmingham Fastener Manufacturing

P.O. Box 10323  
Birmingham, Alabama 35202  
(205) 595-3512

Pg 1 of 1

## Certificate of Compliance

Customer : AMERICAN TIMBER  
P.O. # : 16997

BFM # : 1500031  
Date Shipped : 6/25/2018

Quantity	Description	Lot #	Heat #	Specification	Finish
212	5/8"-11 x 7" Carriage Bolt	217961	JK17100350	F1554-36	F2329
2,500	5/8"-11 x 7" Carriage Bolt	217962	DL17105083	A242	Plain

*Birmingham Fastener Manufacturing. hereby certifies that the material furnished in reference to the above purchase order number will meet or exceed the above assigned specifications.*

Signed:  Date: 07/18/2018  
Brian Hughes

**NUCOR**  
**NUCOR CORPORATION**  
**NUCOR STEEL SOUTH CAROLINA**

**Mill Certification**  
**3/15/2018**

MTR #: C1-427479  
 300 Steel Mill Road  
 DARLINGTON, SC 29541  
 (843) 393-5841  
 Fax: (843) 395-5701

Sold To: BIRMINGHAM FASTENER & SUPPLY  
 PO BOX 10323  
 BIRMINGHAM, AL 35202-1223  
 (205) 595-3511  
 Fax: (205) 591-0244

Ship To: BIRMINGHAM FASTENER & SUPPLY  
 931 AVE 97  
 PO BOX 10323  
 BIRMINGHAM, AL 35202  
 (205) 595-3511  
 Fax: (205) 591-0244

Customer P.O.	61689421	Sales Order	279531 B
Product Group	Merchant Bar Quality	Part Number	30000563-1500L020
Grade	A242BF - ASTM A242-03	Lot #	DL1710502302
Size	9.16" x .5025" Round	Heat #	DL17105053
Product	9.16" x .5025" Round 40" A242BF	B.L. Number	C1 747408
Description	A242BF	Load Number	C1-427479
Customer Spec		Customer Part #	

I hereby certify that the material described herein has been produced in accordance with the specifications and conditions stated herein and that it satisfies the requirements.

Roll Date: 12/17/2017 Melt Date: 8/11/2017 Qty Shipped LBS: 46,832 Qty Shipped Pcs: 1,384

Melt Date: 8/11/2017

C	Mn	V	S	Si	P	Cu	Cr	Ni	Mo	Cb
0.15%	0.91%	0.0150%	0.10%	0.027%	0.018%	0.32%	0.74%	0.28%	0.019%	0.005%

Roll Date: 12/17/2017


Yield 1: 55,000psi  
 Elongation: 27% in 2" (in 50.8mm)  
 Elongation: 21% in 8" (in 203.2mm)

Tensile 1: 84,000psi  
 Yield 2: 54,000psi  
 Elongation: 35% in 2" (in 50.8mm) - test2

Elongation: 20% in 8" (in 203.2mm)  
 Tensile 2: 84,000psi

Specification Comments

1. WELDING OR WELD REPAIR WAS NOT PERFORMED ON THIS MATERIAL
2. MELTED AND MANUFACTURED IN THE USA
3. MERCURY, RADIUM OR ALPHA SOURCE MATERIALS IN ANY FORM HAVE NOT BEEN USED IN THE PRODUCTION OF THIS MATERIAL



James H. Blew  
 Division Metallurgist

NUCOR CORPORATION

TR No. 612061-08-01

115

2024-02-06

**SOLD** BIRMINGHAM FASTENER & SUPPLY  
 PO BOX 10323  
**TO:** BIRMINGHAM, AL 35202-0323



**CERTIFIED MILL TEST REPORT**

Page: 1

**SHIP** BIRMINGHAM FASTENER & SUPP  
 931 AVE W ENSLEY  
**TO:** BIRMINGHAM, AL 35214-

Ship from:  
 MTR #: 0000075451  
 Nucor Steel Jackson, Inc.  
 3630 Fourth Street  
 Flowood, MS 39232  
 800-723-1623

Date: 30-Jun-2017  
 B.L. Number: 438623  
 Load Number: 158744

Material Safety Data Sheets are available at www.nucorbar.com or by contacting your inside sales representative.

NBMG-08 January 1, 2012

LOT # HEAT #	DESCRIPTION	PHYSICAL TESTS				CHEMICAL TESTS											
		YIELD P.S.I.	TENSILE P.S.I.	ELONG % IN 8"	BEND	WT% DEF	C	Ni	Mn	Cr	P	S	V	Si	Cb	Cu	Sn
PO# => JK1710035001	M 70160 Nucor Steel - Jackson Inc	52,687	74,310	21.3%			.15	.77	.014	.037	.20	.29	.31				
JK17100350	9/16" (.5625) Round	363MPa	512MPa				.17	.23	.042	.016	.002						
	40' F1554 Gr36	52,575	74,150	21.3%													
	ASTM F1554-15 Gr36	362MPa	511MPa														
	ROA% = 50																
PO# => JK1710035302	M 70160 Nucor Steel - Jackson Inc	56,906	76,730	20.0%			.16	.82	.021	.040	.22	.29	.32				
JK17100353	9/16" (.5625) Round	392MPa	529MPa				.10	.18	.025	.018	.002						
	40' F1554 Gr36	54,424	75,110	21.3%													
	ASTM F1554-15 Gr36	375MPa	518MPa														
	ROA% = 49																
PO# => JK1710232601	M 70160 Nucor Steel - Jackson Inc	55,743	77,270	23.8%			.17	.80	.015	.033	.22	.39	.33				
JK17102326	9/16" (.5625) Round	384MPa	533MPa				.10	.11	.024	.016	.001						
	40' F1554 Gr36	55,542	77,550	23.8%													
	ASTM F1554-15 Gr36	383MPa	535MPa														
	ROA% = 71																

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.  
 1.1 Weld repair was not performed on this material.  
 2.1 Melted and Manufactured in the United States  
 3.1 Mercury, Radium, or Alpha source materials in any form have not been used in the production of this material.

QUALITY ASSURANCE. Christopher Smith





THIS IS TO CERTIFY THE PRODUCT STATED BELOW WAS FABRICATED AND PROCESSED TO THE ORDER AS INDICATED AND CONFORMS TO THE APPLICABLE SPECIFICATIONS AND STANDARDS.

**Customer:** BIRMINGHAM FASTENER & SUPPLY  
HANCEVILLE DIST CENTER  
1100 MAIN ST  
HANCEVILLE, AL 35077

**Customer Part:** 5/8" TYPE 3 F436  
**Prestige Part:** P1383CH00  
**Part Name:** 5/8"F436 TYPE 3  
**Purchase Order:** 6211422  
**Shipment BOL:** B219698  
**Shipment ID:** A0238117  
**Quantity:** 24000  
**Manufacturers Marking:** "P"

**Steel Supplier:** STEEL TECHNOLOGIES LLC  
**Grade:** SAE CF436 TYPE3 STEEL  
**Lot:** D7926  
**Heat:** 198520  
**Carbon:** .39  
**Manganese:** .79  
**Phosphorous:** .02  
**Sulfur:** .003  
**Silicon:** .24

SPECIFICATIONS

**HARDNESS:** TEST METHOD: ASTM E18  
HRC 38 - 45  
CHECKED TO ASTM F606

TEST RESULTS

**HARDNESS:**  
HRC 43 - 44

:

:

USS/SAE LC Washers are manufactured to the requirements of ASTM F844 specifications  
Chemistry is as reported from raw material certification and does not fall under Prestige Stamping's accreditation.  
This product was produced under an IATF 16949 Quality Assurance System.  
IATF 16949 Certification No: 800334.  
Material was melted and manufactured in the U.S.A.  
This product was manufactured in Warren, Michigan U.S.A.  
This product conforms to all requirements for washers as produced according to A.S.T.M. F-436-13.  
Sampling Plan per P.S.I W.I. # 5.4.18.015.  
The test results only apply to the items tested.  
This test report must not be reproduced except in full without prior written approval.  
Materials used to manufacture these products are mercury, asbestos and radio activity free.  
Product is RoHS compliant.  
No weld repairs made to material.  
All certified product is AIS compliant.

  
FRANK SCHUBERT  
Quality Assurance Manager

D7926

**Wrought Washer Mfg., Inc.**

2100 S. Bay St., Milwaukee, Wisconsin 53207  
Phone: (414) 744-0771 Fax: (414) 744-4811

Processed for:

Prestige Stamping  
23513 Groesbeck Hwy  
Warren, MI 48089

The following coil was processed at Wrought Washer located in the USA on May 24, 2019 and shipped to Prestige Stamping on June 10, 2019.

Coil #: 14752  
Mill Coil #: 2396526  
Heat #: 198520  
Gauge: .136  
Mill coil weight: 42,500#  
Chemistry:

C	Mn	P	S	Al	Si	Cu	Ni	
.39000	.79000	.02000	.00300	.03000	.24000	.26300	.28600	
Cr	Mo	V	Nb/Cb	Ti	N	Ca	B	Sn
.47500	.01800	.00500	.00100	.00200	.00700	.00100	.00000	.01100



Signature  
Quality Manager

TR No. 612061-08-01

118

2024-02-06

**NUCOR**  
Nucor Steel Indiana  
4537 South Nucor Road  
Crawfordsville, IN 47933-0907

METALLURGICAL TESTING CERTIFICATION

0078096

Certificate Number: 825756  
Date Issued: 05/17/2019

Page: 1 of 1

Order Number: 314919 - 0001 HOT ROLLED PICKLED & ANNEALED  
Order Dimensions: 0.1360 in X 51.0000 in  
HRPA,CUT,1040 WEATHERING

Customer Name: BROUGHT WASHER MFG INC  
Customer Address: 2100 S BAY ST

Release Order: MILWAUKEE MI 53207  
Cust PO Number: H3539

Coil Number 2396525.000 HEAD  
L-Yield (ksi): 52.0  
L-Tensile (ksi): 79.8  
L-Elong (%): 30.0  
Rockwell B: 83

Part Number 724148-240 TONS  
Weight: 42,720 LBS

CHEMICAL ANALYSIS

Heat	Slab	C	Mn	P	S	Si	Cu	Sn	Ni	Cr	Mo	Al	N	V	Nb	Ti	B	Sb
198520	04	0.39	0.790	0.020	0.003	0.240	0.263	0.011	0.286	0.475	0.018	0.030	0.007	0.005	0.001	0.002	<0.0005	0.001

Coil Number 2396526.000 HEAD  
L-Yield (ksi): 60.8  
L-Tensile (ksi): 87.2  
L-Elong (%): 29.0  
Rockwell B: 89

Part Number 724148-240 TONS  
Weight: 42,500 LBS

CHEMICAL ANALYSIS

Heat	Slab	C	Mn	P	S	Si	Cu	Sn	Ni	Cr	Mo	Al	N	V	Nb	Ti	B	Sb
198520	05	0.39	0.790	0.020	0.003	0.240	0.263	0.011	0.286	0.475	0.018	0.030	0.007	0.005	0.001	0.002	<0.0005	0.001

WE HEREBY CERTIFY THE ABOVE IS CORRECT AS CONTAINED IN THE RECORDS OF THE CORPORATION  
MELTED AND ROLLED IN THE USA

QF-0261 04/01/2019

1-800-777-0950 HTR\_IND\_INQUIRIES@NUCOR.COM

NUCOR QUALITY ASSURANCE





# HIGHWAY SAFETY CORP

P.O. BOX 358  
GLASTONBURY, CT 06033

## CERTIFICATE OF COMPLIANCE/ANALYSIS REPORT

**SOLD TO:**  
AMERICAN TIMBER AND STEEL  
4832 PLANK ROAD  
PO BOX 809  
Norwalk, OH, USA

**SHIP TO:**  
AMERICAN TIMBER AND STEEL  
4832 PLANK ROAD  
Norwalk,

INVOICE / S.O.: 0209689 / 0157621  
CUSTOMER P.O.: 18524

REFERENCE:  
DATE SHIPPED: 11/5/2018

QTY:	ITEM NUMBER:	CC:	DESCRIPTION:													
			HEAT/LOT NO:	YIELD:	TENSILE:	%ELONG:	C:	Mn:	P:	S:	Sl:	Cl:	Type	ACW		
58	BOLAGG062040	BOLAGG062040	0017265												BOLT LAG 0.625-11 x 04.000 GALV (5/8) A307	
180	WAROG-062-LA	WAROG-062-LA	0017265												WASHER ROUND 0.625 USS MG LARGE (5/8) F644 1-3/4 OD x 1	

ALL STEEL USED IN MANUFACTURING IS MADE AND MELTED IN THE USA, INCLUDING HARDWARE FASTENERS, AND COMPLIES WITH THE BUY AMERICA ACT. ALL COATINGS PROCESSES ARE PERFORMED IN THE USA AND COMPLY WITH THE BUY AMERICA ACT. BOLTS COMPLY WITH ASTM-A307 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM-A153, UNLESS OTHERWISE STATED. NUTS COMPLY WITH ASTM-A563 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM-A153, UNLESS OTHERWISE STATED. WASHERS COMPLY WITH ASTM F-436 AND/OR F-844 SPECIFICATIONS AND ARE GALVANIZED IN ACCORDANCE WITH ASTM-A153, UNLESS OTHERWISE STATED. ALL GUARDRAIL MEETS AASHTO M-180 AND ALL STRUCTURAL STEEL MEETS AASHTO M-270. ALL OTHER GALVANIZED MATERIAL CONFORMS WITH ASTM-A123. ALL OTHER ITEMS COMPLY WITH AASHTO M-111, M-185, M-133, M-265, ASTM A36, ASTM-709, ASTM-123, ASTM A505, AND ASTM-A588 SPECIFICATIONS IF APPLICABLE. COMPLIANCE WITH ALL SPECIFICATIONS OF DEPARTMENT OF PUBLIC WORKS, DEPARTMENT OF HIGHWAYS AND TRANSPORTATION, DIVISION OF ROADS AND BRIDGES AND STATE HIGHWAY ADMINISTRATION IS MET IN ALL RESPECTS.

HIGHWAY SAFETY CORPORATION

QUALITY ASSURANCE MANAGER

NOTARIZED UPON REQUEST:

STATE OF CONNECTICUT COUNTY OF HARTFORD 19<sup>th</sup> DAY OF NOV, 20 18  
SWORN AND SUBSCRIBED BEFORE ME THIS

Notary Public

MARGARET J. SATALINO  
NOTARY PUBLIC  
MY COMMISSION EXPIRES OCT. 31, 2021

# Birmingham Fastener Manufacturing

P.O. Box 10323  
Birmingham, Alabama 35202  
(205) 595-3512

Pg 1 of 1

## Certificate of Compliance

Customer : AMERICAN TIMBER  
P.O. # : 21686

BFM # : 1682256  
Date Shipped : 2/24/2020

Item	Quantity	Description	Lot #	Heat #	Specification	Finish
1	3,000	5/8"-11 Heavy Hex Nut	407090B	DL14104775	AWWA C111	Plain

*Birmingham Fastener Manufacturing. hereby certifies that the material furnished in reference to the above purchase order number will meet or exceed the above assigned specifications.*

Signed:   
Cody Calvert

Date: 06/05/2020

**NUCOR**  
FASTENER DIVISION

LOT NO.  
4070908

Post Office Box 6100  
Saint Joe, Indiana 46786  
Telephone 260/337-1600

CUSTOMER NO./NAME  
9320 BIRMINGHAM FASTENER MFG  
TEST REPORT SERIAL# FB562877  
TEST REPORT ISSUE DATE 4/18/18  
DATE SHIPPED 6/12/18  
NAME OF LAB SAMPLER: PATRICIA SHAFER, LAB TECHNICIAN  
\*\*\*\*\*CERTIFIED MATERIAL TEST REPORT\*\*\*\*\*  
NUCOR PART NO QUANTITY LOT NO. DESCRIPTION  
941060 65470 4070908 5/8-11 GR A242 HV HX NUT BLACK  
MANUFACTURE DATE 4/10/18 HEX NUT BLACK



--CHEMISTRY MATERIAL GRADE -A242NF  
MATERIAL HEAT \*\*CHEMISTRY COMPOSITION (WT% HEAT ANALYSIS) BY MATERIAL SUPPLIER  
NUMBER NUMBER C MN P S SI CU NI CR NUCOR STEEL - SOUTH CAROL  
RM030632 DL14104775 .13 .84 .005 .019 .18 .39 .28 .72

--MECHANICAL PROPERTIES  
SURFACE CORE PROOF LOAD TENSILE STRENGTH  
HARDNESS HARDNESS 9000 LBS DEG-WEDGE  
(R50N) (RC) (LBS) STRESS (PSI)  
N/A N/A PASS N/A N/A  
N/A N/A PASS N/A N/A  
N/A N/A PASS N/A N/A  
N/A N/A PASS N/A N/A  
N/A N/A PASS N/A N/A  
AVERAGE VALUES FROM TESTS

PRODUCTION LOT SIZE 66000 PCS

--DIMENSIONS PER ASME B18.2.2-2010  
CHARACTERISTIC #SAMPLES TESTED MINIMUM MAXIMUM  
Width Across Corners 8 1.177 1.183  
Thickness 32 0.597 0.604

ALL TESTS ARE IN ACCORDANCE WITH THE LATEST REVISIONS OF THE METHODS PRESCRIBED IN THE APPLICABLE SAE AND ASTM SPECIFICATIONS. THE SAMPLES TESTED CONFORM TO THE SPECIFICATIONS AS DESCRIBED/LISTED ABOVE AND WERE MANUFACTURED FREE OF MERCURY CONTAMINATION. THE STEEL WAS MELTED AND MANUFACTURED IN THE U.S.A. AND THE PRODUCT WAS MANUFACTURED AND TESTED IN THE U.S.A. PRODUCT COMPLIES WITH DFARS 252.225-7014. WE CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIAL SUPPLIER AND OUR TESTING LABORATORY. THIS CERTIFIED MATERIAL TEST REPORT RELATES ONLY TO THE ITEMS LISTED ON THIS DOCUMENT AND MAY NOT BE REPRODUCED EXCEPT IN FULL.



MECHANICAL FASTENER  
CERTIFICATE NO. A2LA 0139.01  
EXPIRATION DATE 12/31/19

NUCOR FASTENER  
A DIVISION OF NUCOR CORPORATION

*Bob Haywood*  
BOB HAYWOOD  
QUALITY ASSURANCE SUPERVISOR



**NUCOR**  
**NUCOR CORPORATION**  
**NUCOR STEEL SOUTH CAROLINA**

**Mill Certification**  
**2/19/2016**

30632  
MTR #: C1-384318  
300 Steel Mill Road  
DARLINGTON, SC 29540  
(843) 393-5841  
Fax: (843) 395-8701

Sold To: NUCOR FASTENER INDIANA  
PO BOX 8100  
ST JOE, IN 46785-0000  
(800) 955-8826  
Fax: (219) 337-1726

Ship To: NUCOR FASTENER  
8720 COUNTY ROAD 60  
ST JOE, IN 46785  
(800) 955-8826  
Fax: (219) 337-1722

Customer P.O.	158069	Sales Order	239317.1
Product Group	Special Bar Quality	Part Number	31001015000DMZB
Grade	A242NF - ASTM A242-13	Lot #	DL1410477502
Size	1-1/8" (1.0156) Round Coil	Heat #	DL14104775
Product	1-1/8" (1.0156) Round Coil A242NF	B.L. Number	C1-884956
Description	A242NF	Load Number	C1-384318
Customer Spec		Customer Part #	C25010

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.

Roll Date: 2/17/2016 Melt Date: 7/30/2014 Qty Shipped LBS: 41,834 Qty Shipped Pcs: 10

NO COIL DELIVERIES VIA TRUCK DECEMBER 18TH - JANUARY 4TH  
NO COIL DELIVERIES VIA RAIL DECEMBER 28TH - JANUARY 4TH

Melt Date: 7/30/2014

C	Mn	V	Si	S	P	Cu	Cr	Ni	Mo	Cb	CRNCMO
0.13%	0.84%	0.0120%	0.18%	0.019%	0.005%	0.38%	0.72%	0.28%	0.020%	0.002%	1.410%

CRNCMO: Cr + Ni + Cu + Mo

Atmospheric Corr Res Index: 8.6

Roll Date: 2/17/2016

Yield 1: 62,000psi	Tensile 1: 74,000psi	Elongation: 25% in 8"(% in 203.3mm)
Elongation: 44% in 2"(% in 50.8mm)	Yield 2: 51,000psi	Tensile 2: 74,000psi
Elongation 25% in 8"(% in 203.3mm)	Elongation: 43% in 2"(% in 50.8mm) - test2	

Specification Comments:

1. WELDING OR WELD REPAIR WAS NOT PERFORMED ON THIS MATERIAL
2. MELTED AND MANUFACTURED IN THE USA
3. MERCURY, RADIUM, OR ALPHA SOURCE MATERIALS IN ANY FORM HAVE NOT BEEN USED IN THE PRODUCTION OF THIS MATERIAL

**Chemistry Verification Checks**

Part# C25010 RM# 30632

Checked By \_\_\_\_\_ Date \_\_\_\_\_

Receiving OK: 297 2-23-16

Certifications OK: 375 2-23-16

*James H. Blew*

James H. Blew  
Division Metallurgist

Page 1 of 1

**CERTIFICATE OF COMPLIANCE**

**ROCKFORD BOLT & STEEL CO.  
126 MILL STREET  
ROCKFORD, IL 61101  
815-968-0514 FAX# 815-968-3111**

**CUSTOMER NAME:** AMERICAN TIMBER & STEEL

**CUSTOMER PO:** 21451

**SHIPPER #:** 068659  
**DATE SHIPPED:** 04/17/2020

**LOT#:** P38707 R71433-01  
**UNYTITE LOT #:** 30455-6214823003

**SPECIFICATION:** ASTM A563, GRADE DH HEAVY HEXAGONAL NUT

**COATING:** ASTM SPECIFICATION F-2329 HOT DIP GALVANIZE

**UNIVERSAL GALVANIZING:** 30455-6214823003

**CHEMICAL COMPOSITION**

MILL	GRADE	HEAT#	C	Mn	P	S	SI
GERDAU	1045	62148230	.43	.70	.007	.025	.21

**HARDNESS:**

**SPEC:** 24-38

**ACTUAL:** 27.90

**QUANTITY AND DESCRIPTION:**

1,200 PCS 5/8" HEAVY HEX NUT

WE HEREBY CERTIFY THE ABOVE PARTS HAVE BEEN MANUFACTURED IN THE U.S.A. WITH DOMESTIC STEEL. WE FURTHER CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER, AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY ASSURE THAT ALL ITEMS FURNISHED ON THIS ORDER MEET OR EXCEED ALL APPLICABLE TESTS, PROCESS, AND INSPECTION REQUIREMENTS PER ABOVE SPECIFICATION.



**GERDAU**

US-ML-ST PAUL  
1678 RED ROCK ROAD  
SAINT PAUL, MN 55119  
USA

**CERTIFIED MATERIAL TEST REPORT**

Page 1/1

<b>CUSTOMER SHIP TO</b> UNYTTTE INC LASALLE PLANT 325 CIVIC ROAD LA SALLE, IL 61301 USA		<b>CUSTOMER BILL TO</b> UNYTTTE INC 1 UNYTTTE DR PERU, IL 61354-9710 USA		<b>GRADE</b> 1045M23F02N	<b>SHAPE / SIZE</b> Round Bar / 7/8"	<b>DOCUMENT ID:</b> 0000028294
<b>SALES ORDER</b> 7321959/000010		<b>CUSTOMER MATERIAL N°</b> B1045SC0.8750 A		<b>LENGTH</b> 24'10"	<b>WEIGHT</b> 39.917 LB	<b>HEAT / BATCH</b> 62148230/02
<b>CUSTOMER PURCHASE ORDER NUMBER</b> P008130			<b>BILL OF LADING</b> 1332-0000058102	<b>DATE</b> 03/12/2019		

CHEMICAL COMPOSITION													
C	Mn	P	S	Si	Cr	Ni	Cu	Mo	Sp	V	Nb	Al	
0.43	0.70	0.007	0.025	0.21	0.20	0.08	0.17	0.016	0.024	0.022	0.001	0.005	

METALURGICAL CHARACTERISTICS			
PhsGr	E381 S	E381 R	E381 C

HARDENABILITY	
DI A255	Inch
	1.35

**COMMENTS / NOTES**

Material 100% melted and rolled in the USA. Manufacturing processes for this steel, which may include scrap melted in an electric arc furnace and hot rolling, have been performed at Gerdau St. Paul Mill, 1678 Red Rock Road, Saint Paul, Minnesota, USA. All product produced from strand cast billets. Silicon killed (deoxidized) steel. No weld repairs performed. Steel not exposed to mercury or any liquid alloy which is liquid at ambient temperatures during processing or while in Gerdau St. Paul Mills possession. Any modification to this certification as provided by Gerdau-St. Paul Mill without the expressed written consent of Gerdau St. Paul Mill negates the validity of this test report. This report shall not be reproduced except in full, without the expressed written consent of Gerdau St. Paul Mill. Gerdau St. Paul Mill is not responsible for the inability of this material to meet specific applications. Roll batch 62148230/03 roll date 2/8/2019 Fine Grain (FG 5-8) Quality Program Manual Rev. 8, Implemented date 7/13/2018

*Debra L. Kariesch*

The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. This material, including the billets, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

*Bhaskar* **BHASKAR YALAMANCHILI**  
 QUALITY DIRECTOR  
 Phone: (409) 267-1071 Email: Bhaskar.Yalamanchili@gerdau.com

*Alex* **ALEX BRANDENBURG**  
 QUALITY ASSURANCE MGR.  
 Phone: (651) 731-5662 Email: Alex.Brandenburg@gerdau.com

# Birmingham Fastener Manufacturing

P.O. Box 10323  
Birmingham, Alabama 35202  
(205) 595-3512

Pg 1 of 1

## Certificate of Compliance

**Customer :** AMERICAN TIMBER  
**P.O. # :** 20512

**BFM # :** 1628407  
**Date Shipped :** 9/30/2019

Item	Quantity	Description	Lot #	Heat #	Specification	Finish
1	869	3/4"-10 x 8 1/2" Carriage Bolt	86911	10592090	AWWAC111	Plain
4	10,545	5/8"-11 x 4" Hex Lag Screw	32361	10575880	AWWAC111	Plain

*Birmingham Fastener Manufacturing. hereby certifies that the material furnished in reference to the above purchase order number will meet or exceed the above assigned specifications.*

**Signed:**  **Date:** 11/04/2019  
Brian Hughes



# CHARTER STEEL

A Division of  
Charter Manufacturing Company, Inc.

## EMAIL

1658 Cold Springs Road  
Saukville, Wisconsin 53080  
(262) 268-2400  
1-800-437-8789  
Fax (262) 268-2570

Melted in USA Manufactured in USA

## CHARTER STEEL TEST REPORT

**Birmingham Fastener & Supply**  
931 Avenue W  
Birmingham, AL-35234  
Kind Attn :Blane Vines

Cust P.O.	6198448
Customer Part #	336513
Charter Sales Order	50058866
Heat #	10592090
Ship Lot #	4575439
Grade	A242 M SK FG IQ 11/16 RNDCOIL
Process	HRCC
Finish Size	11/16
Ship date	19-FEB-19

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed below and that it satisfies these requirements. The recording of false, fictitious and fraudulent statements or entries on this document may be punishable as a felony under federal statute.

### Test results of Heat Lot # 10592090

Lab Code: 7388

CHEM	C	MN	P	S	SI	NI	CR	MO	CU	SN	V
%Wt	.07	.55	.017	.013	.230	.36	.72	.05	.28	.008	.003
	AL	N	B	TI	NB						
	.026	.0070	.0001	.002	.002						

### Test results of Rolling Lot # 1263788

	# of Tests	Min Value	Max Value	Mean Value	
TENSILE (KSI)	1	62.9	62.9	62.9	TENSILE LAB = 0358-02
REDUCTION OF AREA (%)	1	78	78	78	RA LAB = 0358-02

REDUCTION RATIO=81:1

### Specifications:

Manufactured per Charter Steel Quality Manual Rev Date 05/12/17  
Charter Steel certifies this product is indistinguishable from background radiation levels by having process radiation detectors in place to measure for the presence of radiation within our process & products.  
Meets customer specifications with any applicable Charter Steel exceptions for the following customer documents:  
Customer Document = BF A242      Revision =      Dated = 07-JUL-08

### Additional Comments:

Melt Source:  
Charter Steel  
Saukville, WI, USA

Trip: 1341333



Page 1 of 2

This MTR supersedes all previously dated MTRs for this order

Janice Barnard Division Mgr. of Quality Assurance  
barnardJ@chartersteel.com  
Printed Date : 02/19/2019

The following statements are applicable to the material described on the front of this Test Report:

1. Except as noted, the steel supplied for this order was melted, rolled, and processed in the United States meeting DFARS compliance, LEEDS compliance, REACH compliance, ROHS-WEEE compliance, and Conflict Materials Restrictions.
2. Mercury was not used during the manufacture of this product, nor was the steel contaminated with mercury during processing.
3. Unless directed by the customer, there are no welds in any of the coils produced for this order.
4. The laboratory that generated the analytical or test results can be identified by the following key:

Certificate Number	Lab Code	Laboratory	Address
0358-01	7388	CSSM Charter Steel Melting Division	1658 Cold Springs Road, Saukville, WI 53080
0358-02	8171	CSSR/CSSP Charter Steel Rolling/ Processing Division	1658 Cold Springs Road, Saukville, WI 53080
0358-03	123633	CSFP Charter Steel Ohio Processing Division	6255 US Highway 23, Rising Sun, OH 43457
0358-04	125544	CSCM/CSCR Charter Steel Cleveland	4300 E. 49th St., Cuyahoga Heights, OH 44125-1004
*	*	--	Subcontracted test performed by laboratory not in Charter Steel System

5. When run by a Charter Steel laboratory, the following tests were performed according to the latest revisions of the specifications listed below, as noted in the Charter Steel Laboratory Quality Manual:

Test	Specifications	CSSM	CSSR/CSSP	CSFP	CSCM/CSCR
Chemistry Analysis	ASTM E415; ASTM E1019	X			X
Macroetch	ASTM E381	X			X
Hardenability (Jominy)	ASTM A255; SAE J406; JIS G0561	X			X
Grain Size	ASTM E112	X	X	X	X
Tensile Test	ASTM E8; ASTM A370		X	X	X
Rockwell Hardness	ASTM E18; ASTM A370	X	X	X	X
Microstructure (spheroidization)	ASTM A892		X	X	
Inclusion Content (Methods A, E)	ASTM E45		X		X
Decarburization	ASTM E1077		X	X	X

Charter Steel has been accredited to perform all of the above tests by the American Association for Laboratory Accreditation (A2LA). These accreditations expire 01/31/21. All other test results associated with a Charter Steel laboratory that appear on the front of this report, if any, were performed according to documented procedures developed by Charter Steel and are not accredited by A2LA.

6. The test results on the front of this report are the true values measured on the samples taken from the production lot. They do not apply to any other sample.
7. This test report cannot be reproduced or distributed except in full without the written permission of Charter Steel. The primary customer whose name and address appear on the front of this form may reproduce this test report subject to the following restrictions:
  - It may be distributed only to their customers
  - Both sides of all pages must be reproduced in full
8. This certification is given subject to the terms and conditions of sale provided in Charter Steel's acknowledgement (designated by our Sales Order number) to the customer's purchase order. Both order numbers appear on the front page of this Report.
9. Where the customer has provided a specification, the results on the front of this test report conform to that specification unless otherwise noted on this test report.





# Birmingham Fastener Manufacturing

P.O. Box 10323  
Birmingham, Alabama 35202  
(205) 595-3512

Pg 1 of 1

## Certificate of Compliance

Customer : AMERICAN TIMBER  
P.O. # : 20512

BFM # : 1628407  
Date Shipped : 10/28/2019

Item	Quantity	Description	Lot #	Heat #	Specification	Finish
1	9,131	3/4"-10 x 8 1/2" Carriage Bolt	107531	DL18100861	AWWAC111	Plain
2	3,000	3/4" Str Rd Washer	296127	227567	ASTM F436 T3	Plain
2	6,000	3/4" Str Rd Washer	D7926	198520	ASTM F436 T3	Plain
3	7,000	3/4"-10 Heavy Hex Nut	799283	75068613	ASTM A563 DH	Plain
4	4,300	5/8"-11 x 4" Hex Lag Screw	32361	10575880	AWWAC111	HDG

*Birmingham Fastener Manufacturing. hereby certifies that the material furnished in reference to the above purchase order number will meet or exceed the above assigned specifications.*

Signed:  Date: 11/04/2019  
Brian Hughes

**NUCOR**  
**NUCOR CORPORATION**  
**NUCOR STEEL SOUTH CAROLINA**

**Mill Certification**  
**7/25/2019**

MTR #: C1-473652  
 300 Steel Mill Road  
 DARLINGTON, SC 29540  
 (843) 393-5841  
 Fax: (843) 395-8701

Sold To: BIRMINGHAM FASTENER & SUPPLY  
 PO BOX 10323  
 BIRMINGHAM, AL 35202-0323  
 (205) 595-3511  
 Fax: (205) 591-0244

Ship To: BIRMINGHAM FASTENER & SUPPLY  
 931 AVE W  
 PO BOX 10323  
 BIRMINGHAM, AL 35202  
 (205) 595-3511  
 Fax: (205) 591-0244

Customer P.O.	6207420	Sales Order	310039.5
Product Group	Merchant Bar Quality	Part Number	30000680480DEQ0
Grade	A242BF - ASTM A242-03	Lot #	DL1810086102
Size	.680" Round	Heat #	DL18100861
Product	.680" Round 40' A242BF	B.L. Number	C1-791357
Description	A242BF	Load Number	C1-473652
Customer Spec		Customer Part #	

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.

Roll Date: 3/23/2019 Melt Date: 2/6/2018 Qty Shipped LBS: 14,831 Qty Shipped Pcs: 300

Melt Date: 2/6/2018


C	Mn	V	Si	S	P	Cu	Cr	Ni	Mo	Cb
0.15%	0.86%	0.0120%	0.17%	0.007%	0.006%	0.31%	0.72%	0.25%	0.014%	0.004%

Roll Date: 3/23/2019

Yield 1: 53,000psi	Tensile 1: 79,000psi	Elongation: 22% in 8"(% in 203.3mm)
Elongation: 35% in 2"(% in 50.8mm)	Yield 2: 53,000psi	Tensile 2: 81,000psi
Elongation 24% in 8"(% in 203.3mm)	Elongation: 39% in 2"(% in 50.8mm) - test2	

Specification Comments:

1. WELDING OR WELD REPAIR WAS NOT PERFORMED ON THIS MATERIAL
2. MELTED AND MANUFACTURED IN THE USA
3. MERCURY, RADIUM, OR ALPHA SOURCE MATERIALS IN ANY FORM HAVE NOT BEEN USED IN THE PRODUCTION OF THIS MATERIAL



James H. Blew  
 Division Metallurgist

TR No. 612061-08-01

130

2024-02-06

INSPECTION CERTIFICATE

ROCKFORD BOLT AND STEEL CO.
126 MILL STREET
ROCKFORD, IL 61101
815-968-0514 FAX: 815-968-3111

LOT# 32693

PAGE 1 OF 1

Batch Qty: 15,213
Sample Qty: 6
Date of Manufacture: 02/04/2020

THIS REPORT CONTAINS DATA THAT WAS PRODUCED UNDER THE
FOLLOWING SUBCONTRACTORS:
\*Raw Material: KREHER STEEL - ISO 9001:2015 #98-1181-03
Not ISO 17025 Accredited

SPECIFICATION: ASTM A325 2014, Specification For Structural Bolts
Head markings: "A325" and "D1AE"
ASTM A153, Class C Hot Dip Galvanization

CUSTOMER NAME: AMERICAN TIMBER & STEEL
4832 PLANK ROAD; P.O. BOX 767; NORWALK, OH 44857

DESCRIPTION: 3/4" -11 x 8.5" Carriage Bolt

CUSTOMER PO#: 21451 SHIPPER#: 068659
DATE SHIPPED: 04/17/2020

QUANTITY: 14,886 PCS

CHEMICAL COMPOSITION MILL CERT\*

HEAT # 100101783

Table with 6 columns: GRADE, C, Mn, P, S, Si. Rows include 1045, SPEC., and ACTUAL values.

MECHANICAL PROPERTIES

Table with 4 columns: TENSILE, PROOF LOAD, HARDNESS. Rows include SPEC. and ACTUAL values.

APPROVED SIGNATURE: [Signature] DATE: 4/28/2020

THESE PARTS CONFORM TO ABOVE SPECIFICATIONS.

Tension Testing: ASTM F606
Proof Load Testing: ASTM F606
Hardness Testing: ASTM F606

WE HEREBY CERTIFY THE ABOVE BOLTS HAVE BEEN MANUFACTURED BY ROCKFORD BOLT & STEEL
IN OUR FACILITY IN ROCKFORD, ILLINOIS WITH MATERIAL WHICH WAS MELTED AND MANUFACTURED
IN U.S.A. WE FURTHER CERTIFY THAT THIS IS A TRUE REPRESENTATION OF INFORMATION PROVIDED
BY THE MATERIALS SUPPLIER AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT
QUALITY MEET OR EXCEED ALL APPLICABLE TEST, PROCESSES, AND INSPECTION REQUIREMENTS
PER THE ABOVE SPECIFICATION. THIS REPORT MAY NOT BE REPRODUCED EXCEPT IN FULL, WITHOUT
THE WRITTEN APPROVAL OF ROCKFORD BOLT. THE REPORT MUST NOT BE USED BY THE CLIENT TO
CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY NVLAP, NIST, OR ANY AGENCY
OF THE U.S. GOVERNMENT.
\*THIS INFORMATION IS NOT COVERED BY ROCKFORD BOLT AND STEEL'S NVLAP ACCREDITATION.\*



NVLAP LAB CODE 200255-0





### Mill Certification 12/31/2019

MTR#:322914-1  
Lot #:10010178321  
2911 E NUCOR ROAD  
PO BOX 309  
NORFOLK, NE 68701 US  
402-644-0200  
Fax: 402-644-0329

Sold To: KREHER STEEL CO LLC  
1550 N 25TH AVE  
MELROSE PARK, IL 60160 US

Ship To: KREHER STEEL CO LLC  
1550 N 25TH AVE  
MELROSE PARK, IL 60160 US

Customer PO	1-58695	Sales Order #	10023420 - 2.2
Product Group	Hot Roll - Engineered Bar	Product #	1071853
Grade	1045CA4	Lot #	10010178321
Size	0.75"	Heat #	100101783
BOL #	BOL-410411	Load #	322914
Description	Hot Roll - Engineered Bar Round 3/4" 1045CA4 24' 3" [291"] 8001-10000 lbs	Customer Part #	
Production Date	12/17/2019	Qty Shipped LBS	48120
Product Country Of Origin	United States	Qty Shipped EA	1320
Original Item Description		Original Item Number	

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.

Melt Country of Origin : United States

Melting Date: 12/04/2019

C (%)	Mn (%)	P (%)	S (%)	Si (%)	Ni (%)	Cr (%)	Mo (%)	Cu (%)	V (%)	Nb (%)	Zr (%)
0.50	0.75	0.011	0.018	0.18	0.09	0.14	0.03	0.16	0.003	0.001	0.002
N (PPM)	Sn (%)	Al (%)	Pb (%)	Ca (%)	B (%)	As (%)					
67	0.007	0.03	0.000	0.002	0.0000	0.004					

Ni + Cr + Mo (%) : 0.25

Austenitic fine grain by chemical analysis per the latest revision of ASTM A29  
Reduction Ratio 99.34 : 1

**ASTM E45 Method A (Worst)**

Sulfides: T: 1.5 H: 0.5 Alumina : T: 1.0 H: 0.5 Silicates T: 0.5 H: 0.0 Globular T: 1.0 H: 0.5

**Other Test Results**

Macroetch E381 Surface : 1 Macroetch E381 Mid Radius : 1 Macroetch E381 Center : 2  
DI Calculated (IN) : 1.47

**Comments:**

ASTM A576-90B  
JDM AO QL-2  
EN 10204 3.1  
EN 10204 3.1  
All manufacturing processes of the steel materials in this product, including melting, have been performed in the United States.  
Finished product is hot rolled in the United States.  
All products produced are weld free.  
Mercury, in any form, has not been used in the production or testing of this material.  
Test conform to ASTM A29-16, ASTM E415 and ASTM E1019-resulphurized grades or applicable customer requirements.  
All material melted at Nucor Steel Nebraska is produced in an Electric Arc Furnace.  
Strand Cast  
Tests included in ISO 17025 scope: Chemistry, Tensile, Brinell Hardness, Rockwell Hardness, Inclusion, and Grain Size.  
Exporting Country-USA  
Sales@nucome.com

NBMG-10 January 1, 2012

Jim Hill, Division Metallurgist

Page 1 of 2

**NUCOR**

**Mill Certification**  
12/31/2019

MTR#:322914-1  
Lot #:10010178321  
2911 E NUCOR ROAD  
PO BOX 309  
NORFOLK, NE 68701 US  
402-644-0200  
Fax: 402-644-0329

---

NBMG-10 January 1, 2012

  
Jim Hill, Division Metallurgist

Page 2 of 2

# Birmingham Fastener Manufacturing

P.O. Box 10323  
Birmingham, Alabama 35202  
(205) 595-3512

Pg 1 of 1

## Certificate of Compliance

Customer : AMERICAN TIMBER  
P.O. # : 20512

BFM # : 1628407  
Date Shipped : 10/28/2019

Item	Quantity	Description	Lot #	Heat #	Specification	Finish
1	9,131	3/4"-10 x 8 1/2" Carriage Bolt	107531	DL18100861	AWWAC111	Plain
2	3,000	3/4" Str Rd Washer	296127	227567	ASTM F436 T3	Plain
2	6,000	3/4" Str Rd Washer	D7926	198520	ASTM F436 T3	Plain
3	7,000	3/4"-10 Heavy Hex Nut	799283	75068613	ASTM A563 DH	Plain
4	4,300	5/8"-11 x 4" Hex Lag Screw	32361	10575880	AWWAC111	HDG

*Birmingham Fastener Manufacturing. hereby certifies that the material furnished in reference to the above purchase order number will meet or exceed the above assigned specifications.*

Signed: \_\_\_\_\_

  
Brian Hughes

Date: 11/04/2019



STAMPING THE FUTURE  
WROUGHT WASHER MFG., INC.



July 18, 2018

Certification of Compliance

008816  
BIRMINGHAM FASTENER & SUPPLY  
PO BOX 10323  
BIRMINGHAM, AL 35202

Wrought Washer  
Ordr/Lot Number  
296127

HT ORDER 271426

Heat Number	Chemical Analysis							
	C	Mn	P	S	Si	Cr	Cu	Ni
227567	0.360	0.620	0.016	0.002	0.276	0.467	0.266	0.257
Purchase Order Number	Part Description			Date Shipped	Quantity Shipped			
6187951	3/4 F436 RD TYPE 3 W HT			07/17/2018	9,000			

We hereby certify that the subject parts conform to the requirements of the applicable specification indicated for the subject parts and are in complete conformance to F436-11. We hereby certify that the subject parts were hardened to RC 38-45.

We hereby certify that all statutory requirements as to American Production and Labor Standards and all conditions of purchase applicable to the transaction have been complied with and that the subject parts were melted and manufactured in the U.S.A. No weld repairs were made to the material.

Truly yours,  
Wrought Washer Mfg., Inc.

*Paul J. Seggelink*

Paul Seggelink  
Q.A. Manager

*Susan M. Daoust*

Sworn and subscribed before me on July 18, 2018  
My commission expires April 24, 2021



(036) TYPE 3, HT, F436  
WW INTERNAL USE : 65866206/001/010928/47103

1901 CHICORY RD. • MOUNT PLEASANT, WI 53403 • PHONE (262) 554-9550 • FAX (262) 554-9584  
VISIT OUR WEBSITE: [www.wroughtwasher.com](http://www.wroughtwasher.com)

TR No. 612061-08-01

135

2024-02-06

**NUCOR**  
SHEET MILL GROUP

Nucor Steel-Crawfordsville  
4537 South Nucor Blvd  
Crawfordsville, IN 47933-0507

Order Number: 225084 - 0001  
Order Dimensions: 0 1380 in X 51 3750 in  
HOT ROLLED BAND, D40 WEATHERING, HML

Certified to ordered chemistry

Coil Number  
1668849 DCE

Part Number  
724148

METALLURGICAL TESTING CERTIFICATION

97659

K033542

Certificate Number: 447332  
Date Issued: 02/14/2017  
Page: 1 of 1

Customer Name: WROUGHT BASKET MFG. INC.  
Customer Address: 2100 SOUTH BAY STREET

MILWAUKEE WI 53207

Cost PO Number: H2364

CHEMICAL ANALYSIS

Heat	Slab	C	Mn	P	S	Si	Cu	Sn	Ni	Cr	Mo	Al	N	V	Nb	Ti	B	Sh
227567	02	0.35	0.620	0.016	0.002	0.276	0.266	0.008	0.257	0.457	0.021	0.036	0.008	0.004	0.002	0.005	0.0005	0.003

WE HEREBY CERTIFY THE ABOVE IS CORRECT AS CONTAINED IN THE RECORDS OF THE CORPORATION  
MELTED AND ROLLED IN THE USA

02-0261 04/19/2007

NUCOR QUALITY ASSURANCE

*[Signature]*  
MICHAEL L. SATE


HEAT TREAT PROCESSING CHART

Wrought Washer Mfg., Inc.

CUSTOMER 314 TYPE 3 TAG # 989918 WT. 6865 PG.      Of       
 I.C. # 060924 LOT # 47103 FURNACE # 2001 Set-up Checklist       
 ORDER # 271426 O.D. 1.469 I.D. .813 THK .148 RC SPECS 38-45 Verification     

DATE	<u>3-18</u>																			
TIME	<u>2<sup>00</sup></u>	<u>3<sup>00</sup></u>	<u>4<sup>00</sup></u>	<u>.430</u>																
OPERATOR #	<u>455</u>																			
CARBON	<u>36</u>																			
Mn	<u>62</u>																			
GAS FLOW RATE	<u>125</u>																			
NITROGEN FLOW	<u>125</u>																			
DRAW TEMP	<u>815</u>																			
QUENCH %	<u>620</u>																			
RETORT SPEED																				
BEND TEST																				
DYE PEN TEST																				
RC TEST BLOCK	<u>40</u>																			

	Quench	Temp	Quench	Temp	Quench	Temp	Quench	Temp	Quench	Temp	Quench	Temp	Quench	Temp	Quench	Temp	Quench	Temp	Quench	Temp	
Sample	1	53	44	55	41	58	42														
Measurements	2	55	43	55	43	53	42														
	3	55	43	56	41	55	41														
	4	55	43	55	42	55	41														
	5	54	44	56	42	54	42														
Sum		272	217	277	209	272	208														
Average X		54	43	55	42	54	42														
Range R		2	1	1	2	2	1														
Notes																					
Core Hardness																					



Surface RC: 41-42 Core RC: 40-42 Inspection Results RC Inspected By: RC Date: 3-18-13

Prestige  
Stamping,  
LLC



23513 Groesbeck Highway  
Warren, Michigan 48089  
(586) 773-2700 \* Fax (586) 773-2298  
www.PrestigeStamping.com

**PRODUCT CERTIFICATION**  
CERTIFICATION NUMBER

201114

THIS IS TO CERTIFY THE PRODUCT STATED BELOW WAS FABRICATED AND PROCESSED TO THE ORDER AS INDICATED AND CONFORMS TO THE APPLICABLE SPECIFICATIONS AND STANDARDS.

**Customer:** BIRMINGHAM FASTENER & SUPPLY  
HANCEVILLE DIST CENTER  
1100 MAIN ST  
HANCEVILLE, AL 35077

<b>Customer Part:</b> 3/4" TYPE3 F436	<b>Steel Supplier:</b> STEEL TECHNOLOGIES LLC
<b>Prestige Part:</b> P1480CH00	<b>Grade:</b> SAE CF436 TYPE3 STEEL
<b>Part Name:</b> 3/4"F436 TYPE 3	<b>Lot:</b> D7926
<b>Purchase Order:</b> 6213872	<b>Heat:</b> 198520
<b>Shipment BOL:</b> B219698	<b>Carbon:</b> .39
<b>Shipment ID:</b> A0238117	<b>Manganese:</b> .79
<b>Quantity:</b> 14400	<b>Phosphorous:</b> .02
<b>Manufacturers Marking:</b> "P"	<b>Sulfur:</b> .003
	<b>Silicon:</b> .24

SPECIFICATIONS

**HARDNESS:** TEST METHOD: ASTM E18  
HRC 38 - 45  
CHECK TO ASTM F606

TEST RESULTS

**HARDNESS:**  
HRC 41 - 43

USS/SAE LC Washers are manufactured to the requirements of ASTM F944 specifications  
Chemistry is as reported from raw material certification and does not fall under Prestige Stamping's accreditation.  
This product was produced under an IATF 16949 Quality Assurance System.  
IATF 16949 Certification No: 800334.  
Material was melted and manufactured in the U.S.A.  
This product was manufactured in Warren, Michigan U.S.A.  
This product conforms to all requirements for washers as produced according to A.S.T.M. F-436-13.  
Sampling Plan per P.S.I W.I. # 5.4.18.015.  
The test results only apply to the items tested.  
This test report must not be reproduced except in full without prior written approval.  
Materials used to manufacture these products are mercury, asbestos and radio activity free.  
Product is RoHS compliant.  
No weld repairs made to material.  
All certified product is AIS compliant.

  
FRANK SCHUBERT  
Quality Assurance Manager

D7926

**Wrought Washer Mfg., Inc.**

2100 S. Bay St., Milwaukee, Wisconsin 53207  
Phone: (414) 744-0771 Fax: (414) 744-4811

Processed for:

Prestige Stamping  
23513 Groesbeck Hwy  
Warren, MI 48089

The following coil was processed at Wrought Washer located in the USA on May 24, 2019 and shipped to Prestige Stamping on June 10, 2019.

Coil #: 14752  
Mill Coil #: 2396526  
Heat #: 198520  
Gauge: .136  
Mill coil weight: 42,500#  
Chemistry:

C	Mn	P	S	Al	Si	Cu	Ni	
.39000	.79000	.02000	.00300	.03000	.24000	.26300	.28600	
Cr	Mo	V	Nb/Cb	Ti	N	Ca	B	Sn
.47500	.01800	.00500	.00100	.00200	.00700	.00100	.00000	.01100



\_\_\_\_\_  
Signature  
Quality Manager

TR No. 612061-08-01

139

2024-02-06

**NUCOR**  
Nucor Steel Indiana  
4537 South Nucor Road  
Crawfordsville, IN 47933-0907

METALLURGICAL TESTING CERTIFICATION

0078096

Certificate Number: 825756  
Date Issued: 05/17/2019

Page: 1 of 1

Order Number: 314919 - 0001 HOT ROLLED PICKLED & ANNEALED  
Order Dimensions: 0.1360 in X 51.0000 in  
HRPA,CUT,1040 WEATHERING

Customer Name: BROUGHT WASHER MFG INC  
Customer Address: 2100 S BAY ST

Release Order: MILWAUKEE MI 53207  
Cust PO Number: H3539

Coil Number 2396525.000 HEAD  
L-Yield (ksi): 52.0  
L-Tensile (ksi): 79.8  
L-Elong (%): 30.0  
Part Number 724148-240 TONS  
Weight: 42,720 LBS  
Rockwell B: 83

CHEMICAL ANALYSIS

Heat	Slab	C	Mn	P	S	Si	Cu	Sn	Ni	Cr	Mo	Al	N	V	Nb	Ti	B	Sb
198520	04	0.39	0.790	0.020	0.003	0.240	0.263	0.011	0.286	0.475	0.018	0.030	0.007	0.005	0.001	0.002	<0.0005	0.001

Coil Number 2396526.000 HEAD  
L-Yield (ksi): 60.8  
L-Tensile (ksi): 87.2  
L-Elong (%): 24.0  
Part Number 724148-240 TONS  
Weight: 42,500 LBS  
Rockwell B: 89

CHEMICAL ANALYSIS

Heat	Slab	C	Mn	P	S	Si	Cu	Sn	Ni	Cr	Mo	Al	N	V	Nb	Ti	B	Sb
198520	05	0.39	0.790	0.020	0.003	0.240	0.263	0.011	0.286	0.475	0.018	0.030	0.007	0.005	0.001	0.002	<0.0005	0.001

WE HEREBY CERTIFY THE ABOVE IS CORRECT AS CONTAINED IN THE RECORDS OF THE CORPORATION  
MELTED AND ROLLED IN THE USA

GF-0261 04/01/2019

1-800-777-0950 MTR\_IND\_INQUIRIES@NUCOR.COM

NUCOR QUALITY ASSURANCE



**CERTIFICATE OF COMPLIANCE**

**ROCKFORD BOLT & STEEL CO.  
126 MILL STREET  
ROCKFORD, IL 61101  
815-968-0514 FAX# 815-968-3111**

**CUSTOMER NAME:** AMERICAN TIMBER & STEEL

**CUSTOMER PO:** 21451

**SHIPPER #:** 068659  
**DATE SHIPPED:** 04/17/2020

**LOT#:** P38393 R69206

**PRESTIGE STAMPING:** D5831, D5811

**SPECIFICATION:** ASTM SPECIFICATION F436-10 FOR HARDENED WASHERS

**COATING:** ASTM B695, CLASS 55, TYPE I MECHANICAL GALVANIZATION

**MECHANICAL GALV-PLATING:** 518053, 518051

**CHEMICAL COMPOSITION**

STEEL SUPPLIER	HEAT#	C	Mn	P	S
ARCELORMITTAL	9515612	0.29	1.19	0.025	0.002
ARCELORMITTAL	9514538	0.31	1.21	0.011	0.003

**HARDNESS:**

SPEC: RC38-45

ACTUAL: 41 - 42

ACTUAL: 41 - 42

**QUANTITY AND DESCRIPTION:**

8,800 PCS 3/4" STRUCTURAL WASHER

WE HEREBY CERTIFY THE ABOVE PARTS HAVE BEEN MANUFACTURED IN THE U.S.A. WITH DOMESTIC STEEL. WE FURTHER CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER, AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY ASSURE THAT ALL ITEMS FURNISHED ON THIS ORDER MEET OR EXCEED ALL APPLICABLE TESTS, PROCESS, AND INSPECTION REQUIREMENTS PER ABOVE SPECIFICATION.

**Prestige  
Stamping,  
Inc.**



23513 Groesbeck Highway  
Warren, Michigan 48089  
(586) 773-2700 \* Fax: (586) 773-2298  
www.PrestigeStamping.com

**PRODUCT CERTIFICATION**  
CERTIFICATION NUMBER

184881

**THIS IS TO CERTIFY THE PRODUCT STATED BELOW WAS FABRICATED AND PROCESSED TO THE ORDER AS INDICATED AND CONFORMS TO THE APPLICABLE SPECIFICATIONS AND STANDARDS.**

**Customer:** ROCKFORD BOLT AND STEEL CO  
126 MILL ST  
ROCKFORD, IL 61101

**Customer Part:** 095763-MG  
**Prestige Part:** P1480HP200  
**Part Name:** 3/4" F436 M/G  
**Purchase Order:** P38393  
**Shipment BOL:** B210774  
**Shipment ID:** A0227178  
**Quantity:** 4000  
**Manufacturers Marking:** "P"

**Steel Supplier:** HORIZON STEEL CO.  
**Grade:** CF436 GRADE STEEL  
**Lot:** D5831  
**Heat:** 9515612  
**Carbon:** .29 (.22 - .57)  
**Manganese:** 1.19 (.6 - 1.6)  
**Phosphorous:** .025 (.04 Max.)  
**Sulfur:** .002 (.05 Max.)  
**Silicon:** .23 (.15 Min.)

**SPECIFICATIONS**

**HARDNESS:** TEST METHOD: ASTM E18  
HRC 38 - 45  
CHECK TO ASTM F606

**PLATING:** TEST METHOD: ASTM B499  
0.0022" Min.  
MECH GALV TO ASTM B695  
CLASS 55 TYPE 1

**TEST RESULTS**

**HARDNESS:**  
HRC 41 - 42

**PLATING:**  
0.0022" - 0.0030"

US/DIN LC Washers are manufactured to the requirements of ASTM F959 specifications.  
Chemistry is as reported from raw material certification and does not fall under Prestige Stamping's accreditation.  
This product was produced under an ISO/TS 16949 Quality Assurance System.  
ISO/TS 16949 Certification No: 0082905.  
Material was melted and manufactured in the U.S.A.  
This product was manufactured in Warren, Michigan U.S.A.  
This product conforms to all requirements for washers as produced according to A.S.T.M. F-436-13.  
Sampling Plan per P.S.I.W.L. 9 B.4.78.015.  
The test results only apply to the items tested.  
This test report must not be reproduced except in full without prior written approval.  
Materials used to manufacture these products are magnetic, radioactive and radio activity free.  
Product is RoHS compliant.  
No weld repairs made to material.  
All certified product is AISI compliant.

  
**FRANK SCHUBERT**  
Quality Assurance Manager

Econ Information System

07/02/18


14:15

HSIE

PAGE 1 of 1

R69206

1457


 <b>Harrison Steel Co.</b> 50390 UTICA DRIVE SHELBY TOWNSHIP, MI 48315 Phone: (586) 552-2135 Fax: (586) 586-3116	<b>BILL TO:</b> PRESTIGE STAMPING 23513 GROESBECK HWY. WARREN, MI 48090	<b>SHIP TO:</b> PREST PRESTIGE STAMPING, INC 23513 GROESBECK HIGHWAY WARREN, MI 48090
--	--	--

**BOL# 613604**  
 Ship Date: 4/20/2018

<b>Order Information</b>		
SO #: 908562-1 PART #: ZZ5600122 YOUR PART #: PART P1490H00 PART DESC : HRPO F436 GRADE *MELTED & MFG IN USA*	POR:30803-02 END USE PO#: REV #: END USE PO#: REV #:	CPO#: Use End User PO#:

<b>Chemistry</b>	Heat Number	9515812									
C: 0.2900	Mn: 1.1900	P: 0.0250	S: 0.0020	Si: 0.2300	Cr: 0.0200	Al: 0.0480	V: 0.0040	NI: 0.0100	Nb/CB: 0.0010		
Cr: 0.0300	Ti: 0.0020	N: 0.0038	Mn: 0.0100	Ca: 0.0015	B: 0.0000	Sn: 0.0120					

Tag No	Product	Gage	Width	Length	Weight	Rb	Tensile		Yield		Elong	R-VAL	N VAL	Test Method	Pull Code
							psi	Mpa	psi	Mpa					
4374254	HP HSLA	.122 MIN	5.5000		5.224	92									N/A
4374255	HP HSLA	.122 MIN	5.5000		5.256	92									N/A
4374256	HP HSLA	.122 MIN	5.5000		5.266	92									N/A
4374257	HP HSLA	.122 MIN	5.5000		5.266	92									N/A
4374259	HP HSLA	.122 MIN	5.5000		5.240	92									N/A
4374260	HP HSLA	.122 MIN	5.5000		5.266	92									N/A
4374261	HP HSLA	.122 MIN	5.5000		5.282	92									N/A
4374262	HP HSLA	.122 MIN	5.5000		5.294	92									N/A
4374263	HP HSLA	.122 MIN	5.5000		5.262	92									N/A
4374264	HP HSLA	.122 MIN	5.5000		5.186	92									N/A
4374265	HP HSLA	.122 MIN	5.5000		5.210	92									N/A
4374266	HP HSLA	.122 MIN	5.5000		5.234	92									N/A
4374267	HP HSLA	.122 MIN	5.5000		5.220	92									N/A
4374268	HP HSLA	.122 MIN	5.5000		5.290	92									N/A

 <b>Horizon Steel Co.</b> 60380 UTICA DRIVE SHELBY TOWNSHIP, MI 48315 Phone: (586) 532-2135 Fax: (586) 566-3118	<b>BILL TO:</b> PRESTIGE STAMPING 23513 GROESBECK HWY. WARREN, MI 48090	<b>SHIP TO:</b> PREST PRESTIGE STAMPING, INC 23513 GROESBECK HIGHWAY WARREN, MI 48090
<b>BOL# 613604</b> Ship Date: 4/20/2018		

4374269	HP HSLA	.122 MIN	5.5000	5,380	92	N/A
4374270	HP HSLA	.122 MIN	5.5000	5,414	92	N/A
4374271	HP HSLA	.122 MIN	5.5000	5,410	92	N/A
4374272	HP HSLA	.122 MIN	5.5000	5,402	92	N/A

I certify that the test results shown are correct as contained in the records of Horizon Steel Co. and in compliance with the requirements of the order.

*Mary Claire Collins*

Mary Claire Collins  
Quality Assurance

ArcelorMittal  
 Cleveland  
 Flat Carbon  
 Cleveland, OH 44116



Horizon Steel Company  
 50390 Utica Dr.  
 Shelby Township, MI 48315

Dear Jim,

December 3, 2017

I have reviewed our records and have confirmed that the following coils were manufactured from heats that were "melted/melted" at the Cleveland Facility.

The heat numbers and the relating coils are stated below:

Seq	Heat Nbr	Tag Nbr
1	9416483	878263
		878653
		878652
		878651
	9515612	878650
		878657
		878656
		878655
2		878654
	4188285	877647
		877648
		877646
3		878490
4	9414946	832687
5	9415687	832689
	9416254	869574
6		869326
	9416386	875805
7		875804
8	9416387	875809
9	8815105	869062
10	8815330	869337
		875803
	8818908	875807
11		875808
12	8815614	877080
13	8815615	877130

1.)

Chemical: Lot#		P R O P E R T I E S							
9414483		C	Mn	P	S	Si	Cu	Ni	
		0.3100	1.1900	0.0120	0.0020	0.2300	0.0300	0.0100	
		Cr	Mo	Sn	Al	V	Co	N	
		0.0200	0.0100	0.0250	0.0440	0.0020	0.0000	0.0040	
		B	Zr	Ti	Fe	Ca	O		
		0.0000		0.0020	0.0010	0.0014			

2.)

Chemical: Lot#		P R O P E R T I E S							
5315612		C	Mn	P	S	Si	Cu	Ni	
		0.2900	1.1900	0.0250	0.0020	0.2300	0.0200	0.0100	
		Cr	Mo	Sn	Al	V	Co	N	
		0.0300	0.0100	0.0120	0.0480	0.0040	0.0010	0.0040	
		B	Zr	Ti	Fe	Ca	O		
		0.0000		0.0020	0.0010	0.0015			

3.)

Chemical: Lot#		P R O P E R T I E S							
4188281		C	Mn	P	S	Si	Cu	Ni	
		0.3100	1.1100	0.0120	0.0010	0.2400	0.0200	0.0100	
		Cr	Mo	Sn	Al	V	Co	N	
		0.0400	0.0100	0.0020	0.0350	0.0020	0.0000	0.0050	
		B	Zr	Ti	Fe	Ca	O		
		0.0001		0.0020	0.0010	0.0023			



Prestige  
Stamping,  
Inc.



23513 Greenbank Highway  
Warren, Michigan 48089  
(586) 773-2700 \* Fax (586) 773-2298  
www.PrestigeStamping.com

**PRODUCT CERTIFICATION**  
CERTIFICATION NUMBER

184880

THIS IS TO CERTIFY THE PRODUCT STATED BELOW WAS FABRICATED AND PROCESSED TO THE ORDER AS INDICATED AND CONFORMS TO THE APPLICABLE SPECIFICATIONS AND STANDARDS.

**Customer:** ROCKFORD BOLT AND STEEL CO  
126 MILL ST  
ROCKFORD, IL 61101

**Customer Part:** 095763-MG  
**Prestige Part:** P1480HP200  
**Part Name:** 3/4" F436 M/G  
**Purchase Order:** P38393  
**Shipment BOL:** B210774  
**Shipment ID:** A0227178  
**Quantity:** 16000  
**Manufacturers Marking:** "P"

**Steel Supplier:** HORIZON STEEL CO.  
**Grade:** CF436 GRADE STEEL  
**Lot:** D5811  
**Heat:** 9514538  
**Carbon:** .31 (.22 - .57)  
**Manganese:** 1.21 (.6 - 1.6)  
**Phosphorous:** .011 (.04 Max.)  
**Sulfur:** .003 (.05 Max.)  
**Silicon:** .24 (.15 Min.)

SPECIFICATIONS

**HARDNESS:** TEST METHOD: ASTM E18  
HRC 38 - 45  
CHECK TO ASTM F606

**PLATING:** TEST METHOD: ASTM B499  
0.0022" Min.  
MECH GALV TO ASTM B695  
CLASS 55 TYPE 1

TEST RESULTS

**HARDNESS:**  
HRC 41 - 42

**PLATING:**  
0.0022" - 0.0030"

US/SAE LC Washers are manufactured to the requirements of ASTM F294 specifications.  
Chemistry is as reported from raw material certification and does not fall under Prestige Stamping's accreditation.  
This product was produced under an ISO/TS 16949 Quality Assurance System.  
ISO/TS 16949 Certificate No: 0052333.  
Material was melted and manufactured by the U.S.A.  
This product was manufactured in Warren, Michigan U.S.A.  
This product conforms to all requirements for washers as produced according to A.S.T.M. F-498-12.  
Sampling Plan per P.S.I W.A. # 8-4-18.016.  
The test results only apply to the items tested.  
This test report must not be reproduced except in full without prior written approval.  
Materials used to manufacture these products are aerospace and radio activity free.  
Product is RoHS compliant.  
No weld repairs made to material.  
All certified product is AS compliant.

  
FRANK SCHUBERT  
Quality Assurance Manager


Econ Information System

07/02/18

14:15

HSIE

PAGE 1 of 1

 <b>Horizon Steel Co.</b> 50990 UTICA DRIVE SHELBY TOWNSHIP, MI 48315 Phone: (588) 532-2135 Fax: (588) 598-3118		<b>BILL TO:</b> PRESTIGE STAMPING 23513 GROESBECK HWY. WARREN, MI 48090	<b>SHIP TO:</b> PREST PRESTIGE STAMPING, INC 23513 GROESBECK HIGHWAY WARREN, MI 48090												
<b>BOL# 613454</b> Ship Date: 4/16/2018															
<b>Order Information</b>															
SO #: 804873 -1 PART #: ZZ5508122 YOUR PART #: PART P1480H00 PART DESC: HRPO F438 GRADE "MELTED & MFG IN USA"		POW:30179-05 END USE POW: REV #:	CPO#: Use End User POW:												
<b>Chemistry</b> Heat Number 9514538															
C: 0.3100	Mn: 1.2100	P: 0.0110	S: 0.0030	Si: 0.2400	Cu: 0.0400	Al: 0.0420	V: 0.0020	NE: 0.0300	Nb/CE: 0.0000*						
Cr: 0.0600	Ti: 0.0030	N: 0.0052	Mo: 0.0100	Ca: 0.0915	B: 0.0003	Sn: 0.0080									
Tag No	Product	Gage	Width	Length	Weight	Rb	Tensile		Yield		Elong	R VAL	N VAL	Test Method	Pull Code
							psi	Mpa	psi	Mpa					
4373537	HP HSLA	.122 MIN	5.5000		5.312	93									N/A
4373538	HP HSLA	.122 MIN	5.5000		5.352	93									N/A
4373539	HP HSLA	.122 MIN	5.5000		5.348	93									N/A
4373540	HP HSLA	.122 MIN	5.5000		5.338	93									N/A
4373549	HP HSLA	.122 MIN	5.5000		5.278	93									N/A
4373555	HP HSLA	.122 MIN	5.5000		5.332	93									N/A
4373556	HP HSLA	.122 MIN	5.5000		5.330	93									N/A
4373561	HP HSLA	.122 MIN	5.5000		5.292	93									N/A
4373564	HP HSLA	.122 MIN	5.5000		5.282	93									N/A

I certify that the test results shown are correct as contained in the records of Horizon Steel Co. and in compliance with the requirements of the order.

*Mary Claire Collins*

Mary Claire Collins  
 Quality Assurance

ArcelorMittal  
Cleveland  
Flat Carbon  
Cleveland, OH 44116



Horizon Steel Company  
30390 Utton Dr.  
Shelby Township, MI 48315

Dear Jim,

June 26, 2017

I have reviewed our records and have confirmed that the following coil was manufactured from a heat that was "melted/smelted" at the Cleveland Facility.

The heat number and the relating coils are stated below:

Heat number: 9614688      Coil numbers: 616143, 616157

Chemical: K099		P R O P E R T I E S									
951638		C	Si	P	S	Al	Ca	Mn	Cu	Ni	
		0.0100	1.2100	0.0110	0.0030	0.2400	0.0400	0.0300			
		Cu	Mo	Sb	Bi	V	Co	K			
		0.0000	0.0100	0.0000	0.0020	0.0020	0.0010	0.0000			
		B	Er	Ti	Sn	Cr					
		0.0000		0.0000	0.0010	0.0010					

Sincerely,

*Sharon Kovach*  
Account Manager - Special Products  
ArcelorMittal Cleveland  
T +1 216 428 6063 | F +1 440 848 8546

**CERTIFICATE OF COMPLIANCE**

**ROCKFORD BOLT & STEEL CO.  
126 MILL STREET  
ROCKFORD, IL 61101  
815-968-0514 FAX# 815-968-3111**

**CUSTOMER NAME:** AMERICAN TIMBER & STEEL

**CUSTOMER PO:** 21451

**SHIPPER #:** 068659  
**DATE SHIPPED:** 04/17/2020

**LOT#:** P39299 R73245

**PRESTIGE STAMPING:** D7506

**SPECIFICATION:** ASTM SPECIFICATION F436-10 FOR HARDENED WASHERS

**COATING:** ASTM B695, CLASS 55, TYPE I MECHANICAL GALVANIZATION

**MECHANICAL GALV-PLATING:** 120029-35

**CHEMICAL COMPOSITION**

**HARDNESS:**

STEEL SUPPLIER	HEAT#	C	Mn	P	S
STEEL DYNAMICS	21933130	0.52	0.7	0.011	0.001

**SPEC:** HRC 38-45

**ACTUAL:** 41 - 43

**QUANTITY AND DESCRIPTION:**

6,200 PCS 3/4" STRUCTURAL WASHER

WE HEREBY CERTIFY THE ABOVE PARTS HAVE BEEN MANUFACTURED IN THE U.S.A. WITH DOMESTIC STEEL. WE FURTHER CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER, AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY ASSURE THAT ALL ITEMS FURNISHED ON THIS ORDER MEET OR EXCEED ALL APPLICABLE TESTS, PROCESS, AND INSPECTION REQUIREMENTS PER ABOVE SPECIFICATION.

Prestige  
Stamping,  
LLC



23513 Groesbeck Highway  
Warren, Michigan 48089  
(586)773-2700 \* Fax (586)773-2298  
www.PrestigeStamping.com

**PRODUCT CERTIFICATION**  
CERTIFICATION NUMBER

211453

THIS IS TO CERTIFY THE PRODUCT STATED BELOW WAS FABRICATED AND PROCESSED TO THE ORDER AS INDICATED AND CONFORMS TO THE APPLICABLE SPECIFICATIONS AND STANDARDS.

**Customer:** ROCKFORD BOLT AND STEEL CO  
126 MILL ST  
ROCKFORD, IL 61101

**Customer Part:** 095763-MG  
**Prestige Part:** P1480HP200  
**Part Name:** 3/4" F436 M/G  
**Purchase Order:** P39299  
**Shipment BOL:** B224643  
**Shipment ID:** A0244690  
**Quantity:** 20000  
**Manufacturers Marking:** "P"

**Steel Supplier:** MARATHON METALS, LLC  
**Grade:** CF436 GRADE STEEL  
**Lot:** D8936  
**Heat:** 21933130  
**Carbon:** .52  
**Manganese:** .70  
**Phosphorous:** .011  
**Sulfur:** .001  
**Silicon:** .23

SPECIFICATIONS

**HARDNESS:** TEST METHOD: ASTM E18  
HRC 38 - 45  
CHECK TO ASTM F606

**PLATING:** TEST METHOD: ASTM B499  
0.0022" Min.  
MECH GALV TO ASTM B695  
CLASS 55 TYPE 1

TEST RESULTS

**HARDNESS:**  
HRC 41 - 43

**PLATING:**  
0.0022" - 0.0030"

USS/SAE LC Washers are manufactured to the requirements of ASTM F844 specifications  
Chemistry is as reported from raw material certification and does not fall under Prestige Stamping's accreditation.  
This product was produced under an IATF 16949 Quality Assurance System.  
IATF 16949 Certification No: 800334.  
Material was melted and manufactured in the U.S.A.  
This product was manufactured in Warren, Michigan U.S.A.  
This product conforms to all requirements for washers as produced according to A.S.T.M. F-436-13.  
Sampling Plan per P.S.I W.J. # S.A.18.015.  
The test results only apply to the items tested.  
This test report must not be reproduced except in full without prior written approval.  
Materials used to manufacture these products are mercury, asbestos and radio activity free.  
Product is RoHS compliant.  
No weld repairs made to material.  
All certified product is RoHS compliant.

  
FRANK SCHUBERT  
Quality Assurance Manager

R73245

Econ Information System

02/28/20

14:17

CTHO

PAGE 1 of 1

DP936

17Dec19 11:21 TEST CERTIFICATE No: MNP 8400

Sold By:  
 MARATHON METALS/MNP CORP P/O No 33352-01  
 6440 MACK Rel  
 DETROIT, MI 48207 S/O No MNP 61139-001  
 Tel: 313-571-9544 Fax: 313-971-6449 B/L No MNP 73301-001 Shp 17Dec19  
 Inv No Inv

Sold To: ( 912) Ship To: (001)  
 PRESTIGE STAMPING INC. PRESTIGE STAMPING INC.  
 23513 GROESBECK HIGHWAY 23513 GROESBECK HIGHWAY  
 WARREN MI 48090 P.O. BOX 1086  
 WARREN MI 48090

Tel: 586 773-2700 Fax: 586 773-2298

CERTIFICATE of ANALYSIS and TESTS Cert. No: MNP 8400 17Dec19

Part No P1480H00.  
 P&C 1025 CARBON P436 Pcs Mgt  
 .122/.128 X 5.5000" 16 38,465

MILL CERTS  
 MELTED & MFG IN USA  
 ROCKWELL B90

Heat Number	Tag No	Pcs	Mgt
21933130	S20639	2	4,770
21933130	S20640	2	4,830
21933130	S20641	2	4,835
21933130	S20642	2	4,810
21933130	S20644	2	4,800
21933130	S20645	2	4,820
21933130	S20646	2	4,820
21933130	S20647	2	4,780

Heat Number \*\*\* Chemical Analysis \*\*\*  
 21933130 C=0.5200 Mn=0.7000 P=0.0110 S=0.0010 Al=0.0270 Si=0.2300  
 Nb=0.0010 N=0.0080 V=0.0040 Ti=0.0020 Cu=0.1000 Cr=0.0700  
 Sn=0.0050 Ni=0.0400 Mo=0.0200 Ca=0.0020

Page: 1 .... Last



TR No. 612061-08-01

152

2024-02-06



**Steel Dynamics, Inc.**  
Flat Roll Group

4500 County Road 59  
Butler, IN 46721 USA  
Telephone (260) 868-8000  
Fax (260) 868-8955

## Metallurgical Certification

Cert #

Ship To	United States					Contact					
	MNP c/o Marathon Metals 6440 Mack					Contact					
Sold To	Detroit, MI 48207 United States										
	Length	2,134 Ft. / 650 m	Width	49.7500 in. / 1,264 mm	Chem Treat	No					
Weight	45,230 lbs / 20,515.97 kg	Gauge	0.1220 in. / 3.10 mm	Mn	Oiled	No					

Coil #		Coil Alias	
Order #		Heat #	21933130
Line Item #	5	PO #	MNP
Part #	Washers		
Material Spec.	SAE 1050		
Product Desc.	Prime Processed Hot Rolled Band		
Cert Comment	Customer specified chemistry - SDI is not responsible for properties		
Surface Treatment			

Ladle Chemical Analysis (%)

C	Mn	P	S	Si	Al	Cr	Ni	Cr	Mo	Sn	N	v	Nb	Ti	B	Ca	Pb	Zr
0.52	0.70	0.011	0.001	0.28	0.027	0.10	0.04	0.07	0.02	0.005	0.008	0.004	0.001	0.002	0.0000	0.002	0.000	0.0004

Mechanical Properties (if applicable)

Tests on Sample      English      Metric

*Hiroshi Kimura*  
Hiroshi Kimura  
Metallurgist

Shipped from Butler, IN, United States.

Melted, thin slab cast and rolled by proud Americans in Butler, IN, USA.

SDI does not weld or repair Prime Processed Hot Rolled Band products.

All tests were performed according to applicable standards and are correct as contained in the records of the company.

# Birmingham Fastener Manufacturing

P.O. Box 10323  
Birmingham, Alabama 35202  
(205) 595-3512

Pg 1 of 1

## Certificate of Compliance

Customer : AMERICAN TIMBER  
P.O. # : 20512

BFM # : 1628407  
Date Shipped : 10/28/2019

Item	Quantity	Description	Lot #	Heat #	Specification	Finish
1	9,131	3/4"-10 x 8 1/2" Carriage Bolt	107531	DL18100861	AWWAC111	Plain
2	3,000	3/4" Str Rd Washer	296127	227567	ASTM F436 T3	Plain
2	6,000	3/4" Str Rd Washer	D7926	198520	ASTM F436 T3	Plain
3	7,000	3/4"-10 Heavy Hex Nut	799283	75068613	ASTM A563 DH	Plain
4	4,300	5/8"-11 x 4" Hex Lag Screw	32361	10575880	AWWAC111	HGD

**Birmingham Fastener Manufacturing. hereby certifies that the material furnished in reference to the above purchase order number will meet or exceed the above assigned specifications.**

Signed:  Date: 11/04/2019  
Brian Hughes



**FONTANA FASTENERS**  
PLANT FRANKFORT LE

# TEST REPORT

Operations Center  
3281 West County Road 0 NS  
Frankfort, IN 46041-6966  
T. 765.654.0477  
F. 765.654.0857

Ship Date	10-22-19
Certification	LD13838*1*P20012048
Report Date	10-22-19

Cust PO	6225994
Lot Nbr	799283
Quantity	18000
Mfg Date	02-26-18

BIRMINGHAM FASTENER & SUPPLY  
1100 MAIN STREET SE  
HANCEVILLE, AL 35077

PART INFORMATION			
Part Number	75CNDHF/D	Finish	PLAIN
Description	A563 DH3 HV 3/4-10 ASME B18.2.2 HEAVY HEX NUT MADE IN USA	Head Marking	LE DH3 USA

RAW MATERIAL ANALYSIS							
Steel Heat Nbr	Steel Supplier	Steel Grade	Code	Element	Rqd Min Pct	Rqd Max Pct	Percent
GER75068613-26	GERDAU MACSTEEL INC	4140 MOD	C	Carbon	0.40	0.45	0.42
			Mn	Manganese	0.90	1.00	0.95
			P	Phosphorus	0.000	0.040	0.011
			S	Sulfur	0.000	0.050	0.006
			Si	Silicon	0.150	0.250	0.190
			Ni	Nickel	0.20	0.30	0.24
			Cr	Chromium	0.45	0.65	0.53
			Mo	Molybdenum	0.15	0.25	0.20
			Cu	Copper	0.20	0.30	0.23
			Al	Aluminum	0.015	0.035	0.020
			V	Vanadium	0.000	0.010	0.002

Certification test results include those reported by the following laboratories:

Fontana Fasteners, Inc., ISO17025-A2LA Cert#0122.02, 05-31-20

MECHANICAL PROPERTIES					
Wedge Angle					
Proof Load	58450/175000 (lbs/Psi)				
Test Performed	Required	High	Low	Average	Samples
NUT PROOF, PSI	175000 / 175000	175000	175000	175000	10
Core Hardness, HRC	32 / 38	34	26	30	13



# TEST REPORT

**Operations Center**  
 3281 West County Road 0 NS  
 Frankfort, IN 46041-6966  
 T. 765.654.0477  
 F. 765.654.0857

Ship Date	10-22-19
Certification	LD13838*1*P20012048
Report Date	10-22-19

Cust PO	6225994
Lot Nbr	799283
Quantity	18000
Mfg Date	02-26-18

### Applicable Standards, Specifications, and Sampling Schemes:

Test methods in accordance to ASTM F606/ISO 898-1 where applicable. Sampling plan in accordance to ASTM F1470. Thread fit and dimensional properties are compliant to ASME B18.2.1. Mechanical properties are according to SAE J429 or ISO 898-1 were applicable. Bolts passed a surface discontinuity inspection per ASTM F788. These bolts were manufactured in the USA from domestic material and were not produced from heat in which Bismuth, Selenium, Tellurium, or Lead was intentionally added. Bolts were not exposed to Mercury or any other metal alloy that is liquid at ambient temperature during processing or while in our possession. The listed standards, specifications, and sampling schemes are of the revision in effect on the date of manufacture unless noted otherwise. Only those standards specifically noted under "test methods" or "additional test methods" are included on LE's scope of laboratory accreditation.

### Additional Information

None

This lot has been found to conform to the requirements of the above standards and specifications

We certify The product furnished by Fontana Fasteners, Inc. was manufactured, sampled, tested, and inspected in accordance with the standards and specifications listed above and with Fontana Fasteners, Inc. Quality Manual in effect as of the date of manufacture. The above data accurately represents values provided by Fontana Fasteners, Inc. suppliers and/or values generated in one of Fontana Fasteners, Inc. A2LA accredited laboratories. This test report relates only to the sample tested above. This document may only be reproduced unaltered and may not be used for any purpose other than the purpose of certifying the same or lesser quantity of the product specified herein. Reproduction, alteration or use of this document for any other purpose is prohibited, except as expressly provided in this certification. Fontana Fasteners, Inc. makes no (and disclaims all) representations, warranties and guarantees whatsoever, whether express, implied or statutory, including, without limitation, any warranty of merchantability or fitness for a particular purpose.

Quality Management System including Test Reports managed by: Josh Lowery - Quality Supervisor, Fontana Fasteners Inc.



**CERT #0122.02**  
**"MECHANICAL FIELD OF TESTING"**



GERDAU SPECIAL STEEL NORTH AMERICA  
 5591 MORRILL ROAD  
 JACKSON, MICHIGAN 49201

**CERTIFIED MATERIAL TEST REPORT**

<b>CUSTOMER ORDER NUMBER</b> 130651	<b>CUSTOMER PART NUMBER</b> 95B223700A4	<b>HEAT NUMBER</b> 75068613	<b>WORK ORDER NUMBER</b> 313378 101	<b>DATE</b> 9/25/17
--	--	--------------------------------	--	------------------------

210mm Billet

REPORT TO

SHIP TO

ACUMENT GLOBAL TECH.  
 DBA: FONTANA FASTENERS  
 3281 W COUNTRY RD 0 NS

FONTANA FASTENERS INC-MFG  
 3281 W COUNTY RD 0 NS

FRANKFORT , IN 46041

FRANKFORT , IN 46041

**ORDERED**

<b>GRADE</b> 4140 MOD	<b>SIZE</b> 37.MM RND	<b>LENGTH</b> 20'
--------------------------	--------------------------	----------------------

**CUSTOMER SPECIFICATIONS**  
 CHEMISTRY ONLY: ASTM A563-15 GRADE DH3/ASTM A194-15 GRADE 2H

**CHEMICAL ANALYSIS**

C	Mn	P	S	Si	Ni	Cr	Mo	Cu	Sn	Al
0.42	0.95	0.011	0.006	0.19	0.24	0.53	0.20	0.23	0.009	0.020
V	Nb									
0.002	0.003									

HYDROGEN = 1.7 ppm

GRAIN SIZE SPECIFICATION ASTM E112 GRAINSIZE 5-8

REDUCTION RATIO

RATIO= 40.8 TO 1.0

\*\* MATERIAL 100% MELTED AND MANUFACTURED IN THE U.S.A. BY THE ELECTRIC ARC FURNACE AND CONTINUOUS CASTING METHOD. THE PRODUCT HAS NOT BEEN REPAIRED BY WELDING AND THIS MATERIAL HAS NOT BEEN EXPOSED TO MERCURY OR TO ANY OTHER METAL ALLOY THAT IS LIQUID AT AMBIENT TEMPERATURES DURING PROCESSING OR WHILE IN OUR POSSESSION. GERDAU MONITORS ALL INCOMING SCRAP AND ALL HEATS OF STEEL TO ENSURE THAT PRODUCTS SHIPPED ARE FREE OF RADIOACTIVE MATERIAL.

PAGE 1 OF 1

We certify that these data are correct and in compliance with specified requirements.

Gerdau Monroe  
 3000 East Front Street  
 Monroe, MI 48161

*Patrick Doyle* Patrick Doyle  
 Quality Assurance Representative

**CERTIFICATE OF COMPLIANCE**

**ROCKFORD BOLT & STEEL CO.**  
126 MILL STREET  
ROCKFORD, IL 61101  
815-968-0514 FAX# 815-968-3111

**CUSTOMER NAME:** AMERICAN TIMBER & STEEL

**CUSTOMER PO:** 21451

**SHIPPER #:** 068659  
**DATE SHIPPED:** 04/17/2020

**LOT#:** P38836 R71968  
**UNYTITE LOT:** 30836-75070667

**SPECIFICATION:** ASTM A583, GRADE DH HEAVY HEXAGONAL NUT

**COATING:** ASTM SPECIFICATION F2329 HOT DIP GALVANIZE  
**UNIVERSAL GALVANIZING:** 30836-75070667

**CHEMICAL COMPOSITION**

MILL	GRADE	HEAT#	C	Mn	P	S	Si
GERDAU	1045	75070667	.45	.77	.010	.035	.21

**HARDNESS:**

**SPEC:** 24-38  
**ACTUAL:** 29.05

**QUANTITY AND DESCRIPTION:**

175 PCS 3/4" HEAVY HEXAGONAL NUT

WE HEREBY CERTIFY THE ABOVE PARTS HAVE BEEN MANUFACTURED IN THE U.S.A. WITH DOMESTIC STEEL. WE FURTHER CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER, AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY ASSURE THAT ALL ITEMS FURNISHED ON THIS ORDER MEET OR EXCEED ALL APPLICABLE TESTS, PROCESS, AND INSPECTION REQUIREMENTS PER ABOVE SPECIFICATION.





Unytite, Inc.  
 One Unytite Drive  
 Peru, IL 61354  
 USA  
 Tel 815-224-2221  
 Fax 815-224-3434

**Customer Shipper**

Bill/Ship To: Rockford Bolt and Steel Co.  
 126 Mill St.  
 Rockford, IL 61101  
 Buyer: Rockford Bolt and Steel Co.

**Shipper No: 70061**



Ship Date: 7/31/19

Carrier: Customer Advise

Trailer No:

Shipping Tracking No:

Freight Terms: Collect

Class or Rate: 50

Pallets: 23

Cust PO	Rel	Customer Part No	Rev	Part Name	Part No	Rev	Lot No.	Containers	Ship Qty	Net	Gross	
P38828	12			AASHTO M180 Guard Rail, Double Recess, Hot Dipped Galv	AASHTO M180 5/8-11 +0.031 DBRC HDG G-RAIL NUT		30879-190519 (180)	(180) Keg (Can w/rd)	178,837	30,392 lbs	31,042 lbs	
P38836	12	✓		ASTM A563 Heavy Hex Nut, Grade DH, Hot Dipped Galv, Blue Dye	A563 3/4-10 +0.020 DH HHN HDG BLUE DYE		30836-75070667 (27)	(27) Keg (Can w/rd)	27,000	4,860 lbs	4,957 lbs	
<b>Total:</b>									<b>207 Containers</b>	<b>206,837</b>	<b>35,252 lbs</b>	<b>36,704 lbs</b>

Driver Signature  
*R71968*

Packing Slip

Subject to Unytite Inc. Standard Terms and Conditions of Sale, Document Number 13-002, dated 08-09-06. Document is subject to change without notice.

[https://www.plexonline.com/8a47ba35-4628-46d7-a084-85e6c5a421eb/Sales/Report\\_Shipper.asp?sm=1...](https://www.plexonline.com/8a47ba35-4628-46d7-a084-85e6c5a421eb/Sales/Report_Shipper.asp?sm=1...) 7/31/2019



**UNYTITE INC.**  
**INNOVATIVE FASTENING SYSTEMS**

Unytite, Inc.  
 One Unytite Drive  
 Peru, IL 61354  
 Tel 815-224-2221  
 Fax 815-224-3434

**INSPECTION CERTIFICATE**



**Customer:** Rockford Bolt and Steel Company **Ship To:**  
**Customer Part No:**  
**Customer PO No:** P38836 **Shipped Qty:**  
**Lot Number:** 30836-75070667



**Part No:** A563 3/4-10 +0.020 DH HHN HDG BLUE DYE



**Description:** ASTM A563 Heavy Hex Nut, Grade DH, Hot Dipped Galv, Blue Dye

**Manufactured Quantity:** 37,739

Specification	Amend	Specification	Amend
ASME B1.1	2003	ASME B18.2.2	2015
ASME B18.2.6	2011	ASTM A563	2015
ASTM F2329/F2329M	2015	ASTM F806/806M	2016
ASTM F812	2017		

**Test No:** 20170 **Test:** A563 DH Mechanical Properties

Description	Hardness (HRC)	Tempering Temp (500 degree F Min)	Proof Load (Pass/Fail) (ASTM Min LBS)	Shape & Dimension ASME B18.2.2	Thread Precision ASME B18.1.1	Visual ASTM F812
Sample Inspection	29.05	1,193	50,100	Pass	Pass	Pass


Heat No	Grade	Manufacturer	Origin	C	Mn	P	S	Si	Cr	Ni	Cu
75070667	1045	Gardau Special Steel North America	USA	0.4500	0.7700	0.010	0.0350	0.2100	0.1800	0.1100	0.2000

All tests are in accordance with the latest revisions of the methods prescribed in the applicable SAE and ASTM Specifications.

The samples tested conform the specifications as described/listed above and were manufactured free of mercury contamination and there is no welding performed in the production of the products. No heats to which Bismuth, Selenium, Tellurium, or Lead was intentionally added have been used to produce products.

The steel was melted and manufactured in the U.S.A. and the product was manufactured and tested in the U.S.A.

We certify that this data is true representation of information provided by the material supplier and our testing laboratory. This certified material test report relates only to the items listed on this document and may not be reproduced except in full.



*Chris Thorsen*

Thorsen, Chris - Supervisor, Quality

7/18/19

Date



GERDAU SPECIAL STEEL NORTH AMERICA  
 5591 MORRILL ROAD  
 JACKSON, MICHIGAN 49201

CERTIFIED MATERIAL TEST REPORT

CUSTOMER ORDER NUMBER P007419-2	CUSTOMER PART NUMBER B1045SC1.0000	INVT NUMBER 75070667	WORK ORDER NUMBER B19128 102	DATE 5/03/18
------------------------------------	---------------------------------------	-------------------------	---------------------------------	-----------------

210mm Billet

REPORT TO

UNYTITE INC  
 ONE UNYTITE DRIVE

PERU , IL 61354-9710

SHIP TO

UNYTITE, INC  
 LASALLE PLANT

325 CIVIC RD  
 LASALLE , IL 61301

ORDERED

GRADE 1045	SIZE 1"	FORM RND	LENGTH 24' 10 1/2"
---------------	------------	-------------	-----------------------

CUSTOMER SPECIFICATIONS  
 SAE 1045; ASTM E381-17; RMS 021 DATED 9/28/06

CHEMICAL ANALYSIS

C	Mn	P	S	Si	Ni	Cr	Mo	Cu	Sn	Al
0.45	0.77	0.010	0.035	0.21	0.11	0.16	0.04	0.20	0.010	0.003
V	Nb									
0.056	0.002									

GRAIN SIZE SPECIFICATION ASTM E112 FINE GRAIN 5-8

MICROCLEANLINESS SPECIFICATION ASTM E45 METH A

	A		B		C		D	
AVERAGE	T	H	T	H	T	H	T	H
	2.4	0.2	1.0	0.0	0.2	0.0	0.6	0.2

MACROSTRUCTURAL TEST PER - ASTM E381

PLATE I

	S	R	C
FRONT	1	1	1
MIDDLE	1	1	1

PAGE 1



CONTINUED ON PAGE 2



GERDAU SPECIAL STEEL NORTH AMERICA  
 5591 MORRILL ROAD  
 JACKSON, MICHIGAN 49201

**CERTIFIED MATERIAL TEST REPORT**

<small>CUSTOMER ORDER NUMBER</small> P007419-2	<small>CUSTOMER PART NUMBER</small> B1045SC1.0000	<small>HEAT NUMBER</small> 75070667	<small>WORK ORDER NUMBER</small> 319128 102	<small>DATE</small> 5/03/18
---	--	--	--	--------------------------------

210mm Billet

REPORT TO

SHIP TO

UNYTITE INC  
 ONE UNYTITE DRIVE

UNYTITE, INC  
 LASALLE PLANT

PERU , IL 61354-9710

325 CIVIC RD  
 LASALLE , IL 61301

**ORDERED**

<small>GRADE</small> 1045	<small>SIZE</small> 1" RND	<small>LENGTH</small> 24' 10 1/2"
------------------------------	-------------------------------	--------------------------------------

CUSTOMER SPECIFICATIONS  
 SAE 1045; ASTM E381-17; RMS 021 DATED 9/28/06

BACK 1 1 1  
 DECARB SPECIFICATION ASTM E1077  
 F TOTAL= 0.010  
 REDUCTION RATIO  
 RATIO= 86.7 TO 1.0  
 RESIDUAL MAX SPECIFICATION RMS 021  
 Ni+Cr = 0.2690

\*\* MATERIAL 100% MELTED AND MANUFACTURED IN THE U.S.A. BY THE ELECTRIC ARC FURNACE AND CONTINUOUS CASTING METHOD. THE PRODUCT HAS NOT BEEN REPAIRED BY WELDING AND THIS MATERIAL HAS NOT BEEN EXPOSED TO MERCURY OR TO ANY OTHER METAL ALLOY THAT IS LIQUID AT AMBIENT TEMPERATURES DURING PROCESSING OR WHILE IN OUR POSSESSION. GERDAU MONITORS ALL INCOMING SCRAP AND ALL HEATS OF STEEL TO ENSURE THAT PRODUCTS SHIPPED ARE FREE OF RADIOACTIVE MATERIAL. MATERIAL IS 100% RECYCLABLE.

PAGE 2 OF 2

*Patrick Doyle* Patrick Doyle

**CERTIFICATE OF COMPLIANCE**

**ROCKFORD BOLT & STEEL CO.  
126 MILL STREET  
ROCKFORD, IL 61101  
815-968-0514 FAX# 815-968-3111**

**CUSTOMER NAME:** AMERICAN TIMBER & STEEL

**CUSTOMER PO:** 21451

**SHIPPER #:** 068659  
**DATE SHIPPED:** 04/17/2020

**LOT#:** P38996 R72790  
**UNYTITE LOT:** 31631-6215051403

**SPECIFICATION:** ASTM A563, GRADE DH HEAVY HEXAGONAL NUT

**COATING:** ASTM SPECIFICATION F2329 HOT DIP GALVANIZE  
**UNIVERSAL GALVANIZING:** 31631-6215051403

**CHEMICAL COMPOSITION**

MILL	GRADE	HEAT#	C	Mn	P	S	Si
GERDAU	1045	62150514	.45	.72	.014	.014	.23


**HARDNESS:**

**SPEC:** 24-38  
**ACTUAL:** 29.11

**QUANTITY AND DESCRIPTION:**

13,975 PCS 3/4" HEAVY HEXAGONAL NUT

WE HEREBY CERTIFY THE ABOVE PARTS HAVE BEEN MANUFACTURED IN THE U.S.A. WITH DOMESTIC STEEL. WE FURTHER CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER, AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY ASSURE THAT ALL ITEMS FURNISHED ON THIS ORDER MEET OR EXCEED ALL APPLICABLE TESTS, PROCESS, AND INSPECTION REQUIREMENTS PER ABOVE SPECIFICATION.



**UNYTITE INC.**  
 INNOVATIVE FASTENING SYSTEMS

Unytite, Inc.  
 One Unytite Drive  
 Peru, IL 61354  
 Tel 815-224-2221  
 Fax 815-224-3434

**INSPECTION CERTIFICATE**

Customer: Rockford Bolt and Steel Co. Ship To:

Customer Part No:  
 Customer PO No: P38996  
 Lot Number: 31631-6215051403

Shipped Qty:

Part No: A563 3/4-10 +0.020 DH HHN HDG BLUE DYE



Description: ASTM A563 Heavy Hex Nut, Grade DH, Hot Dipped Galv, Blue Dye

Manufactured Quantity: 101,864

Specification	Amend	Specification	Amend
ASME B1.1	2003	ASME B18.2.2	2015
ASME B18.2.6	2011	ASTM A563	2015
ASTM F2329/F2328M	2015	ASTM F608/608M	2016
ASTM F812	2017		

Test No: 20686 Test: A563 DH Mechanical Properties

Description	Hardness (HRC)	Tempering Temp (800 degree F Min)	Proof Load (Pass ASTM Min LBS)	Shape & Dimension ASME B18.2.2	Thread Precision ASME B18.1.1	Visual ASTM F812
Sample Inspection	29.11	1,130	60,100	Pass	Pass	Pass


Heat No	Grade	Manufacturer	Origin	C	Mn	P	S	Si	Cr	Ni	Cu
62150514	1046	Corus Americas	USA	0.4800	0.7200	0.014	0.0140	0.2300	0.1700	0.0800	0.2300

All tests are in accordance with the latest revisions of the methods prescribed in the applicable SAE and ASTM Specifications.

The samples tested conform the specifications as described/listed above and were manufactured free of mercury contamination and there is no welding performed in the production of the products. No heats to which Bismuth, Selenium, Tellurium, or Lead was intentionally added have been used to produce products.

The steel was melted and manufactured in the U.S.A. and the product was manufactured and tested in the U.S.A.

We certify that this data is true representation of information provided by the material supplier and our testing laboratory. This certified material test report relates only to the items listed on this document and may not be reproduced except in full.



*Chris Thorsen*


11/28/18


Thorsen, Chris - Supervisor, Quality

Date

Plot 11/28/18 3:02 PM cthorsen Page 1

R12790

 <p><b>GERDAU</b></p> <p>US - ST PAUL 1678 RED ROCK ROAD SAINT PAUL, MN 55119 USA</p>	<p><b>CUSTOMER SHIP TO</b> UNYHITE INC LASALLE PLANT 325 CIVIC ROAD LA SALLE, IL 61301 USA</p>	<p><b>CUSTOMER BILL TO</b> UNYHITE INC 1 UNYHITE DR PERU, IL 61354-9710 USA</p>	<p><b>GRADE</b> 1045M23R22N</p>	<p><b>SHAPE / SIZE</b> Round Bar / 1"</p>	<p><b>DOCUMENT ID:</b> 000004265</p>																										
	<p><b>SALES ORDER</b> 78874600010</p>	<p><b>CUSTOMER MATERIAL N°</b> B104SSC1.0000 F</p>	<p><b>LENGTH</b> 25'01.50"</p>	<p><b>WEIGHT</b> 3,698 LB</p>	<p><b>HEAT / BATCH</b> 6219931403</p>																										
<p><b>CUSTOMER PURCHASE ORDER NUMBER</b> P00841R</p>		<p><b>BILL OF LADING</b> 1359-0100075325</p>	<p><b>DATE</b> 09/11/2019</p>		<p><b>SPECIFICATION / DATE OF REVISION</b> ASTM A329-16 ASTM A329-17</p>																										
<p><b>CHEMICAL COMPOSITION</b></p> <table border="1"> <thead> <tr> <th>C</th> <th>Mn</th> <th>P</th> <th>S</th> <th>Si</th> <th>Cr</th> <th>Ni</th> <th>Cu</th> <th>Nb</th> <th>Sp</th> <th>V</th> <th>Nb</th> <th>Al</th> </tr> </thead> <tbody> <tr> <td>0.45</td> <td>0.72</td> <td>0.014</td> <td>0.023</td> <td>0.33</td> <td>0.23</td> <td>0.08</td> <td>0.17</td> <td>0.020</td> <td>0.009</td> <td>0.032</td> <td>0.001</td> <td>0.005</td> </tr> </tbody> </table>						C	Mn	P	S	Si	Cr	Ni	Cu	Nb	Sp	V	Nb	Al	0.45	0.72	0.014	0.023	0.33	0.23	0.08	0.17	0.020	0.009	0.032	0.001	0.005
C	Mn	P	S	Si	Cr	Ni	Cu	Nb	Sp	V	Nb	Al																			
0.45	0.72	0.014	0.023	0.33	0.23	0.08	0.17	0.020	0.009	0.032	0.001	0.005																			
<p><b>HARDENABILITY</b> D<sub>1.25</sub> 131</p>																															
<p><b>COMMENTS / NOTES</b> Material 100% melted and rolled in the USA. Manufacturing processes for this steel, which may include scrap melted in an electric arc furnace and hot rolling, have been performed at Gerdau St. Paul Mill, 1678 Red Rock Road, Saint Paul, Minnesota, USA. All products produced from strand cast billets. Subject to 100% inspection test. No weld repairs performed. Steel not exposed to moisture or any liquid alloy which is liquid at ambient temperatures during processing or while in Gerdau St. Paul Mill possession. Any modification to this certification as provided by Gerdau St. Paul Mill without the expressed written consent of Gerdau St. Paul Mill negates the validity of this test report. This report shall not be reproduced except in full, without the expressed written consent of Gerdau St. Paul Mill. Gerdau St. Paul Mill is not responsible for the inability of this material to meet specific applications. Roll back: 6219931403 Roll date: 8/22/2019. Fire Chain (GG 3-8) Quality Program Manual Rev. 3, implemented date 7/13/2018</p>																															

*Debra L. Karsich*  


The above figures are certified chemical and physical test records as contained in the permanent records of company. We certify that these data are correct and in compliance with specified requirements. Weld repair has not been performed on this material. This material, including the billet, was melted and manufactured in the USA. CMTR complies with EN 10204 3.1.

*Anastasya* BRASKAS YALAMANGILI  
 QUALITY DIRECTOR  
 Phone: (609) 267-6073 Email: Anastasya.Yalamangili@gerdau.com

*Alex* ALEX BRANDENBURG  
 QUALITY ASSURANCE MGR  
 Phone: (631) 731-5662 Email: Alex.Brandenburg@gerdau.com



**CERTIFICATE OF COMPLIANCE**

**ROCKFORD BOLT & STEEL CO.  
126 MILL STREET  
ROCKFORD, IL 61101  
815-968-0514 FAX# 815-968-3111**

**CUSTOMER NAME:** AMERICAN TIMBER & STEEL

**CUSTOMER PO:** 21451

**SHIPPER #:** 068659  
**DATE SHIPPED:** 04/17/2020

**LOT#:** P39289 R73494  
**UNYTITE LOT:** 32205-75078628

**SPECIFICATION:** ASTM A563, GRADE DH HEAVY HEXAGONAL NUT

**COATING:** ASTM SPECIFICATION F2329 HOT DIP GALVANIZE  
**UNIVERSAL GALVANIZING:** 32205-75078628

**CHEMICAL COMPOSITION**

MILL	GRADE	HEAT#	C	Mn	P	S	Si
GERDAU	1045	75078628	.44	.74	.006	.029	.24

**HARDNESS:**

**SPEC:** 24-38  
**ACTUAL:** 28.37

**QUANTITY AND DESCRIPTION:**

850 PCS 3/4" HEAVY HEXAGONAL NUT

WE HEREBY CERTIFY THE ABOVE PARTS HAVE BEEN MANUFACTURED IN THE U.S.A. WITH DOMESTIC STEEL. WE FURTHER CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER, AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY ASSURE THAT ALL ITEMS FURNISHED ON THIS ORDER MEET OR EXCEED ALL APPLICABLE TESTS, PROCESS, AND INSPECTION REQUIREMENTS PER ABOVE SPECIFICATION.



Unytite, Inc.  
 One Unytite Drive  
 Peru, IL 61354  
 USA  
 Tel 815-224-2221  
 Fax 815-224-3434

**Customer Shipper**

Bill/Ship To: Rockford Bolt and Steel Co.  
 126 Mill St.  
 Rockford, IL 61101  
 Buyer: Rockford Bolt and Steel Co.

**Shipper No: 72877**



Ship Date: 4/13/20

Carrier: A & B / Dohm

Trailer No:

Shipping Tracking No: steel nuts

Freight Terms: Collect

Class or Rate: 50

Pallets: 3

Cust PO	Rel	Customer Part No	Rev	Part Name	Part No	Rev	Lot No.	Containers	Ship Qty	Net	Gross
P39289	2/20/20			ASTM A563 Heavy Hex Nut; Grade DH, Hot Dipped Galv, Blue Dye	A563 3/4-10+0.020 DH HHN HDG BLUE DYE		32205- 75078828 (27)	(27) Keg (Can w/ld)	27,000	4,860 lbs	4,957 lbs
<b>Total:</b>								27 Containers	27,000	4,860 lbs	4,957 lbs


Driver Signature

*R13194*

Packing Slip

Subject to Unytite Inc. Standard Terms and Conditions of Sale, Document Number 13-002, dated 08-09-06. Document is subject to change without notice.

Plex 4/13/20 11:32 AM plupperschmid Page 2



**UNYTITE INC.**  
**INNOVATIVE FASTENING SYSTEMS**

Unytite, Inc.  
 One Unytite Drive  
 Peru, IL 61354  
 Tel 815-224-2221  
 Fax 815-224-3434

**INSPECTION CERTIFICATE**

Job Information      Certified Date: 3/26/20

**Customer:** Rockford Bolt and Steel Co.      **Ship To:**  
**Customer Part No:**  
**Customer PO No:** P39289      **Shipped Qty:**  
**Lot Number:** 32205-75078628

Part Information

**Part No:** A563 3/4-10 +0.020 DH HHN HDG BLUE DYE  
**Description:** ASTM A563 Heavy Hex Nut, Grade DH, Hot Dipped Galv, Blue Dye  
**Manufactured Quantity:** 124,752

Table Specifications

Specification	Amend	Specification	Amend
ASME B1.1	2003	ASME B18.2.2	2015
ASME B18.2.6	2019	ASTM A563	2015
ASTM F2329/F2329M	2015	ASTM F606/606M	2019
ASTM F812	2017		

Test No: 21694 Test: A563 DH Mechanical Properties

Description	Hardness (HRC)	Tempering Temp (800 degree F Min)	Proof Load (Pass ASTM Min LBS)	Shape & Dimension ASME B18.2.2	Thread Precision ASME B18.1.1	Visual ASTM F812
Sample Inspection	28.37	1,040	50,100	Pass	Pass	Pass

Chemical Analysis

Heat No	Grade	Manufacturer	Origin	C	Mn	P	S	Si	Cr	Ni	Cu
75078628	1045	Genial Special Steel North America	USA	0.4406	0.7400	0.0060	0.0290	0.2400	0.1000	0.0600	0.1600

All tests are in accordance with the latest revisions of the methods prescribed in the applicable SAE and ASTM Specifications.  
 The samples tested conform the specifications as described/listed above and were manufactured free of mercury contamination and there is no welding performed in the production of the products. No heats to which Bismuth, Selenium, Tellurium, or Lead was intentionally added have been used to produce products.  
 The steel was melted and manufactured in the U.S.A. and the product was manufactured and tested in the U.S.A.  
 We certify that this data is true representation of information provided by the material supplier and our testing laboratory. This certified material test report relates only to the items listed on this document and may not be reproduced except in full.

      3/26/20  
 Thorsen, Chris - Supervisor, Quality      Date



GERDAU SPECIAL STEEL NORTH AMERICA  
 5581 MORRILL ROAD  
 JACKSON, MICHIGAN 48201 USA

**CERTIFIED MATERIAL TEST REPORT**

CUSTOMER ORDER NUMBER	CUSTOMER PART NUMBER	HEAT NUMBER	WORK ORDER NUMBER	DATE
P008846	B10458C1.0000	75078628	334801 101	1/28/20

240mm Bloom

REPORT TO

SHIP TO

UNYTITE INC  
 ONE UNYTITE DRIVE

UNYTITE, INC  
 LASALLE PLANT

PERU , IL 61354-9710

325 CIVIC RD  
 LASALLE , IL 61301

**ORDERED**

GRADE	SIZE	LENGTH
1045	1" RND	24' 10 1/2"

CUSTOMER SPECIFICATIONS  
 SAB 1045; ASTM E381-17; RMS 021 REV 3 DATED 09/17/19

BACK 1 1 1

DECARB SPECIFICATION ASTM E1077 RMS 021 REV 3

F TOTAL= 0.009

REDUCTION RATIO SPECIFICATION RMS 021 REV 3

RATIO= 113.7 TO 1.0

RESIDUAL MAX SPECIFICATION RMS 021 REV 3

Ni+Cr = 0.1630

\*\* MATERIAL 100% MELTED AND MANUFACTURED IN THE U.S.A. BY THE ELECTRIC ARC FURNACE AND CONTINUOUS CASTING METHOD. THE PRODUCT HAS NOT BEEN REPAIRED BY WELDING AND THIS MATERIAL HAS NOT BEEN EXPOSED TO MERCURY OR TO ANY OTHER METAL ALLOY THAT IS LIQUID AT AMBIENT TEMPERATURES DURING PROCESSING OR WHILE IN OUR POSSESSION. GERDAU MONITORS ALL INCOMING SCRAP AND ALL HEATS OF STEEL TO ENSURE THAT PRODUCTS SHIPPED ARE FREE OF RADIOACTIVE MATERIAL. MATERIAL IS 100% RECYCLABLE.

PAGE 2 OF 2

We certify that these data are correct and in compliance with specified requirements.

Gerdau Monroe  
 3000 East Front Street  
 Monroe, MI 48181

*Patrick Doyle*  
 Patrick Doyle  
 Pat.Doyle@Gerdau.com  
 Quality Assurance R#

Invoice No. 929064  
 Bill of Lading 358705  
 Customer No. 4429  
 Customer P.O. 116882

NUCOR-YAMATO STEEL CO.  
 P.O. BOX 1228: BLYTHEVILLE, AR 72316

**CERTIFIED MILL TEST REPORT**  
**100% Melted and Manufactured in U.S.A**  
 All Shapes produced by Nucor-Yamato Steel are cast and rolled to a fully killed and fine grain practice

Date 2018-12-11

CONTRACTORS STEEL CO  
 36555 AMRHEIN RD.  
 LIVONIA MI 48150  
 USA

CONTRACTORS STEEL COMPANY  
 48649 SCHOONER DR.  
 BELLEVILLE MI 48111  
 USA

ASTM A992/A992M-11 A572/A572M GR50-15  
 ASTM A709/A709M-15 GR50 (345)  
 ASTM A709/A709M-15 GR50S (345S)  
 CSA G40.21-13 50WM (345WM)  
 ASTM A6/A6M-14

Item#	Item Description	Qty	Heat#	Mechanical Properties							Chemical Properties																	
				Yield to Tensile Ratio	Yield Strength		Tensile Strength		ELONG %	Charpy Impact			C	Mn	P	S	Si	Cu	Ni	Cr	Mo	V	Cb	CE	Sn	Pcm	Cl	
					KSI	MPa	KSI	MPa		Temp ° F	Impact Energy ft-lbf	Loc																Temp ° C
1	W27X161.0 50 ft 0 in W690X240 (15.24 m)	1	499022	0.79 0.79	56 56 383 386	71 71 487 490	28 27								.08	1.11	.013	.027	.20	.31	.13	.16	.04	.01	.021	.34	.01	.17
2	W30X173.0 50 ft 0 in W760X257 (15.24 m)	1	481990	0.78 0.78	54 55 375 382	70 71 482 490	28 28								.08	1.10	.008	.021	.22	.26	.09	.09	.02	.01	.025	.31	.01	.16

ELONGATION BASED ON 8.00 INCH GAUGE LENGTH  
 $P_{cm} = C + S/30 + Mn/20 + Cu/20 + Ni/60 + Cr/20 + Mo/15 + V/10 + Sb(8 - Approx. .0005)$   
 Corrosion Index =  $26.01(\%Cu) + 3.88(\%Ni) + 1.2(\%Cr) + 1.49(\%S) + 17.28(\%P) - 7.29(\%Cu)(\%Ni) - 9.10(\%Ni)(\%P) - 33.39(\%Cu)^2$   
 ISO 9001:2015 certified (Registration # 0985-07).  
 All mechanical testing is performed by the Quality Testing Lab, which is independent of the production departments.  
 The Charpy machine striker geometry used by Nucor-Yamato Steel is the 8 mm (0.315") striker (KV<sub>g</sub>) per ASTM A370 Section 22.1.2 and ISO 148-1 Section 7.3.

CARBON EQUIVALENT CE =  $C + Mn/6 + (Cr + Mo + V)/5 + (Ni + Cu)/15$   
 Mercury has not been used in the direct manufacturing of this material.  
 This material was produced in accordance with the Nucor-Yamato Steel Quality Manual.

I hereby certify that the contents of this report are accurate and correct. All test results and operations performed by this material manufacturer are in compliance with the requirements of the material specifications, and when designated by the purchaser, meet the applicable specifications.

*Raymond*  
 Chief Metallurgist

State of Arkansas  
 County of Mississippi  
 Sworn to and subscribed before me  
 on 2018-12-11  
 My commission expires on 07/17/2023



**OLYMPIC STEEL**  
5080 RICHMOND ROAD  
BEDFORD HEIGHTS, OH 44146 USA  
PHONE: 216-292-3800

## METALLURGICAL TEST REPORT

>>>>> CERTIFICATE OF ANALYSIS AND TESTS <<<<<<

Sold To: AMERICAN TIMBER AND STEEL  
4832 PLANK RD.  
NORWALK, OH 44857

Ship To: AMERICAN TIMBER AND STEEL  
4832 PLANK RD.  
NORWALK, OH 44857

Sales Order: 614083 - 01      B/L No: 983730      Release: 2      Date: 20-May-2020  
Reference: FORRAI, HALLIE (11855) 2nd B/L:      Cus Ord #: 21885  
Cus Name: AMERICAN TIMBER AND STEEL

### Description of Material and Specification

Hot Rolled Sheet A606/606  
.375IN x 48IN x 192IN

TAG#: 27719329

HEAT#: 32016780/STEEL DYNAMICS, INC. - FLAT ROLLED

MC # 27699054

MS # 20B528734

### Chem Elem Symbol / Elem Content Value:

<C : .05> <MN : .86> <P : .02> <S : .001> <SI : .45> <AL : .035> <V : .031> <CB : .002> <CU : .33> <NI : .16>  
<CR : .43> <MO : .02> <N : .009> <TI : .001> <B : 0> <CA : .002> <ZR : .0008> <PB : 0> <SN : .006>

YIELD STRENGTH	MIN:	60800	PSI	MAX	60800	PSI
TENSILE STRENGTH	MIN:	76100	PSI	MAX	76100	PSI
ELONGATION 2"	MIN:	34	%	MAX	34	%

We hereby certify the above is correct as contained in the records of the corporation



Branch Certification Manager

USER: REPORTS@SEMSP01  
REPORT: ST\_MSR\_OSI

20-May-2020 4:44 AM  
Page 1 of 2

# Birmingham Fastener Manufacturing

P.O. Box 10323  
Birmingham, Alabama 35202  
(205) 595-3512

Pg 1 of 1

## Certificate of Compliance

Customer : AMERICAN TIMBER  
P.O. # : 19191

BFM # : 1579744  
Date Shipped : 5/10/2019

Item	Quantity	Description	Lot #	Heat #	Specification	Finish
1	519	5/8"-11 x 12" Carriage Bolt	92212	DL18104710	ASTM A242	Plain

*Birmingham Fastener Manufacturing. hereby certifies that the material furnished in reference to the above purchase order number will meet or exceed the above assigned specifications.*

Signed:  Date: 06/05/2020  
Cody Calvert



**NUCOR**  
**NUCOR CORPORATION**  
**NUCOR STEEL SOUTH CAROLINA**

**Mill Certification**  
**4/23/2019**

MTR #: C1-466062  
 300 Steel Mill Road  
 DARLINGTON, SC 29540  
 (843) 393-6841  
 Fax: (843) 395-8701

Sold To: BIRMINGHAM FASTENER & SUPPLY  
 PO BOX 10323  
 BIRMINGHAM, AL 35202-0323  
 (205) 595-3511  
 Fax: (205) 591-0244

Ship To: BIRMINGHAM FASTENER & SUPPLY  
 931 AVE W  
 PO BOX 10323  
 BIRMINGHAM, AL 35202  
 (205) 595-3511  
 Fax: (205) 591-0244

Customer P.O.	6179624	Sales Order	301893.7
Product Group	Merchant Bar Quality	Part Number	30000563480DEQ0
Grade	A242BF - ASTM A242-03	Lot #	DL1810471001
Size	9/16" (.5625) Round	Heat #	DL18104710
Product	9/16" (.5625) Round 40' A242BF	B.L. Number	C1-784101
Description	A242BF	Load Number	C1-466062
Customer Spec		Customer Part #	

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.

Roll Date: 7/19/2018 Melt Date: 7/15/2018 Qty Shipped LBS: 7,208 Qty Shipped Pcs: 213

Melt Date: 7/15/2018


C	Mn	V	Si	S	P	Cu	Cr	Ni	Mo	Cb
0.15%	0.90%	0.0120%	0.18%	0.028%	0.014%	0.32%	0.79%	0.26%	0.026%	0.003%

Roll Date: 7/19/2018

Yield 1: 52,000psi	Tensile 1: 82,000psi	Elongation: 23% in 8"(% in 203.3mm)
Elongation: 35% in 2"(% in 50.8mm)	Yield 2: 52,000psi	Tensile 2: 83,000psi
Elongation 22% in 8"(% in 203.3mm)	Elongation: 34% in 2"(% in 50.8mm) - test2	

Specification Comments:

1. WELDING OR WELD REPAIR WAS NOT PERFORMED ON THIS MATERIAL
2. MELTED AND MANUFACTURED IN THE USA
3. MERCURY, RADIUM, OR ALPHA SOURCE MATERIALS IN ANY FORM HAVE NOT BEEN USED IN THE PRODUCTION OF THIS MATERIAL



James H. Blew  
 Division Metallurgist

# Birmingham Fastener Manufacturing

P.O. Box 10323  
Birmingham, Alabama 35202  
(205) 595-3512

Pg 1 of 1

## Certificate of Compliance

Customer : AMERICAN TIMBER  
P.O. # : 20512

BFM # : 1628407  
Date Shipped : 9/30/2019

Item	Quantity	Description	Lot #	Heat #	Specification	Finish
1	869	3/4"-10 x 8 1/2" Carriage Bolt	86911	10592090	AWWAC111	Plain
4	10,545	5/8"-11 x 4" Hex Lag Screw	32361	10575880	AWWAC111	Plain

*Birmingham Fastener Manufacturing. hereby certifies that the material furnished in reference to the above purchase order number will meet or exceed the above assigned specifications.*

Signed:  Date: 11/04/2019  
Brian Hughes

**CERTIFICATE OF COMPLIANCE**

**ROCKFORD BOLT & STEEL CO.  
128 MILL STREET  
ROCKFORD, IL 61101  
815-968-0514 FAX# 815-968-3111**

**CUSTOMER NAME:** BIRMINGHAM FASTENERS COMPANY

**CUSTOMER PO:** 6221129

**SHIPPER #:** 067290  
**DATE SHIPPED:** 09/23/2019

**LOT#:** 32361

**SPECIFICATION:** ASTM A307, GRADE A STEEL BOLTS, MADE WITH ASTM A242 WEATHERING STEEL

**COATING:** N/A

**CHEMICAL COMPOSITION**

MILL	GRADE	HEAT#	C	Mn	P	S	Si	Cu	Ni	Cr
NUCOR	A242	10575880	.07	.55	.010	.014	.200	.28	.32	.73

**QUANTITY AND DESCRIPTION:**

14,924 PCS 5/8" X 4" HEXAGONAL HEADED LAG BOLT

WE HEREBY CERTIFY THE ABOVE BOLTS HAVE BEEN MANUFACTURED BY ROCKFORD BOLT AND STEEL IN ROCKFORD, ILLINOIS. THE MATERIAL USED WAS MELTED AND MANUFACTURED IN THE U.S.A. WE FURTHER CERTIFY THAT THIS DATA IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER, AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY ASSURE THAT ALL ITEMS FURNISHED ON THIS ORDER MEET OR EXCEED ALL APPLICABLE TESTS, PROCESS, AND INSPECTION REQUIREMENTS PER ABOVE SPECIFICATIONS.

STATE OF ILLINOIS  
COUNTY OF WINNEBAGO  
SIGNED BEFORE ME ON THIS

4<sup>th</sup> DAY OF November, 2019  
Merry F. Shane

Dinda Melomas  
APPROVED SIGNATORY

11/4/19  
DATE





**CHARTER  
STEEL**

A Division of  
Charter Manufacturing Company, Inc.

EMAIL

1658 Cold Springs Road  
Saukville, Wisconsin 53080  
(262) 268-2400  
1-800-437-8789  
Fax (262) 268-2570

**CHARTER STEEL TEST REPORT**

Melted in USA Manufactured in USA

**Rockford Bolt & Steel**  
126 Mill St.  
Rockford, IL-61101  
Kind Attn :Linda McComas

Cust P.O.	P38510
Customer Part #	100110
Charter Sales Order	70088529
Heat #	10575880
Ship Lot #	4553057
Grade	A242 M SK FG IQ 19/32 RNDCOIL
Process	HRC2
Finish Size	19/32
Ship date	02-OCT-18

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed below and that it satisfies these requirements. The recording of false, fictitious and fraudulent statements or entries on this document may be punishable as a felony under federal statute.

Test results of Heat Lot # 10575880

Lab Code: 7388  
CHEM  
%WI

	C	MN	P	S	SI	NI	CR	MO	CU	SN	V
%WI	.07	.55	.010	.014	.200	.32	.73	.03	.28	.007	.004
	AL	N	B	TI	NB						
	.027	.0080	.0002	.001	.001						

Test results of Rolling Lot # 1263603

REDUCTION RATIO=109:1

Specifications:

Manufactured per Charter Steel Quality Manual Rev Date 05/12/17  
Charter Steel certifies this product is indistinguishable from background radiation levels by having process radiation detectors in place to measure for the presence of radiation within our process & products.  
Meets customer specifications with any applicable Charter Steel exceptions for the following customer documents:  
Customer Document = ASTM A242/A242M -13 Revision = Dated = 01-MAY-13

Additional Comments:

Melt Source:  
Charter Steel  
Saukville, WI, USA

Trip: 1311283



This MTR supersedes all previously dated MTRs for this order

*Janice Barnard*  
Janice Barnard Division Mgr. of Quality Assurance  
barnardj@chartersteel.com  
Printed Date : 10/02/2018

The following statements are applicable to the material described on the front of this Test Report:

1. Except as noted, the steel supplied for this order was melted, rolled, and processed in the United States meeting DFARS compliance, LEEDS compliance, REACH compliance, ROHS-WEEE compliance, and Conflict Materials Restrictions.
2. Mercury was not used during the manufacture of this product, nor was the steel contaminated with mercury during processing.
3. Unless directed by the customer, there are no welds in any of the coils produced for this order.
4. The laboratory that generated the analytical or test results can be identified by the following key:

Certificate Number	Lab Code	Laboratory	Address
0358-01	7388	CSSM Charter Steel Melting Division	1658 Cold Springs Road, Saukville, WI 53080
0358-02	8171	CSSR/CSSP Charter Steel Rolling/ Processing Division	1658 Cold Springs Road, Saukville, WI 53080
0358-03	123833	CSFP Charter Steel Ohio Processing Division	6255 US Highway 23, Rising Sun, OH 43457
0358-04	125544	CSCM/CSCR Charter Steel Cleveland	4300 E. 49th St., Cuyahoga Heights, OH 44125-1004
*	*	--	Subcontracted test performed by laboratory not in Charter Steel System

5. When run by a Charter Steel laboratory, the following tests were performed according to the latest revisions of the specifications listed below, as noted in the Charter Steel Laboratory Quality Manual:

Test	Specifications	CSSM	CSSR/CSSP	CSFP	CSCM/CSCR
Chemistry Analysis	ASTM E415; ASTM E1019	X			X
Macroetch	ASTM E381	X			X
Hardenability (Jominy)	ASTM A255; SAE J406; JIS G0561	X			X
Grain Size	ASTM E112	X	X	X	X
Tensile Test	ASTM E8; ASTM A370		X	X	X
Rockwell Hardness	ASTM E18; ASTM A370	X	X	X	X
Microstructure (spheroidization)	ASTM A892		X	X	
Inclusion Content (Methods A, E)	ASTM E45		X		X
Decarburization	ASTM E1077		X	X	X

Charter Steel has been accredited to perform all of the above tests by the American Association for Laboratory Accreditation (A2LA). These accreditations expire 01/31/19. All other test results associated with a Charter Steel laboratory that appear on the front of this report, if any, were performed according to documented procedures developed by Charter Steel and are not accredited by A2LA.

6. The test results on the front of this report are the true values measured on the samples taken from the production lot. They do not apply to any other sample.
7. This test report cannot be reproduced or distributed except in full without the written permission of Charter Steel. The primary customer whose name and address appear on the front of this form may reproduce this test report subject to the following restrictions:
  - It may be distributed only to their customers
  - Both sides of all pages must be reproduced in full
8. This certification is given subject to the terms and conditions of sale provided in Charter Steel's acknowledgement (designated by our Sales Order number) to the customer's purchase order. Both order numbers appear on the front page of this Report.
9. Where the customer has provided a specification, the results on the front of this test report conform to that specification unless otherwise noted on this test report.



TR No. 612061-08-01

177

2024-02-06

INSPECTION CERTIFICATE

ROCKFORD BOLT AND STEEL CO.  
126 MILL STREET  
ROCKFORD, IL 61101  
815-968-0514 FAX: 815-968-3111

LOT# 32688

Batch Qty: 15,651  
Sample Qty: 3  
Date of Manufacture: 02/11/2020

SPECIFICATION: ASTM A325 2014, Specification For Structural Bolts  
Head markings: "A325 and "01AE"  
ASTM A153, Class C Hot Dip Galvanization

DESCRIPTION: 5/8" -11 x 4" Heavy Hexagonal Lag Bolt.

QUANTITY: 15,648

MECHANICAL PROPERTIES

	TENSILE	PROOF LOAD	HARDNESS
SPEC.:	120,000 psi	85,000 psi	HRC 34 MAX
ACTUAL:	133,200 psi	85,100 psi	27.40
	137,900 psi	85,100 psi	28.25
	135,900 psi	85,100 psi	27.73

THESE PARTS CONFORM TO ABOVE SPECIFICATIONS.

Tension Testing: ASTM F606  
Proof Load Testing: ASTM F606  
Hardness Testing: ASTM F606

WE HEREBY CERTIFY THE ABOVE BOLTS HAVE BEEN MANUFACTURED BY ROCKFORD BOLT & STEEL IN OUR FACILITY IN ROCKFORD, ILLINOIS WITH MATERIAL WHICH WAS MELTED AND MANUFACTURED IN U.S.A. WE FURTHER CERTIFY THAT THIS IS A TRUE REPRESENTATION OF INFORMATION PROVIDED BY THE MATERIALS SUPPLIER AND THAT OUR PROCEDURES FOR THE CONTROL OF PRODUCT QUALITY MEET OR EXCEED ALL APPLICABLE TEST, PROCESSES, AND INSPECTION REQUIREMENTS PER THE ABOVE SPECIFICATION. THIS REPORT MAY NOT BE REPRODUCED EXCEPT IN FULL, WITHOUT THE WRITTEN APPROVAL OF ROCKFORD BOLT. THE REPORT MUST NOT BE USED BY THE CLIENT TO CLAIM PRODUCT CERTIFICATION, APPROVAL, OR ENDORSEMENT BY NVLAP, NIST, OR ANY AGENCY OF THE U.S. GOVERNMENT.  
"THIS INFORMATION IS NOT COVERED BY ROCKFORD BOLT AND STEEL'S NVLAP ACCREDITATION."

PAGE 1 OF 1

THIS REPORT CONTAINS DATA THAT WAS PRODUCED UNDER THE FOLLOWING SUBCONTRACTORS:  
\*Raw Mate G3 (GRAND BLANC) -ISO 9001:2015 #C2019-00846  
Not ISO 17025 Accredited

CUSTOMER NAME: AMERICAN TIMBER & STEEL  
4832 PLANK ROAD; P.O. BOX 767; NORWALK, OH 44857

CUSTOMER PO#: 21451 SHIPPER#: 068659  
DATE SHIPPED: 04/17/2020

CHEMICAL COMPOSITION MILL CERT\*

HEAT # DL18105083

GRADE	C	Mn	P	S	SI
1045	X 100	X 100	X 1000	X 1000	x100
SPEC.	.43-.50	.60-.90	.040 max	.050 max	.15-.35
ACTUAL	.47	.68	.005	.014	.21

*Jeff Nave*  
APPROVED SIGNATORY DATE 4/28/2020



# PACKING LIST

Worth Steel and Machinery, Inc.  
 4001 W. 122nd St  
 Alsip, IL 60803  
 708-388-6300 Fax 708-388-6467  
 www.worthsteel.com

Shipper No: 12701

Ship Date: 04/22/19

Page: 1

Customer Phone: 248-524-0192

Customer Fax: 248-524-0406

<b>B</b> <b>I</b> <b>L</b> <b>L</b> G3 Steel Group 1465 Brown Road Orion, MI 48359-2267 USA ATTN: Ron Nowak	<b>S</b> <b>H</b> <b>I</b> <b>P</b> Rockford Bolt & Steel 125 Mill Street Rockford, IL 61101 USA ATTN: Ron Nowak
---	--

Sales Order No: 59922 Order Date: 04/15/19 Cust Code: 666923 Job Number:	Purchase Order: P04760 Ship Via: ID LOGISTICS FOB: ALSIP Salesperson:
---	--

Line	Description	Quantity	Unit	Weight
1	CUSTOMER MAT. .625" Diam. Hot Roll Rod 1045 x s/c 240" 2,483 pcs  Length Tolerance +1.00"/-.000"  8,000 lbs Max. Bundles  Oil Spray  11 Bundles		LB	45530

Total Weight	Freight	Date Filled
Total Cubic Ft	Insurance	Filled By



STRAIGHT BILL OF LADING - NOT NEGOTIABLE

**NUCOR**  
 NUCOR CORPORATION  
 NUCOR STEEL SOUTH CAROLINA

Nucor Steel - South Carolina  
 300 Steel Mill Road  
 DARTINGTON, SC 29840  
 843-393-5841

Page: 1 of 2

Bill of Lading No.:  
 782750 Rev 0

PICKED: 04-08-2019 1:54 PM  
 PRINT: 8-Apr-2019 4:11 PM  
 SHIP: 04-08-2019 4:10 PM

SOLD TO: 000

SHIP TO: 505

G3 STEEL GROUP  
 ATTN: STEVE HASON  
 1465 BROWN ROAD  
 ORION, IL 60859--226  
 (708) 524-0192

Worth Steel & Machinery  
 4001 W. 123rd St  
 Alsip, IL 60803

Subject to section 7 of the terms and conditions of the Bill of Lading. If this statement is to be converted to the complete bill of lading, recipient on the carrier, the consignee and shipper shall sign the following statement:  
 The carrier may require to make payment of this amount without payment of freight and all other lawful charges.

Freight Mode: Truck

CUSTOMER NO.	CUSTOMER ORDER NUMBER	OUR ORDER NUMBER	SHIPPER NUMBER	TERMS
15159	See Below	See Below	C1-484227	Collect
SHIP VIA		VEHICLE NUMBER	ROUTING	
Nucor CPU Carrier		NGCB NOVA LINE		
SPECIAL INSTRUCTIONS THIS SHIPMENT IS SUBJECT TO THE TERMS AND CONDITIONS OF THE BILL OF LADING AND THE CARRIER'S TARIFFS. NO CHARGES WILL BE INCURRED FOR THIS SHIPMENT. THE CARRIER MAY REQUIRE TO MAKE PAYMENT OF THIS AMOUNT WITHOUT PAYMENT OF FREIGHT AND ALL OTHER LAWFUL CHARGES.				
34	5/8" (1.6250) Wire Rod Coil 1045CP			46,772
Tag# 1	DL1913027573	Lot #1: DL1913027573	Pieces: 1	3,824
Tag# 2	DL1913027574	Lot #2: DL1913027574	Pieces: 1	4,284
Tag# 3	DL1913027575	Lot #3: DL1913027575	Pieces: 1	4,284
Tag# 4	DL1913027576	Lot #4: DL1913027576	Pieces: 1	4,308
Tag# 5	DL1913027578	Lot #5: DL1913027578	Pieces: 1	4,259
Tag# 6	DL1913027579	Lot #6: DL1913027579	Pieces: 1	4,296
Tag# 7	DL1913027580	Lot #7: DL1913027580	Pieces: 1	4,296
Tag# 8	DL1913027581	Lot #8: DL1913027581	Pieces: 1	4,282
Tag# 9	DL1913027582	Lot #9: DL1913027582	Pieces: 1	4,282
Tag# 10	DL1913027583	Lot #10: DL1913027583	Pieces: 1	4,309
5/8" (1.6250) Wire Rod Coil 1045CP - Continued			3200025900DKA	

Carrier Name: Nucor CPU Carrier  
 RECEIVED, subject to the terms and conditions of this Bill of Lading  
 04-08-2019 4:10 PM

Carrier's No: NGCB NOVA LINE

If the shipment moves between two ports by a carrier by water, this law requires that the bill of lading shall state whether it is "net weight" or "gross weight".

The property described above is apparent good order, except as noted hereon and condition of contents is package, unopened, marked, compressed, and delivered as indicated above, which said former (the word "owner" being understood throughout this contract as meaning any person or corporation) is responsible at the receipt of the property unless the contract specifies in writing to the contrary. It is the responsibility of the shipper to deliver to another carrier or to the consignee in good condition. If a mutually agreed time period is provided, the carrier shall be subject to all the terms and conditions of the bill of lading. THIS BILL OF LADING IS NOT SUBJECT TO ANY CLASSIFICATION TARIFFS, WHETHER INDIVIDUALLY DETERMINED OR FILED WITH ANY FEDERAL OR STATE REGULATORY AGENCY, EXCEPT AS SPECIFICALLY AGREED TO IN WRITING BY THE SHIPPER AND CARRIER.

The spread-on declared value of the property is hereby specifically related by the shipper to be not necessary.

Carrier Certification:  
 Carrier acknowledges receipt of the property described above in good order and condition.  
 Per: *[Signature]*

Shipper hereby certifies that he is familiar with all the terms and conditions of this bill of lading, including those on the back hereof, and the said terms and conditions, any transfer accepted by the shipper and accepted for "bill" and "no" weights.

STRAIGHT BILL OF LADING - NOT NEGOTIABLE

**NUCOR**  
 NUCOR CORPORATION  
 NUCOR STEEL SOUTH CAROLINA

Nucor Steel - South Carolina  
 300 Steel Mill Road  
 DARLINGTON, SC 29540  
 843-353-5841

Page: 2 of 2

Bill of Lading No.  
 782750 Rev 0

PICKED: 04-08-2019 1:54 PM  
 PRINT: 8-Apr-2019 4:11 PM  
 SHIP: 04-08-2019 4:10 PM

SOLD TO: 000

63 STEEL GROUP  
 ATTN STEVE MASON  
 1465 BROWN ROAD  
 ORION, MI 48359--226  
 (248) 524-0192

SHIP TO: 505

Worth Steel & Machinery  
 4001 W. 123rd St  
 Alsip, IL 60803

Subject to section 7 of the terms and conditions of this bill of lading, if this shipment is to be delivered to the consignee without recourse on the carrier, the consignee shall sign the following statement:  
 The carrier may decline to make delivery on this shipment without receipt of freight and all other bills due.

Freight Mode: Truck

CUSTOMER NO.	CUSTOMER ORDER NUMBER	OUR ORDER NUMBER	SHIPPER NUMBER	TERMS	TARE	
10100	See Below	See Below	G1-464227	Collect	(Signature of Consignor)	
SHIP VIA		VEHICLE NUMBER	ROUTING		Freight Collect or PREPAID (initials required)	
Nucor CPU Carrier		NOCB NOVA LINE			CARRIER'S COLLECTOR	
<p>Our Order Number: 20854971                  Customer PO# : 000 32760                  Ship # : 001513027500</p> <p>Net # : 001510506305                  Gross # : 001510506302</p> <p>Place# : 1      4,258</p>						
Total Tare: 11      Total Pieces: 11      46,771						

Name of Carrier: Nucor CPU Carrier  
 RECEIVED: subject to the terms and conditions of this bill of lading  
 04-08-2019 4:10 PM

Carrier: NOCB NOVA LINE

The property described above is apparent good order, except as noted, contents and condition of contents of packages unknown, marked, assigned, and delivered as indicated above, which said carrier (the word carrier being understood throughout this contract as meaning any person or corporation in possession of the property under the contract) agrees to carry to its usual place of delivery at said destination, if on its route, subject to delivery to another carrier as may be required. It is mutually agreed that when delivery is to be performed hereunder that by whether individually determined or filed with any FEDERAL OR STATE REGULATORY AGENCY EXCEPT AS SPECIFICALLY AGREED TO IN WRITING BY THE SHIPPER AND CARRIER.

If the shipment moves between two ports by a carrier by water, the law requires that the bill of lading shall state whether it is "carrier's weight" or "shipper's weight".

The agreed-on declared value of the property is hereby specifically stated by the shipper to be not exceeding

Carrier Certification  
 Carrier acknowledges receipt of the property described above in good order and condition.  
 Per: *[Signature]*

Shipper hereby certifies that he is familiar with all the terms and conditions of this bill of lading, including those on the back hereof, and that he will accept and comply with the same as stated by the shipper and accepted for said and the weight.

**NUCOR**  
**NUCOR CORPORATION**  
**NUCOR STEEL SOUTH CAROLINA**

Mill Certification  
 4/8/2018

2018 04 08  
 10:56 AM  
 DARLINGTON, SC 29540  
 (843) 393-5671  
 Fax: (843) 398-8701

Ship To: 33 STEEL GROUP  
 ATTN: STEVE MASON  
 485 BROWN ROAD  
 CRION MI 48358-228  
 (248) 524-0192  
 Fax: (248) 524-0468

Ship To: 33 STEEL GROUP  
 485 BROWN RD  
 CRION MI 48358 US

Customer P.O.	IKE 38760	Sales Order	308549.1
Product Group	Rod	Part Number	32000625000DYAA
Grade	1045	Lot #	DL1810506303
Size	5/8" (6250) Wire Rod	Heat #	DL18105063
Product	5/8" (6250) Wire Rod Coil 1045CGP	B.L. Number	C1-782750
Description	1045CGP	Load Number	C1-484227
Customer Spec		Customer Part #	

I hereby certify that the material described herein has been manufactured in accordance with the specifications and standards listed above and that it satisfies those requirements.

Roll Date: 3/14/2018 Melt Date: 7/31/2018 Qty Shipped LBS: 48,774 Qty Shipped Pcs: 11

Melt Date: 7/31/2018

C	Mn	P	S	Si	V	Ni	Cr	Mo	Cu	Sn	Pb
0.47%	0.88%	0.005%	0.004%	0.24%	0.0040%	0.08%	0.07%	0.017%	0.14%	0.005%	0.004%
Al	B	N	CRNCMO								
0.002%	0.0005%	0.0050%	0.010%								

CRNCMO: Cr + Ni + Cu + Mo

Roll Date: 3/14/2018

Min Tensile: 110000psi

Max Tensile: 110000psi

Average Tensile: 110000psi

Reduction of Area: 42%


Specification Comments:

1. WELDING OR WELD REPAIR WAS NOT PERFORMED ON THIS MATERIAL.
2. MELTED AND MANUFACTURED IN THE USA.
3. MERCURY, RADIUM, OR ALPHA SOURCE MATERIALS IN ANY FORM HAVE NOT BEEN USED IN THE PRODUCTION OF THIS MATERIAL.

*John H. Allen*

James H. Allen  
 Nucor Metallurgy

Page 1 of 1

 <p><b>Texas A&amp;M Transportation Institute</b></p> <p><small>Proving Ground 3100 SH 47, Bldg. 7091 Bryan, TX 77807</small></p>	<p><b>QF-7.3-01-Concrete Sampling</b></p>	<p>Doc. No. <input type="text" value="QF-7.3-01"/></p>	<p>Issue Date: <input type="text" value="2018-06-18"/></p>
<p><b>Quality Form</b></p>	<p>Prepared by: <input type="text" value="Wanda L. Menges"/></p> <p>Approved by: <input type="text" value="Darrell L. Kuhn"/></p>	<p>Revision: <input type="text" value="6"/></p>	<p>Page: <input type="text" value="1 of 1"/></p>

[The information contained in this document is confidential to TTI Proving Ground.]

**Project No:** 612061-3 and 4     **Casting Date:** 4/30/2020     **Mix Design (psi):** 4000 psi

Name of Technician Taking Sample _____ Signature of Technician Taking Sample _____	Name of Technician Breaking Sample _____ Signature of Technician Breaking Sample _____
<u>Teracon</u>	<u>Teracon</u>
<u>Teracon</u>	<u>Teracon</u>

Load No.	Truck No.	Ticket No.	Location (from concrete map)
T1	8162	6038645	100% of deck

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
See attached Reports from Terracon					

CUSTOMER'S COPY

TICKET NO.



# Martin Marietta

1503 LBJ Freeway  
Suite 400  
Dallas, Tx 75234

6038645



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
10:55	:	:	:	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST \_\_\_\_\_ GAL.  
 ALLOWABLE WATER (withheld from batch) \_\_\_\_\_ GAL.  
 TEST CYLINDER TAKEN  YES  NO BY \_\_\_\_\_  
 CYLINDER TAKEN  BEFORE  AFTER WATER

CUSTOMER SIGNATURE

X

DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE.

**ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.**

CUSTOMER NAME AND DELIVERY ADDRESS

BRYAN CONSTRUCTION CO  
RELLIS CAMPUS TTI, CO

PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
817	8162	2047	5.0	830	

DRIVER NAME	DATE
ANDRA DARNELL	4/30/20

CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY
509195	89128	5.00	5.00

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
5.00	CYDS	892406252 CON, RG, 2, 4000, RE		

SPECIAL DELIVERY INSTRUCTIONS

SOUTH 2818, RIGHT LEDNARD RD, RIGHT ON HWY 47, LEFT INTO RELIS STRAIGHT TO GATE AND THEY WILL MEET YOU

SALES TAX

TOTAL

**DANGER!** MAY CAUSE ALKALI BURNS. SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY **FORM:**

Truck	Driver	User	Slump	Ticket Num	Ticket ID	Time	Date
8162	746154	user		6038645	82783	10:55	4/30/20
Load Size	Mix Code	Returned	Qtz	Mix Age	Seq	Load ID	
5.00	CYDS R9740625				D	83864	

Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat
1"BS	1383 lb	6541 lb	6540 lb	-0.02%	0.40% M	3 gal
3/8"OG	586 lb	2540 lb	2520 lb	-0.79%	0.40% M	1 gal
SAND-1	1483 lb	7346 lb	7360 lb	0.20%	4.50% M	40 gal
CMT-I/II	394 lb	1970 lb	1950 lb	-1.02%		
FLYASH-C	131 lb	650 lb	650 lb	0.76%		
H2O	250 lb	750 lb	744 lb	-1.84%		89 gal
IV-610	16 oz	99 oz	99 oz	0.51%		

Actual Num Batches: 1  
 Load Total: 19770 lb Design 0.476 Water/Cement 0.481 T Design 149.8 gal Actual 133.2 gal To Add: 11.6 gal  
 Slump: 5.00 in # Water in Truck: 5.0 gal Adjust Water: 0.0 gal / Load 1/4th Water: -2.0 gal / CYD



**CONCRETE COMPRESSIVE STRENGTH TEST REPORT**



Report Number: A1171057.0113  
Service Date: 04/30/20  
Report Date: 07/08/20 Revision 1 -  
Task: PO #612061

6198 Imperial Loop  
College Station, TX 77845-5765  
979-846-3767 Reg No: F-3272

**Client**

Texas Transportation Institute  
Attn: Gary Gerke  
TTI Business Office  
3135 TAMU  
College Station, TX 77843-3135

**Project**

Riverside Campus  
Riverside Campus  
Bryan, TX

Project Number: A1171057

**Material Information**

Specified Strength: 4,000 psi @ 28 days  
  
Mix ID: R9z40625  
Supplier: Martin Marrieta  
Batch Time: 1050 Plant: 617  
Truck No.: 8162 Ticket No.: 6038245

**Sample Information**

Sample Date: 04/30/20 Sample Time: 1145  
Sampled By: Matcek, James  
Weather Conditions: Sunny  
Accumulative Yards: 5.0 Batch Size (cy): 5  
Placement Method: Direct Discharge  
Water Added Before (gal): 0  
Water Added After (gal): 0  
Sample Location: Centerline  
Placement Location: Merritt Parkway

**Field Test Data**

Test	Result	Specification
Slump (in):	4 1/2	Not Specified
Air Content (%):	1.7	Not Specified
Concrete Temp. (F):	79	40 - 95
Ambient Temp. (F):	70	40 - 95
Plastic Unit Wt. (pcf):	150.2	Not Specified
Yield (Cu. Yds.):		

**Laboratory Test Data**

Set No.	Specimen ID	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Maximum Load (lbs)	Compressive Strength (psi)	Fracture Type	Tested By
1	A	6.01	28.37	05/01/20	06/01/20	32	136,210	4,800	3	SLS
1	B	6.01	28.37	05/01/20	06/01/20	32	142,080	5,010	1	SLS
1	C	6.01	28.37	05/01/20	06/01/20	32	138,130	4,870	2	SLS
							<b>Average (32 days)</b>	<b>4,890</b>		
1	D			05/01/20			Hold			

Initial Cure: Outside

Final Cure: Field Cured

Comments: Average compressive strength of 32 day cylinders complies with the specified strength.

**Samples Made By: Terracon**

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: Matcek, James

Start/Stop: 0945-1215

Reported To:

Contractor:

Report Distribution:

- (1) Texas Transportation Institute, Gary Gerke
- (1) Terracon Consultants, Inc., Alex Dunigan, P.E.
- (1) Texas Transportation Institute, Bill Griffith

Reviewed By:

Alexander Dunigan  
Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.





CUSTOMER'S COPY

TICKET NO.



# Martin Marietta

6080436

1503 LBJ Freeway  
Suite 400  
Dallas, Tx 75234



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
8:29	8:40	9:00	:	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST \_\_\_\_\_ GAL.  
 ALLOWABLE WATER (withheld from batch) \_\_\_\_\_ GAL.  
 TEST CYLINDER TAKEN  YES  NO BY \_\_\_\_\_  
 CYLINDER TAKEN  BEFORE  AFTER WATER

CUSTOMER SIGNATURE

X

DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE.

**ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.**

CUSTOMER NAME AND DELIVERY ADDRESS

BRYAN CONSTRUCTION C  
RELLIS CAMPUS/TTI, CO

PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
617	8120	2033	5.0	302-10-13	
DRIVER NAME					DATE
Jeremy Freeman					5/22/20
CUSTOMER NUMBER		PROJECT	CUM. QTY	ORDERED QTY	
509195		92332	4.00	4.00	

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
4.00	CYDS	R9Z40625 CDM, RG, Z, 4000, RE		

SPECIAL DELIVERY INSTRUCTIONS

SOUTH 2810, RIGHT LEONARD RD, RIGHT ON HWY 47, LEFT INTO RELIS STRAIGHT TO GATE AND THEY WILL MEET YOU.

SALES TAX

TOTAL

**DANGER!** MAY CAUSE ALKALI BURNS.  
SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY **FORM:**

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
8120	956950	user	6080436	83242		8:29	5/22/20
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
4.00	CYDS R9Z40625				D	84327	
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
1"RG	1383 lb	5220 lb	5260 lb	+ 0.62%	0.30% M	2 gl	
3/8"PS	586 lb	2030 lb	2000 lb	-1.47%	0.23% M	1 gl	
SAND-1	1403 lb	5052 lb	5000 lb	-0.48%	4.10% M	29 gl	
DWT-1/II	394 lb	1576 lb	1590 lb	0.89%			
FLYASH-C	131 lb	564 lb	525 lb	-0.19%			
HE0	250 lb	675 lb	668 lb	-1.05%		80 gl	
ZY-610	16 oz	79 oz	80 oz	1.32%			
Actual	Num Batches: 1						
Load Total: 15928 lb	Design 0.476	Water/Cement 0.473 T	Design 119.8 gl	Actual 111.5 gl	To Add: 8.3 gl		
Slump: 5.00 in	# Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	/ Load	Trim Water: -1.9 gl	CYD		

**CONCRETE COMPRESSIVE STRENGTH TEST REPORT**

Report Number: A1171057.0118  
 Service Date: 05/22/20  
 Report Date: 05/22/20  
 Task: PO #612061

**Terracon**  
 6198 Imperial Loop  
 College Station, TX 77845-5765  
 979-846-3767 Reg No: F-3272

**Client**

Texas Transportation Institute  
 Attn: Gary Gerke  
 TTI Business Office  
 3135 TAMU  
 College Station, TX 77843-3135

**Project**

Riverside Campus  
 Riverside Campus  
 Bryan, TX

Project Number: A1171057

**Material Information**

Specified Strength: 4,000 psi @ 28 days  
 Mix ID: R9Z40625  
 Supplier: Martin Marietta  
 Batch Time: 0829 Plant: 617  
 Truck No.: 8120 Ticket No.: 6080436

**Sample Information**

Sample Date: 05/22/20 Sample Time: 0907  
 Sampled By: Jacob Epps  
 Weather Conditions: Cloudy, windy  
 Accumulative Yards: 4/4 Batch Size (cy): 4  
 Placement Method: Direct Discharge  
 Water Added Before (gal): 0  
 Water Added After (gal): 0  
 Sample Location: Bottom 1/3 of guard rail wall  
 Placement Location: Merritt Parkway guard rail wall, anchor, and terminal curb sections

**Field Test Data**

Test	Result	Specification
Slump (in):	3 3/4	Not Specified
Air Content (%):	1.5	Not Specified
Concrete Temp. (F):	88	40 - 95
Ambient Temp. (F):	84	40 - 95
Plastic Unit Wt. (pcf):	148.4	Not Specified
Yield (Cu. Yds.):		

**Laboratory Test Data**

Set No.	Specimen ID	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Maximum Load (lbs)	Compressive Strength (psi)	Fracture Type	Tested By
1	A	6.00	28.27	05/26/20	07/07/20	46 F	149,250	5,280	2	SLS
1	B	6.00	28.27	05/26/20	07/07/20	46 F	161,690	5,720	6	SLS
1	C	6.00	28.27	05/26/20	07/07/20	46 F	161,650	5,720	2	SLS
1	D			05/26/20		Hold				

Initial Cure: Outside

Final Cure: Field Cured

Comments: F = Field Cured

**Samples Made By: Terracon**

Services: Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

Terracon Rep.: Jacob Epps

Start/Stop: 0800-1030

Reported To:

Contractor:

Report Distribution:


(1) Texas Transportation Institute, Gary Gerke (1) Terracon Consultants, Inc., Alex Dunigan, P.E.  
 (1) Texas Transportation Institute, Bill Griffith

Reviewed By:

  
 Alexander Dunigan  
 Project Manager

Test Methods: ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

 <b>Texas A&amp;M Transportation Institute</b> <small>Proving Ground 3100 SH-47, Bldg 7091 Bryan, TX 77807</small>	<b>QF-7.3-01-Concrete Sampling</b>	Doc. No. <b>QF-7.3-01</b>	Issue Date: <b>2018-06-18</b>
		<b>Quality Form</b> Prepared by: Wanda L. Menges Approved by: Darrell L. Kuhn	Revision: <b>6</b>

The information contained in this document is confidential to TTI Proving Ground.

**Project No:** 612061    **Casting Date:** 6/11/2020    **Mix Design (psi):** 4000 psi

Name of Technician Taking Sample	<u>Teracon</u>	Name of Technician Breaking Sample	<u>Teracon</u>
Signature of Technician Taking Sample	<u>Teracon</u>	Signature of Technician Breaking Sample	<u>Teracon</u>

Load No.	Truck No.	Ticket No.	Location (from concrete map)
T1	9019	6113686	100% of curb

Load No.	Break Date	Cylinder Age	Total Load (lbs)	Break (psi)	Average
See attached Reports from Terracon					

CUSTOMER'S COPY


TICKET NO.



# Martin Marietta

1503 LBJ Freeway  
Suite 400  
Dallas, Tx 75234

6113686



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
10:57	11:04	11:27	11:30	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST \_\_\_\_\_ GAL.  
 ALLOWABLE WATER (withheld from batch) \_\_\_\_\_ GAL.  
 TEST CYLINDER TAKEN  YES  NO BY \_\_\_\_\_  
 CYLINDER TAKEN  BEFORE  AFTER WATER

CUSTOMER SIGNATURE

X

DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED SIGNATURE ABOVE.

**ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.**

CUSTOMER NAME AND DELIVERY ADDRESS

BRYAN CONSTRUCTION C  
RELLIS CAMPUS/TTI, CO

PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
617	9019	2021	5.0	302-10-13	
DRIVER NAME		DATE			
WATTS, RODNEY		6/11/20			
CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY		
503195	92332	7.00	7.00		

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
7.00	CYDS	R9Z40625	COM, RG, Z, 4000, RE	

SPECIAL DELIVERY INSTRUCTIONS

SOUTH 2818, RIGHT LEONARD RD, RIGHT ON HWY 47, LEFT INTO RELLISCAMPUS, GO STRAIGHT TO THE GATE THEY WILL MEET YOU THERE

SALES TAX

TOTAL

**DANGER!** MAY CAUSE ALKALI BURNS. SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY FORM:

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
9019	726255	user	6113686	83705		10:57	6/11/20
Load Size	Mix Code	Returned	Qty	Mix	Age	Seq	Load ID
7.00	CYDS	R9Z40625				D	84795
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
1"RS	1303 lb	9158 lb	9160 lb	0.03%	0.40% H	4 gl	
16"PS	506 lb	3550 lb	3580 lb	0.62%	0.45% H	2 gl	
NO-1	1403 lb	10230 lb	10220 lb	-0.10%	4.00% H	49 gl	
P-1/11	394 lb	2758 lb	2730 lb	-1.02%			
CYRSH-C	131 lb	917 lb	925 lb	+ 0.07%			
H2O	250 lb	1189 lb	1184 lb	-0.41%		142 gl	
ZY-618	16 oz	165 oz	165 oz	-0.29%			

Actual Num Batches: 1  
 Load Total: 27009 lb Design 0.476 Water/Cement 0.479 T Design 209.7 gl Actual 197.2 gl To Add: 12.5  
 Slump: 5.00 in @ Water in Trucks: 0.0 gl Adjust Water: 0.0 gl / Load Trip Water: -1.7 gl / CYD



**CONCRETE COMPRESSIVE STRENGTH TEST REPORT**

**Report Number:** A1171057.0120  
**Service Date:** 06/11/20  
**Report Date:** 06/11/20  
**Task:** PO #612061



6198 Imperial Loop  
College Station, TX 77845-5765  
979-846-3767 Reg No: F-3272

**Client**

Texas Transportation Institute  
Attn: Gary Gerke  
TTI Business Office  
3135 TAMU  
College Station, TX 77843-3135

**Project**

Riverside Campus  
Riverside Campus  
Bryan, TX  
  
Project Number: A1171057

**Material Information**

**Specified Strength:** 4,000 psi @ 28 days  
  
**Mix ID:**  
**Supplier:** Martin Marietta Conc  
**Batch Time:** 1057 **Plant:**  
**Truck No.:** 9019 **Ticket No.:** 6113686

**Sample Information**

**Sample Date:** 06/11/20 **Sample Time:** 1200  
**Sampled By:** Randolph E. Rohrbach  
**Weather Conditions:** Clear, light wind  
**Accumulative Yards:** 7/7 **Batch Size (cy):** 7  
**Placement Method:** Direct Discharge  
**Water Added Before (gal):** 0  
**Water Added After (gal):** 0  
**Sample Location:** Center section  
**Placement Location:** Barricade curb

**Field Test Data**

Test	Result	Specification
Slump (in):	2 1/2	
Air Content (%):		
Concrete Temp. (F):	89	
Ambient Temp. (F):	87	
Plastic Unit Wt. (pcf):		
Yield (Cu. Yds.):		

**Laboratory Test Data**

Set No.	Specimen ID	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Maximum Load (lbs)	Compressive Strength (psi)	Fracture Type	Tested By
1	A	6.00	28.27	07/07/20	07/07/20	26 F	129,670	4,590	1	SLS
1	B	6.00	28.27	07/07/20	07/07/20	26 F	134,650	4,760	2	SLS
1	C	6.00	28.27	07/07/20	07/07/20	26 F	123,560	4,370	2	SLS
1	D			07/07/20		Hold				

**Initial Cure:** Outside **Final Cure:** Field Cured

**Comments:** Not tested for plastic unit weight. F = Field Cured

**Samples Made By: Terracon**

**Services:** Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

**Terracon Rep.:** Randolph E. Rohrbach

**Start/Stop:** 1130-1315

**Reported To:**

**Contractor:**

**Report Distribution:**

- (1) Texas Transportation Institute, Gary Gerke
- (1) Terracon Consultants, Inc., Alex Dunigan, P.E.
- (1) Texas Transportation Institute, Bill Griffith

**Reviewed By:**

Alexander Dunigan  
Project Manager

**Test Methods:** ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.





# Martin Marietta

1503 LBJ Freeway  
Suite 400  
Dallas, Tx 75234

TICKET NO. 6179946



LOAD TIME	TO JOB	ARRIVE JOB SITE	BEGIN POUR	FINISH POUR	LEAVE JOB SITE	ARRIVE PLANT
10:29	10:43	11:03	11:09	:	:	:

WATER ADDED ON JOB AT CUSTOMER'S REQUEST  GAL. \_\_\_\_\_  
 ALLOWABLE WATER (withheld from batch) \_\_\_\_\_ GAL. \_\_\_\_\_  
 TEST CYLINDER TAKEN  YES  NO BY \_\_\_\_\_  
 CYLINDER TAKEN  BEFORE  AFTER WATER

CUSTOMER SIGNATURE \_\_\_\_\_  
 DELIVERY OF THESE MATERIALS IS SUBJECT TO THE TERMS AND CONDITIONS ON THE REVERSE SIDE HEREOF AS ACCEPTED BY SIGNATURE ABOVE.

**ADDITIONAL WATER ADDED TO THIS CONCRETE WILL REDUCE ITS STRENGTH. ANY WATER ADDED IN EXCESS OF SPECIFIED SLUMP IS AT CUSTOMER'S RISK.**

CUSTOMER NAME AND DELIVERY ADDRESS  
 BRYAN CONSTRUCTION C  
 RELIS CAMPUS/TTI, CO

PLANT	TRUCK	ORDER NO.	SLUMP	P.O. #/JOB/LOT	GRID
617	7211	2029	5.0	302-10-13	
DRIVER NAME		DATE			
LARRY JANTZEN		7/21/20			
CUSTOMER NUMBER	PROJECT	CUM. QTY	ORDERED QTY		
503195	92332	6.50	6.50		

LOAD QUANTITY	PRODUCT CODE	DESCRIPTION	UNIT PRICE	AMOUNT
6.50	CYDS	R9840636 COM, RG, 6, 4000, RE		

SPECIAL DELIVERY INSTRUCTIONS  
 SOUTH 2818, RIGHT LEONARD RD, RIGHT ON HWY 47, LEFT INTO RELIS CAMPUS, GO STRAIGHT TO THE GATE THEY WILL MEET YOU THERE

SALES TAX  
 TOTAL

**DANGER!** MAY CAUSE ALKALI BURNS.  
 SEE WARNINGS ON REVERSE SIDE.

FOR OFFICE USE ONLY **FORM:**

Truck	Driver	User	Disp	Ticket Num	Ticket ID	Time	Date
7211	777135	user	6179946	84875	10:29	7/21/20	
Load Size	Mix Code	Returned	Qty	Mix Age	Seq	Load ID	
6.50	CYDS R9840636				D	85976	
Material	Design Qty	Required	Batched	% Var	% Moisture	Actual Wat	
3/8" DG	1575 lb	18268 lb	18320 lb	0.50%	0.30% N	4 g/l	
SAND-1	1565 lb	18541 lb	18560 lb	0.57%	3.50% N	14 g/l	
ONT-1/11	435 lb	2828 lb	2820 lb	-0.27%			
FLYASH-C	145 lb	943 lb	940 lb	-0.27%		140 g/l	
H2O	267 lb	1254 lb	1246 lb	-0.67%			
ZY-610	17 oz	170 oz	170 oz	0.21%			
Actual	Num Batches: 1	Design 0.460	Water/Cement 0.462	T	Design 206.0 gl	Actual 197.4 gl	To Add: 10.6 gl
Load Total: 25917 lb							Note: Manual feed oc
Slump: 5.00 in		Water in Truck: 0.0 gl	Adjust Water: 0.0 gl	/ Load	Trim Water: -1.5 gl	CVD	



**CONCRETE COMPRESSIVE STRENGTH TEST REPORT**

**Report Number:** A1171057.0121  
**Service Date:** 07/21/20  
**Report Date:** 07/21/20  
**Task:** PO #612061

**Terracon**  
6198 Imperial Loop  
College Station, TX 77845-5765  
979-846-3767 Reg No: F-3272

**Client**

Texas Transportation Institute  
Attn: Gary Gerke  
TTI Business Office  
3135 TAMU  
College Station, TX 77843-3135

**Project**

Riverside Campus  
Riverside Campus  
Bryan, TX

Project Number: A1171057

**Material Information**

**Specified Strength:** 4,000 psi @ 28 days  
**Mix ID:** R98440636  
**Supplier:** Martin Marietta  
**Batch Time:** 1029 **Plant:** 617  
**Truck No.:** 7211 **Ticket No.:** 6179946

**Sample Information**

**Sample Date:** 07/21/20 **Sample Time:** 1137  
**Sampled By:** Adam Hill  
**Weather Conditions:** cloudy, low wind  
**Accumulative Yards:** 6.5/6.5 **Batch Size (cy):** 6.5  
**Placement Method:** Direct Discharge  
**Water Added Before (gal):** 0  
**Water Added After (gal):** 0  
**Sample Location:** Direct middle of 10 yd length  
**Placement Location:** PO #612061, Main runway, SW end, curb/box

**Field Test Data**

Test	Result	Specification
Slump (in):	5 1/4	Not Specified
Air Content (%):	1.6	Not Specified
Concrete Temp. (F):	92	40 - 95
Ambient Temp. (F):	85	40 - 95
Plastic Unit Wt. (pcf):	142.9	Not Specified
Yield (Cu. Yds.):		

**Laboratory Test Data**

Set No.	Specimen ID	Avg Diam. (in)	Area (sq in)	Date Received	Date Tested	Age at Test (days)	Maximum Load (lbs)	Compressive Strength (psi)	Fracture Type	Tested By
1	A	6.00	28.27	07/22/20	09/02/20	43	148,100	5,240		SLS
1	B	6.00	28.27	07/22/20	09/02/20	43	146,820	5,190		SLS
1	C	6.00	28.27	07/22/20	09/02/20	43	145,110	5,130		SLS
							<b>Average (43 days)</b>	<b>5,190</b>		
1	D			07/22/20		Hold				

**Initial Cure:** Outside

**Final Cure:** Field Cured

**Comments:** Average compressive strength of 43 day cylinders complies with the specified strength.

**Samples Made By: Terracon**

**Services:** Obtain samples of fresh concrete at the placement locations (ASTM C 172), perform required field tests and cast, cure, and test compressive strength samples (ASTM C 31, C 39, C 1231).

**Terracon Rep.:** Adam Hill

**Reported To:** Gary Gerke

**Contractor:**

**Report Distribution:**

(1) Texas Transportation Institute, Gary Gerke  
(1) Texas Transportation Institute, Bill Griffith

(1) Terracon Consultants, Inc., Alex Dunigan, P.E.

**Start/Stop:** 1000-1200

**Reviewed By:**

  
Alexander Dunigan  
Project Manager

**Test Methods:** ASTM C 31, ASTM C143, ASTM C231, ASTM C1064

The tests were performed in general accordance with applicable ASTM, AASHTO, or DOT test methods. This report is exclusively for the use of the client indicated above and shall not be reproduced except in full without the written consent of our company. Test results transmitted herein are only applicable to the actual samples tested at the location(s) referenced and are not necessarily indicative of the properties of other apparently similar or identical materials.

*This page intentionally left blank.*

**APPENDIX C. MODIFIED MERRITT PARKWAY GUIDERAIL WITH NO CURB**

### Notes

**1a.** Drill Ø24" holes for Posts. Backfill Post holes and around Anchor Block with AASHTO M147-65(2004), grade B crushed limestone road base, compacted to MASH standard.

**1b.** Threads not shown on Bolts, Nuts, etc for clarity.

**1c. Material:**

**Steel:** All steel posts, back-up rails, splice plates and channel rubrails which are to be used as "Weathering Steel", shall meet the requirements of ASTM A588. The fabricator shall notify the manufacturer that it is "Weathering Steel" (structural steel for use in bare, unpainted applications) and that the steel shall not be marked with paint or steel die stamped, but identification shall be stenciled with permanent ink. The dimensions of each component shall conform to the plans and ASTM A6. All steel posts shall be galvanized after fabrication to meet the requirements of ASTM A123 and conform to the galvanizing limits and tolerances shown on the plans. A single ¾" diameter hole may be drilled 2" from the top of each post, in the center of the web, to facilitate the galvanizing process on the bottom of all posts.


**Timber:** All timber rail and block-out components shall conform with the following:

- a) Commercial lumber grade No. 1 or better after treatment;
- b) AASHTO M 168;
- c) Minimum stress rating of 1350 psi
- d) Rough sawn (non-planed) or S4S (surface four side) Southern Yellow Pine or Douglas Fir- Larch with nominal dimensions as indicated on the plans. Variations in the size of any dimension shall not be more than ± ¼"
- e) All timber components shall be pressure treated with CCA or ACZA depending on species supplied conforming to AWWA Standard P5 to a minimum net retention of 0.60lb/cubic foot in the assay zone in accordance with AWWA Standard C14.
- f) All timber components shall be fabricated (including but not necessarily limited to cutting, drilling, dapping and chamfering) prior to treatment.
- g) All timber components shall be free of excess preservative and solvent at the conclusion of the treating process. Post treatment cleaning shall be by expansion bath or steaming in accordance with AWWA Standard C2;
- h) Kiln or air dried to a maximum moisture content of 25% after treatment (KDAT - 25);
- i) Grade-marked after treatment by an agency certified by the American Lumber Standard Committee (ALSC).


**Fasteners:**

- a) Round head bolts shall be manufactured in accordance with the sizes designated on the plans, the geometric specifications included in ANSI B18.5.1.2.2 and the material specifications for ASTM A588 steel. All round head bolts shall be marked with the manufacturers symbol and A588.
- b) Hex Lag Screws shall be manufactured in accordance with ASTM A307 Grade A specifications. All Hex Lag Screws shall be hot-dipped galvanized in accordance with ASTM A153 Class C.
- c) Nuts, and Washers shall be ASTM A588 steel.

	Roadside Safety and Physical Security Division - Proving Ground	
	Project #612061-02-1 and -03-1 Merritt Parkway	2020-07-16
Drawn by GESIWS Scale 1:250	Sheet 1 of 12 Notes	




Q:\Accreditation-17025-2017\EIR-000 Project Files\612061-Pooled Fund-Merritt Parkway-Chiara Drafting, 612061 with curb\612061 w curb Drawing



Roadside Safety and Physical Security Division - Proving Ground

Project #612061-02-1 and -03-1	Merritt Parkway	2020-07-16
Drawn by GESWS	Scale 1:50	Sheet 3 of 12 Transition Details

### Curb Sections






Roadside Safety and Physical Security Division - Proving Ground



Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-16
Drawn by GESWS	Scale 1:10	Sheet 4 of 12 Curb Sections	



### Anchor Details



**Anchor Bracket**  
WT 15 x 86.5  
Galvanize after all  
fabrication is complete.  
Scale 1:10




Roadside Safety and  
Physical Security Division -  
Proving Ground



Project #612061-02-1 and -03-1	Merritt Parkway	2020-07-16
Drawn by GESWS	Scale 1:50	Sheet 5 of 12 Anchor Details

# Anchor Block


B7 Threaded Rod,  $\text{Ø} 1 \frac{1}{4} \times 18$ " (x 4)




## Elevation Views



U-bar, bottom  
Grade 60 rebar



U-bar, middle  
Grade 60 rebar




U-bar, top  
Grade 60 rebar



Roadside Safety and  
Physical Security Division -  
Proving Ground


Project #612061-02-1 and -03-1 Merritt Parkway 2020-07-16

Drawn by GESWS Scale 1:20 Sheet 6 of 12 Anchor Block




Roadside Safety and  
Physical Security Division -  
Proving Ground

Project #612061-02-1 and -03-1 Merritt Parkway		2020-07-16
Drawn by GESWS	Scale 1:20	Sheet 7 of 12 Post and Rail Assemblies




Roadside Safety and  
Physical Security Division -  
Proving Ground

Project #612061-02-1 and -03-1 Merritt Parkway		2020-07-16
Drawn by GESWS	Scale 1:20	Sheet 8 of 12 Rail Parts




Roadside Safety and Physical Security Division - Proving Ground

Project #612061-02-1 and -03-1 Merritt Parkway		2020-07-16
Drawn by GESWS	Scale 1:20	Sheet 9 of 12 Transition Rails




Roadside Safety and  
Physical Security Division -  
Proving Ground

Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-16
Drawn by GESWS	Scale 1:20	Sheet 10 of 12 Backup Plates	









**Table C.1. Summary of Strong Soil Test Results for Establishing Installation Procedure.**





Percent Finer Vs. Grain Size of Fill Soil for Dynamic and Static Load Tests



**Dynamic Test Installation Details**




**Static Load Test Installation Details**




Date .....	2008-11-05
Test Facility and Site Location .....	TTI Proving Ground, 3100 SH 47, Bryan, TX 77807
In Situ Soil Description (ASTM D2487) .....	Sandy gravel with silty fines
Fill Material Description (ASTM D2487) and sieve analysis .....	AASHTO M147 Grade B Soil-Aggregate (see sieve analysis above)
Description of Fill Placement Procedure .....	6-inch lifts tamped with a pneumatic compactor
Bogie Weight .....	5009 lb
Impact Velocity .....	20.5 mph

**Table C.2. Test Day Static Soil Strength Documentation for Test No. 612061-03-1.**



Date.....	<u>2020-10-02 for Test No. 612061-03-1</u>
Test Facility and Site Location .....	<u>TTI Proving Ground – 3100 SH 47, Bryan, Tx</u>
In Situ Soil Description (ASTM D2487).....	<u>Sandy gravel with silty fines</u>
Fill Material Description (ASTM D2487) and sieve analysis ..	<u>AASHTO M147 Grade B Soil-Aggregate</u>
Description of Fill Placement Procedure.....	<u>6-inch lifts tamped with a pneumatic compactor</u>

**Table C.3. Test Day Static Soil Strength Documentation for Test No. 612061-02-1A.**



Date.....	<u>2020-09-02 for Test No. 612061-02-1A</u>
Test Facility and Site Location .....	<u>TTI Proving Ground – 3100 SH 47, Bryan, Tx</u>
In Situ Soil Description (ASTM D2487).....	<u>Sandy gravel with silty fines</u>
Fill Material Description (ASTM D2487) and sieve analysis ..	<u>AASHTO M147 Grade B Soil-Aggregate</u>
Description of Fill Placement Procedure.....	<u>6-inch lifts tamped with a pneumatic compactor</u>

**C.3 MASH TEST 3-11 (CRASH TEST NO. 612061-02-1A)**

**C.3.1. Vehicle Properties and Information**

**Table C.1. Vehicle Properties for Test No. 612061-02-1A.**


**Table C.2. Measurements of Vehicle Vertical Center of Gravity for Test No. 612061-02-1A.**

**Table C.3. Exterior Crush Measurements for Test No. 612061-02-1A.**





**Table C.4. Occupant Compartment Measurements for Test No. 612061-02-1A.**

### C.3.2. Sequential Photographs



**Figure C.1. Sequential Photographs for Test No. 612061-02-1A (Overhead and Frontal Views).**



**Figure C.1. Sequential Photographs for Test No. 612061-02-1A (Overhead and Frontal Views) (Continued).**





0.000 s



0.600 s



0.150 s



0.750 s



0.300 s



0.900 s



0.450 s




1.050 s

**Figure C.2. Sequential Photographs for Test No. 612061-02-1A (Rear View).**

Axes are vehicle-fixed.  
Sequence for determining orientation:

1. Yaw.
2. Pitch.
3. Roll.



Test Number: 612061-02-1A
Test Standard Test Number: MASH Test 3-11
Test Article: Merritt Parkway Guiderail
Test Vehicle: 20xx RAM 1500 Pickup
Inertial Mass: xxxx lb
Gross Mass: xxxx lb
Impact Speed: xx.x mi/h
Impact Angle: xx.x°

**Figure C.3. Vehicle Angular Displacements for Test No. 612061-02-1A.**

**C.3.4. Vehicle Accelerations**

**Figure C.4. Vehicle Longitudinal Accelerometer Trace for Test No. 612061-02-1A  
(Accelerometer Located at Center of Gravity).**

**Figure C.5. Vehicle Lateral Accelerometer Trace for Test No. 612061-02-1A  
(Accelerometer Located at Center of Gravity).**



**Figure C.6. Vehicle Vertical Accelerometer Trace for Test No. 612061-02-1A  
(Accelerometer Located at Center of Gravity).**

**C.4. MASH TEST 3-10 (CRASH TEST NO. 612061-03-1)**

**C.4.1. Vehicle Properties and Information**

**Table C.5. Vehicle Properties for Test No. 612061-03-1.**

**Table C.6. Exterior Crush Measurements for Test No. 612061-03-1.**

**Table C.7. Occupant Compartment Measurements for Test No. 612061-03-1.**

### C.4.2. Sequential Photographs



0.000 s



0.050 s



0.100 s



0.150 s



**Figure C.7. Sequential Photographs for Test No. 612061-03-1 (Overhead and Frontal Views).**



0.200 s



0.250 s



0.300 s




0.350 s



**Figure C.7. Sequential Photographs for Test No. 612061-03-1 (Overhead and Frontal Views) (Continued).**

Axes are vehicle-fixed.  
Sequence for determining  
orientation:

1. Yaw.
2. Pitch.
3. Roll.



Test Number: 612061-03-1
Test Standard Test Number: <i>MASH</i> Test 3-10
Test Article: Merritt Parkway Guiderail with No Curb
Test Vehicle: xxxx Nissan Versa
Inertial Mass: xx lb
Gross Mass: xxx lb
Impact Speed: xx.x mi/h
Impact Angle: xx.x°

**Figure C.8. Vehicle Angular Displacements for Test No. 612061-03-1.**



**C.4.4. Vehicle Accelerations**

**Figure C.9. Vehicle Longitudinal Accelerometer Trace for Test No. 612061-03-1  
(Accelerometer Located at Center of Gravity).**

**Figure C.10. Vehicle Lateral Accelerometer Trace for Test No. 612061-03-1  
(Accelerometer Located at Center of Gravity).**

**Figure C.11. Vehicle Vertical Accelerometer Trace for Test No. 612061-03-1  
(Accelerometer Located at Center of Gravity).**

*This page intentionally left blank.*



**APPENDIX D. MERRITT PARKWAY GUIDERAIL TRANSITION**

### Notes

**1a.** Drill Ø24" holes for Posts. Backfill Post holes and around Anchor Block with AASHTO M147-65(2004), grade B crushed limestone road base, compacted to MASH standard.

**1b.** Threads not shown on Bolts, Nuts, etc for clarity.

**1c. Material:**


**Steel:** All steel posts, back-up rails, splice plates and channel rubrails which are to be used as "Weathering Steel", shall meet the requirements of ASTM A588. The fabricator shall notify the manufacturer that it is "Weathering Steel" (structural steel for use in bare, unpainted applications) and that the steel shall not be marked with paint or steel die stamped, but identification shall be stenciled with permanent ink. The dimensions of each component shall conform to the plans and ASTM A6. All steel posts shall be galvanized after fabrication to meet the requirements of ASTM A123 and conform to the galvanizing limits and tolerances shown on the plans. A single ¾" diameter hole may be drilled 2" from the top of each post, in the center of the web, to facilitate the galvanizing process on the bottom of all posts.

**Timber:** All timber rail and block-out components shall conform with the following:


- a) Commercial lumber grade No. 1 or better after treatment;
- b) AASHTO M 168;
- c) Minimum stress rating of 1350 psi
- d) Rough sawn (non-planed) or S4S (surface four side) Southern Yellow Pine or Douglas Fir- Larch with nominal dimensions as indicated on the plans. Variations in the size of any dimension shall not be more than ± ¼"
- e) All timber components shall be pressure treated with CCA or ACZA depending on species supplied conforming to AWPA Standard P5 to a minimum net retention of 0.60lb/cubic foot in the assay zone in accordance with AWPA Standard C14.
- f) All timber components shall be fabricated (including but not necessarily limited to cutting, drilling, dapping and chamfering) prior to treatment.
- g) All timber components shall be free of excess preservative and solvent at the conclusion of the treating process. Post treatment cleaning shall be by expansion bath or steaming in accordance with AWPA Standard C2;
- h) Kiln or air dried to a maximum moisture content of 25% after treatment (KDAT - 25);
- i) Grade-marked after treatment by an agency certified by the American Lumber Standard Committee (ALSC).

**Fasteners:**


- a) Round head bolts shall be manufactured in accordance with the sizes designated on the plans, the geometric specifications included in ANSI B18.5.1.2.2 and the material specifications for ASTM A588 steel. All round head bolts shall be marked with the manufacturers symbol and A588.
- b) Hex Lag Screws shall be manufactured in accordance with ASTM A307 Grade A specifications. All Hex Lag Screws shall be hot-dipped galvanized in accordance with ASTM A153 Class C.
- c) Nuts, and Washers shall be ASTM A588 steel.

		Roadside Safety and Physical Security Division - Proving Ground	
Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-16
Drawn by GESIWS	Scale 1:250	Sheet 1 of 12 Notes	






Q:\Accreditation-17025-2017\EIR-000 Project Files\612061-Pooled Fund-Merritt Parkway-Chiara Drafting, 612061 with curb\612061 w curb Drawing



Roadside Safety and Physical Security Division - Proving Ground

Project #612061-02-1 and -03-1	Merritt Parkway	2020-07-16
Drawn by GESWS	Scale 1:50	Sheet 3 of 12 Transition Details


### Curb Sections





Roadside Safety and Physical Security Division - Proving Ground

Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-16
Drawn by GESWS	Scale 1:10	Sheet 4 of 12 Curb Sections	


Q:\Accreditation-17025-2017\EIR-000 Project Files\612061-000-Pooled Fund-Merritt Parkway-Chiara Drafting, 612061 with curb\612061 w curb Drawing




# Anchor Block



U-bar, bottom  
Grade 60 rebar




U-bar, middle  
Grade 60 rebar




U-bar, top  
Grade 60 rebar

	Roadside Safety and Physical Security Division - Proving Ground		
	Project #612061-02-1 and -03-1	Merritt Parkway	2020-07-16
Drawn by GESWS	Scale 1:20	Sheet 6 of 12 Anchor Block	



Roadside Safety and Physical Security Division - Proving Ground

Project #612061-02-1 and -03-1 Merritt Parkway		2020-07-16
Drawn by GESWS	Scale 1:20	Sheet 7 of 12 Post and Rail Assemblies



Roadside Safety and  
Physical Security Division -  
Proving Ground

Project #612061-02-1 and -03-1 Merritt Parkway




2020-07-16

Drawn by GESWS

Scale 1:20


Sheet 8 of 12 Rail Parts






Roadside Safety and Physical Security Division - Proving Ground


Project #612061-02-1 and -03-1 Merritt Parkway		2020-07-16
Drawn by GESWS	Scale 1:20	Sheet 9 of 12 Transition Rails



Roadside Safety and  
Physical Security Division -  
Proving Ground

Project #612061-02-1 and -03-1		Merritt Parkway	2020-07-16
Drawn by GESWS	Scale 1:20	Sheet 10 of 12 Backup Plates	






Roadside Safety and Physical Security Division - Proving Ground

Project #612061-02-1 and -03-1 Merritt Parkway		2020-07-16
Drawn by GESWS	Scale 1:5	Sheet 12 of 12 Rebar


**Table D.1. Summary of Strong Soil Test Results for Establishing Installation Procedure.**





Percent Finer Vs. Grain Size of Fill Soil for Dynamic and Static Load Tests



**Dynamic Test Installation Details**




**Static Load Test Installation Details**




Date .....	2008-11-05
Test Facility and Site Location .....	TTI Proving Ground, 3100 SH 47, Bryan, TX 77807
In Situ Soil Description (ASTM D2487) .....	Sandy gravel with silty fines
Fill Material Description (ASTM D2487) and sieve analysis .....	AASHTO M147 Grade B Soil-Aggregate (see sieve analysis above)
Description of Fill Placement Procedure .....	6-inch lifts tamped with a pneumatic compactor
Bogie Weight .....	5009 lb
Impact Velocity .....	20.5 mph

**Table D.2. Test Day Static Soil Strength Documentation for Test No. 612061-07-1.**



Date.....	<u>2020-10-07 for Test No. 612061-07-1</u>
Test Facility and Site Location .....	<u>TTI Proving Ground – 3100 SH 47, Bryan, Tx</u>
In Situ Soil Description (ASTM D2487).....	<u>Sandy gravel with silty fines</u>
Fill Material Description (ASTM D2487) and sieve analysis ..	<u>AASHTO M147 Grade B Soil-Aggregate</u>
Description of Fill Placement Procedure.....	<u>6-inch lifts tamped with a pneumatic compactor</u>

**Table D.3. Test Day Static Soil Strength Documentation for Test No. 612061-06-1.**



Date.....	<u>2020-10-12 for Test No. 612061-06-1</u>
Test Facility and Site Location .....	<u>TTI Proving Ground – 3100 SH 47, Bryan, Tx</u>
In Situ Soil Description (ASTM D2487).....	<u>Sandy gravel with silty fines</u>
Fill Material Description (ASTM D2487) and sieve analysis ..	<u>AASHTO M147 Grade B Soil-Aggregate</u>
Description of Fill Placement Procedure.....	<u>6-inch lifts tamped with a pneumatic compactor</u>



### D.3 MASH TEST 3-20 (CRASH TEST NO. 612061-07-1)

#### D.3.1. Vehicle Properties and Information

**Table D.1. Vehicle Properties for Test No. 612061-07-1.**

Date: 2020-10-07 Test No.: 612061 VIN No.: 3N1CN7AP6EK451617

Year: 2014 Make: NISSAN Model: VERSA

Tire Inflation Pressure: 36 PSI Odometer: 90082 Tire Size: P185/65R15

Describe any damage to the vehicle prior to test: None

• Denotes accelerometer location.

NOTES: None

Engine Type: 4 CYL

Engine CID: 1.6 L

Transmission Type:

Auto or  Manual  
 FWD  RWD  4WD

Optional Equipment:



None

Dummy Data:

Type: 50th Percentile Male

Mass: 165 lb

Seat Position: IMPACT SIDE



**Geometry:** inches

A <u>66.70</u>	F <u>32.50</u>	K <u>12.50</u>	P <u>4.50</u>	U <u>15.50</u>
B <u>59.60</u>	G _____	L <u>26.00</u>	Q <u>24.00</u>	V <u>21.25</u>
C <u>175.40</u>	H <u>41.51</u>	M <u>58.30</u>	R <u>16.25</u>	W <u>41.50</u>
D <u>40.50</u>	I <u>7.00</u>	N <u>58.50</u>	S <u>7.50</u>	X <u>79.75</u>
E <u>102.40</u>	J <u>22.25</u>	O <u>30.50</u>	T <u>64.50</u>	
Wheel Center Ht Front <u>11.50</u>	Wheel Center Ht Rear <u>11.50</u>	W-H <u>-0.01</u>		

RANGE LIMIT: A = 65 ±3 inches; C = 169 ±8 inches; E = 98 ±5 inches; F = 35 ±4 inches; H = 39 ±4 inches; O (Top of Radiator Support) = 28 ±4 inches  
 (M+N)/2 = 59 ±2 inches; W-H < 2 inches or use MASH Paragraph A4.3.2

<b>GVWR Ratings:</b>	<b>Mass: lb</b>	<b>Curb</b>	<b>Test Inertial</b>	<b>Gross Static</b>
Front <u>1750</u>	M <sub>front</sub> <u>1442</u>	<u>1442</u>	<u>1439</u>	<u>1524</u>
Back <u>1687</u>	M <sub>rear</sub> <u>972</u>	<u>972</u>	<u>981</u>	<u>1061</u>
Total <u>3389</u>	M <sub>Total</sub> <u>2414</u>	<u>2414</u>	<u>2420</u>	<u>2585</u>

Allowable TIM = 2420 lb ±55 lb | Allowable GSM = 2585 lb ± 55 lb

**Mass Distribution:**

lb LF: 731 RF: 708 LR: 495 RR: 486

**Table D.2. Exterior Crush Measurements for Test No. 612061-07-1.**

Date: 2020-10-7 Test No.: 612061 VIN No.: 3N1CN7AP6EK451617  
 Year: 2014 Make: NISSAN Model: VERSA

**VEHICLE CRUSH MEASUREMENT SHEET<sup>1</sup>**

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____	Bowing: B1 _____ X1 _____
Corner shift: A1 _____	B2 _____ X2 _____
A2 _____	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} =$ _____
< 4 inches _____	
≥ 4 inches _____	

Note: Measure C<sub>1</sub> to C<sub>6</sub> from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L***	C <sub>1</sub>	C <sub>2</sub>	C <sub>3</sub>	C <sub>4</sub>	C <sub>5</sub>	C <sub>6</sub>	±D
		Width** (CDC)	Max**** Crush								
1	Front plane at bmp ht	11	11	18	-	-	-	-	-	-	14
2	Side plane at bmp ht	11	12	43	-	-	-	-	-	-	62
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

<sup>1</sup>Table taken from National Accident Sampling System (NASS).

\*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




\*\*Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

\*\*\*Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

**Table D.3. Occupant Compartment Measurements for Test No. 612061-07-1.**

Date: 2020-10-7 Test No.: 612061 VIN No.: 3N1CN7AP6EK451617  
 Year: 2014 Make: NISSAN Model: VERSA




\*Lateral area across the cab from driver's side kick panel to passenger's side kick panel.

**OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT**

	Before	After (inches)	Differ.
A1	75.00	75.00	0.00
A2	74.00	74.00	0.00
A3	74.00	73.00	-1.00
B1	43.00	43.00	0.00
B2	37.00	37.00	0.00
B3	43.00	44.50	1.50
B4	46.50	46.50	0.00
B5	42.50	42.50	0.00
B6	46.50	46.50	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	26.00	0.00
D1	12.50	12.50	0.00
D2	0.00	0.00	0.00
D3	10.00	13.00	3.00
E1	45.00	45.00	0.00
E2	48.75	55.75	7.00
F	47.50	42.00	-5.50
G	47.50	47.50	0.00
H	39.00	39.00	0.00
I	39.00	37.00	0.00
J*	48.50	41.25	-7.25

### D.3.2. Sequential Photographs



**Figure D.1. Sequential Photographs for Test No. 612061-07-1 (Overhead and Frontal Views).**





0.400 s



0.500 s



0.600 s



0.700 s



**Figure D.1. Sequential Photographs for Test No. 612061-07-1 (Overhead and Frontal Views) (Continued).**





0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s




0.200 s




0.700 s

**Figure D.2. Sequential Photographs for Test No. 612061-07-1 (Rear View).**



Axes are vehicle-fixed.  
Sequence for determining orientation:


1. Yaw.
2. Pitch.
3. Roll.




Test Number: 612061-07-1  
 Test Standard Test Number: *MASH* Test 3-20  
 Test Article: Merritt Parkway Guiderail Transition  
 Test Vehicle: 2014 Nissan Versa  
 Inertial Mass: 2420 lb  
 Gross Mass: 2585 lb  
 Impact Speed: 62.5 mi/h  
 Impact Angle: 25.6°

Figure D.3. Vehicle Angular Displacements for Test No. 612061-07-1.






**Figure D4. Vehicle Longitudinal Accelerometer Trace for Test No. 612061-07-1 (Accelerometer Located at Center of Gravity).**



Test Number: 612061-07-1  
Test Standard Test Number: *MASH* Test 3-20  
Test Article: Merritt Parkway Guiderail Transition  
Test Vehicle: 2014 Nissan Versa  
Inertial Mass: 2420 lb  
Gross Mass: 2585 lb  
Impact Speed: 62.5 mi/h  
Impact Angle: 25.6°

**Figure D.5. Vehicle Lateral Accelerometer Trace for Test No. 612061-07-1  
(Accelerometer Located at Center of Gravity).**

### Z Acceleration at CG



— SAE Class 60 Filter    — 50-msec average

Test Number: 612061-07-1  
Test Standard Test Number: *MASH* Test 3-20  
Test Article: Merritt Parkway Guiderail Transition  
Test Vehicle: 2014 Nissan Versa  
Inertial Mass: 2420 lb  
Gross Mass: 2585 lb  
Impact Speed: 62.5 mi/h  
Impact Angle: 25.6°

**Figure D.6. Vehicle Vertical Accelerometer Trace for Test No. 612061-07-1  
(Accelerometer Located at Center of Gravity).**

## D.4 MASH TEST 3-21 (CRASH TEST NO. 612061-06-1)

### D.4.1. Vehicle Properties and Information

**Table D.6. Vehicle Properties for Test No. 612061-06-1.**

Date: 2020-10-12 Test No.: 612061-06-1 VIN No.: 1C6RR6GT7ES211036  
 Year: 2014 Make: RAM Model: 1500  
 Tire Size: 265/70 R 17 Tire Inflation Pressure: 35 psi  
 Tread Type: Highway Odometer: 130367  
 Note any damage to the vehicle prior to test: None

- Denotes accelerometer location.


NOTES: None

Engine Type: V-8  
 Engine CID: 5.7 L

Transmission Type:  
 Auto or  Manual  
 FWD  RWD  4WD

Optional Equipment:  
None

Dummy Data:  
 Type: 50th Percentile Male  
 Mass: 165 lb  
 Seat Position: IMPACT SIDE



**Geometry:** inches

A	<u>78.50</u>	F	<u>40.00</u>	K	<u>20.00</u>	P	<u>3.00</u>	U	<u>26.75</u>
B	<u>74.00</u>	G	<u>28.00</u>	L	<u>30.00</u>	Q	<u>30.50</u>	V	<u>30.25</u>
C	<u>227.50</u>	H	<u>59.33</u>	M	<u>68.50</u>	R	<u>18.00</u>	W	<u>59.30</u>
D	<u>44.00</u>	I	<u>11.75</u>	N	<u>68.00</u>	S	<u>13.00</u>	X	<u>79.00</u>
E	<u>140.50</u>	J	<u>27.00</u>	O	<u>46.00</u>	T	<u>77.00</u>		
Wheel Center Height Front	<u>14.75</u>	Wheel Well Clearance (Front)	<u>6.00</u>	Bottom Frame Height - Front	<u>12.50</u>				
Wheel Center Height Rear	<u>14.75</u>	Wheel Well Clearance (Rear)	<u>9.25</u>	Bottom Frame Height - Rear	<u>22.50</u>				

RANGE LIMIT: A=78 ±2 inches; C=237 ±13 inches; E=148 ±12 inches; F=39 ±3 inches; G = > 28 inches; H = 63 ±4 inches; O=43 ±4 inches; (M+N)/2=67 ±1.5 inches

GVWR Ratings:	Mass: lb	Curb	Test Inertial	Gross Static
Front	<u>3700</u>	<u>2977</u>	<u>2892</u>	<u>2977</u>
Back	<u>3900</u>	<u>2099</u>	<u>2114</u>	<u>2194</u>
Total	<u>6700</u>	<u>5076</u>	<u>5006</u>	<u>5171</u>

(Allowable Range for TIM and GSM = 5000 lb ±110 lb)

Mass Distribution:	lb	LF:	RF:	LR:	RR:
		<u>1450</u>	<u>1442</u>	<u>1082</u>	<u>1032</u>

**Table D.7. Measurements of Vehicle Vertical Center of Gravity for Test No. 612061-06-1.**

Date: 2020-10-12 Test No.: 612061-06-1 VIN: 1C6RR6GT7ES211036  
 Year: 2014 Make: RAM Model: 1500  
 Body Style: Quad Cab Mileage: 130367  
 Engine: 5.7 L V-8 Transmission: Automatic  
 Fuel Level: Empty Ballast: 80 (440 lb max)  
 Tire Pressure: Front: 35 psi Rear: 35 psi Size: 265/70 R 17

Measured Vehicle Weights: (lb)					
LF:	<u>1450</u>		RF:	<u>1442</u>	Front Axle: <u>2892</u>
LR:	<u>1082</u>		RR:	<u>1032</u>	Rear Axle: <u>2114</u>
Left:	<u>2532</u>		Right:	<u>2474</u>	Total: <u>5006</u>
					5000 ±110 lb allowed
Wheel Base:	<u>140.50</u>	inches	Track: F:	<u>68.50</u>	inches R: <u>68.00</u> inches
	<u>148 ±12</u>	inches allowed		Track = (F+R)/2 = <u>67 ±1.5</u> inches allowed	
Center of Gravity, SAE J874 Suspension Method					
X:	<u>59.33</u>	inches	Rear of Front Axle	(63 ±4 inches allowed)	
Y:	<u>-0.40</u>	inches	Left - Right +	of Vehicle Centerline	
Z:	<u>28</u>	inches	Above Ground	(minimum 28.0 inches allowed)	

Hood Height: 46.00 inches Front Bumper Height: 27.00 inches  
 43 ±4 inches allowed

Front Overhang: 40.00 inches Rear Bumper Height: 30.00 inches  
 39 ±3 inches allowed

Overall Length: 227.50 inches  
 237 ±13 inches allowed

**Table D.8. Exterior Crush Measurements for Test No. 612061-06-1.**

Date: 2020-10-12 Test No.: 612061-06-1 VIN No.: 1C6RR6GT7ES211036  
 Year: 2014 Make: RAM Model: 1500

**VEHICLE CRUSH MEASUREMENT SHEET<sup>1</sup>**

Complete When Applicable	
End Damage	Side Damage
Undeformed end width _____	Bowing: B1 _____ X1 _____
Corner shift: A1 _____	B2 _____ X2 _____
A2 _____	
End shift at frame (CDC)	Bowing constant
(check one)	$\frac{X1 + X2}{2} =$ _____
< 4 inches _____	
≥ 4 inches _____	

Note: Measure C<sub>1</sub> to C<sub>6</sub> from Driver to Passenger Side in Front or Rear Impacts – Rear to Front in Side Impacts.

Specific Impact Number	Plane* of C-Measurements	Direct Damage		Field L***	C <sub>1</sub>	C <sub>2</sub>	C <sub>3</sub>	C <sub>4</sub>	C <sub>5</sub>	C <sub>6</sub>	±D
		Width*** (CDC)	Max**** Crush								
1	Front plane at bmp ht	18	18	40	-	-	-	-	-	-	12
2	Side plane at bmp ht	18	8	68	-	-	-	-	-	-	79
	Measurements recorded										
	<input checked="" type="checkbox"/> inches or <input type="checkbox"/> mm										

<sup>1</sup>Table taken from National Accident Sampling System (NASS).

\*Identify the plane at which the C-measurements are taken (e.g., at bumper, above bumper, at sill, above sill, at beltline, etc.) or label adjustments (e.g., free space).

Free space value is defined as the distance between the baseline and the original body contour taken at the individual C locations. This may include the following: bumper lead, bumper taper, side protrusion, side taper, etc. Record the value for each C-measurement and maximum crush.




\*\*Measure and document on the vehicle diagram the beginning or end of the direct damage width and field L (e.g., side damage with respect to undamaged axle).

\*\*\*Measure and document on the vehicle diagram the location of the maximum crush.

Note: Use as many lines/columns as necessary to describe each damage profile.

**Table D.9. Occupant Compartment Measurements for Test No. 612061-06-1.**

Date: 2020-10-12 Test No.: 612061-06-1 VIN No.: 1C6RR6GT7ES211036  
 Year: 2014 Make: RAM Model: 1500




\*Lateral area across the cab from driver's side kickpanel to passenger's side kickpanel.

**OCCUPANT COMPARTMENT DEFORMATION MEASUREMENT**

	<b>Before</b>	<b>After (inches)</b>	<b>Differ.</b>
A1	65.00	65.00	0.00
A2	63.00	63.00	0.00
A3	65.50	65.50	0.00
B1	45.00	45.00	0.00
B2	38.00	38.00	0.00
B3	45.00	45.00	0.00
B4	39.50	39.50	0.00
B5	43.00	43.00	0.00
B6	39.50	39.50	0.00
C1	26.00	26.00	0.00
C2	0.00	0.00	0.00
C3	26.00	21.50	-4.50
D1	11.00	11.00	0.00
D2	0.00	0.00	0.00
D3	11.50	10.00	-1.50
E1	61.00	55.50	-5.50
E2	63.50	66.00	2.50
E3	63.50	63.50	0.00
E4	63.50	63.50	0.00
F	59.00	58.50	-0.50
G	59.00	59.00	0.00
H	37.50	37.50	0.00
I	37.50	37.50	0.00
J*	25.00	18.50	-6.50



#### D.4.2. Sequential Photographs REPLACE



**Figure D.7. Sequential Photographs for Test No. 612061-06-1 (Overhead and Frontal Views).**




0.400 s



0.500 s



0.600 s



0.700 s



**Figure D.7. Sequential Photographs for Test No. 612061-06-1 (Overhead and Frontal Views) (Continued).**





0.000 s



0.400 s



0.100 s



0.500 s



0.200 s



0.600 s



0.300 s



0.700 s

**Figure D.8. Sequential Photographs for Test No. 612061-06-1 (Rear View).**








Figure D.9. Vehicle Angular Displacements for Test No. 612061-06-1.



Test Number: 612061-06-1  
Test Standard Test Number: *MASH* Test 3-21  
Test Article: Merritt Parkway Guiderail Transition  
Test Vehicle: 2014 RAM 1500 Pickup  
Inertial Mass: 5006 lb  
Gross Mass: 5171 lb  
Impact Speed: 63.0 mi/h  
Impact Angle: 25.2°


**Figure D.10. Vehicle Longitudinal Accelerometer Trace for Test No. 612061-06-1 (Accelerometer Located at Center of Gravity).**



Test Number: 612061-06-1  
Test Standard Test Number: *MASH* Test 3-21  
Test Article: Merritt Parkway Guiderail Transition  
Test Vehicle: 2014 RAM 1500 Pickup  
Inertial Mass: 5006 lb  
Gross Mass: 5171 lb  
Impact Speed: 63.0 mi/h  
Impact Angle: 25.2°

**Figure D.11. Vehicle Lateral Accelerometer Trace for Test No. 612061-06-1  
(Accelerometer Located at Center of Gravity).**





— SAE Class 60 Filter    — 50-msec average

Test Number: 612061-06-1  
Test Standard Test Number: MASH Test 3-21  
Test Article: Merritt Parkway Guiderail Transition  
Test Vehicle: 2014 RAM 1500 Pickup  
Inertial Mass: 5006 lb  
Gross Mass: 5171 lb  
Impact Speed: 63.0 mi/h  
Impact Angle: 25.2°

**Figure D.12. Vehicle Vertical Accelerometer Trace for Test No. 612061-06-1 (Accelerometer Located at Center of Gravity).**